

FACTSHEET

Date: Friday, May 18, 2018

Project Name: SR 92 Relocation & Widening in Douglasville, GA

Project Number: CSSTP-0006-00(900), CSSTP-0006-00(901), STP00-0186-01(011)
PI Number: 0006900, 0006901, 720970-

Project Location: The project is entirely located within the City of Douglasville in Douglas County, GA.

Proposed Project Description: Project 0006900 is the first of three phases to relocate SR 92 through the City of Douglasville. It includes the grade separation of relocated SR 92 at SR 5/US 78 Bankhead Highway, at Norfolk Southern Corporation railroad, and at Strickland Street. The project includes the closing of at-grade railroad crossings at Brown Street, Mozley Street, and SR 92/Dallas Highway, while relocating the McCarley Street at-grade RR crossing 100' to the west of the existing crossing for a better grade. Project 0006901 is the second of three phases to relocate SR 92 in the City of Douglasville. The project begins at Pine Drive (south of I-20 Interchange at SR 92) and goes north on new location to SR 5/US 78/Bankhead Highway where it will tie to phase one (PI# 0006900). Project 720970- is the third of three phases to relocate SR 92 through the City of Douglasville. The project begins at the intersection of relocated SR 92 and relocated Ellis Street where it connects with Phase 1. It ends just north of the existing intersection of SR 92/Dallas Highway and Malone Road.

Preconstruction Information:

- **Downtown Douglasville:** Phase I (PI#0006900), Project Length: 0.33 miles
 - SR 92 Relocation from Cooper Street to Ellis Street Relocation, Including Bridge Underpass (three bridges at US 78/Bankhead Highway, Norfolk Southern RR, and Strickland Street) & Norfolk Southern Rail Road Crossing Closures – Phase I
- **Douglasville Commercial District:** Phase II (PI#0006901), Project Length: 1.43 miles
 - SR 92 Relocation from south of I-20 (Pine Drive) to Cooper Street Relocation – Phase II
- **Douglasville Residential District:** Phase III (PI#720970-), Project Length: 1.34 miles
 - SR 92 Relocation from Ellis Street Relocation to North of Malone Road

Construction Information: The project is awarded and under construction by CW Matthews Contracting, Inc.

- **Railroad Crossing Closure Information:**
 - **Permanent Closures** to relieve the potential for a train and vehicle crash
 - **Brown Street** – Closed June 2014.
 - **Mozley Street** – Closed January 2014.
 - **Campbellton Street/Dallas Highway** – Will remain opened until the SR 92 Underpass is built and open to traffic. After, the crossing will be closed and obliterated.
 - **Temporary Closure:**
 - **McCarley Street** – Once the SR 92 Underpass is built, this crossing will be relocated to the west of the existing crossing to decrease the existing “hump”.

Project Schedule:

- **Concept Completion Date:** December 2013
- **Final Environmental Document Completion Date:** January 2014
- **Right of Way Acquisition Completion Date:** Winter 2013
- **Let to Construction Date:** April 2014
- **Construction Start Date:** Summer 2014
- **Construction Anticipated Completion Date:** November 2020

Contact: Lankston Johnson, Area Manager, email address: lajohnson@dot.ga.gov, phone#: 404-559-6699

- Project website: <http://www.dot.ga.gov/BS/Projects/SpecialProjects>