

1 **Construction and Performance of Inverted Pavements in Georgia**

2  
3  
4  
5 Dwane E. Lewis  
6 Branch Supervisor – Pit and Quarry Branch  
7 [dlewis@dot.ga.gov](mailto:dlewis@dot.ga.gov)  
8

9 Keith Ledford  
10 Technical Services Engineer – Pit and Quarry Branch  
11 [keledford@dot.ga.gov](mailto:keledford@dot.ga.gov)  
12

13 Tanisha Georges, E.I.T.  
14 Pavement Testing Engineer – Pavement Management Branch  
15 [tgeorges@dot.ga.gov](mailto:tgeorges@dot.ga.gov)  
16

17 David M. Jared, P.E.  
18 Acting Chief, Research and Development  
19 [djared@dot.ga.gov](mailto:djared@dot.ga.gov)  
20 (Corresponding Author)  
21

22  
23 Georgia Department of Transportation  
24 Office of Materials and Research  
25 15 Kennedy Drive  
26 Forest Park, GA 30297-2534  
27 Phone: 404.608.4700  
28 Fax: 404.608.4752  
29

30  
31 Word Count = 4214 (text) + 1750 (tables) + 1500 (figures) = **7464**  
32

**33 ABSTRACT**

34 Inverted Pavement (IP) is an innovative highway pavement design where the rigidity of the  
35 lower, supporting layers is significantly greater than that of the upper, structural layers.  
36 Developed by South Africa in the early 1970's, this design is being investigated for various  
37 roadway applications in the United States, while variations of it have been used since the 1980's.  
38 By utilizing native crushed stone and less imported bitumen, South Africa has reported a 20-25%  
39 cost savings compared with conventional concrete and/or bituminous pavements. After being  
40 introduced to the IP design, Georgia Department of Transportation (GDOT) assisted the Georgia  
41 Construction Aggregates Association with construction of an IP test section on a private quarry  
42 haul road. Based on excellent performance of the test section over 10 years, GDOT constructed  
43 its own test section on a new bypass road near LaGrange, Georgia. The successful completion of  
44 the project and the cost savings therein prompted GDOT to allow IP as an optional construction  
45 method on future projects.

**46 INTRODUCTION**

47 Inverted Pavement (IP) is an innovative highway pavement design where the rigidity of the  
48 lower, supporting layers is significantly greater than that of the upper, structural layers.  
49 Developed by South Africa in the early 1970's, this design is also referred to as G1-Base,  
50 Inverted Base, Sandwich Pavement, and Upside Down Pavement. Depending upon traffic  
51 loading, typical design thickness of an IP ranges from 32 to 48 in. (800-1200 mm). The process  
52 begins with 6-12 in. (150-300 mm) of stabilized subbase, followed by 6-12 in. of cement-treated  
53 aggregate base, and then by 4-6 in. (100-150 mm) of unbound graded aggregate base, with a thin  
54 layer of bituminous mix (18-50 mm) completing the design. Since the 1970's, South Africa has  
55 used IP as its primary pavement structure for both local and highway systems (1). IP variants  
56 have also been successfully used on rural routes, state routes, and interstate systems in the United  
57 States since the 1980's (2,3).

**58 South African Experience**

59 IP was developed in South Africa to reduce pavement costs by utilizing (1) abundant native  
60 aggregate products and (2) less imported bitumen. South Africa has reported a 20-25% cost  
61 savings compared with conventional portland cement concrete (PCC) or hot mix asphalt (HMA)  
62 pavements. To confirm the performance of the innovative pavement, South Africa conducted  
63 extensive full-scale accelerated pavement research using a Heavy Vehicle Simulator. It was  
64 determined that the IP roadways actually provided better structural performance than  
65 conventional pavement systems. Most importantly, construction costs were reduced by the need  
66 for only a thin asphaltic surface overlay of 0.75-2 in. (18-50 mm) (1).

67 Based on a 10-year research period, the South African Pavement Design Catalogue listed  
68 IP as having a bearing capacity of 1-50 million Equivalent Standard Axle Loads (ESAL's),  
69 assuming effective surface maintenance over the design period and considering climate.  
70 Numerous examples exist in South Africa where IP was used in heavily trafficked roads. The N1  
71 (Ben Schoeman) Freeway between the metropolitan areas of Johannesburg and Pretoria, with an  
72 average rainfall of 25.5 in. (650 mm) per year, carried more than 15 million ESALs over a period  
73 of more than 20 years before it was structurally strengthened (1).

74  
75  
76  
77  
78

## 79 **Technology Transfer to Georgia**

80 In the spring of 1999, GDOT engineers became familiar with IP technology while attending an  
81 international transportation symposium in South Africa. In November 1999, GDOT met with the  
82 Georgia Construction Aggregate Association (GCAA) to discuss rising construction costs and  
83 the need to pursue alternative, cost-effective construction materials and methods. The IP system  
84 was introduced, and the GCAA expressed much interest.

85 The meeting was followed by the construction of an IP test section at the Lafarge  
86 Building Materials quarry near Madison, Georgia (Morgan County). GDOT worked closely with  
87 GCAA and Lafarge on the design, construction, and testing of the IP test section. Based on the  
88 success of the pilot project, as described herein, and due to the rising cost of asphalt cement,  
89 GDOT built its own IP test section on the South LaGrange Loop in Troup County. This paper  
90 summarizes construction of both the Lafarge quarry road and South LaGrange Loop test  
91 sections. Emphasis is on the concept for each test section, construction operations and  
92 observations, and performance data as available. This data is being provided to support IP as a  
93 potentially viable alternative pavement choice for roadways in Georgia.

94

## 95 **LAFARGE QUARRY TEST SECTION**


96 As above, GDOT chose to assist GCAA with a pilot IP application, following discussion with  
97 GCAA in late 1999. An 800-ft. (244 m) test section was constructed using the South African IP  
98 process on a new access road at the Lafarge Building Materials quarry near Madison, Georgia  
99 (Morgan County). This test section, which was completed in December 2001, served as an  
100 excellent pilot because of the (1) loading that the haul road is subjected to each year; and (2) ease  
101 of tracking this loading in the test section. As discussed below, the test section utilized guidelines  
102 and procedures established by the South African Roads Board. Also, the data collected from  
103 those test sections was used to write a special provision (#320) regarding Inverted Pavements in  
104 the GDOT specifications. This project is hereafter referred to as the Morgan County Project  
105 (MCP).

106

## 107 **Explanation of Test Section and IP Cross-Section**

108 The total length of the haul road was approximately 1200 ft. (366 m), which was divided into  
109 three 400-ft. (122-m) sections for the pilot project. The entire road required as much as 6 feet  
110 (1.8 m) of fill, which consisted of mostly waste aggregate (pit overburden and weathered rock).  
111 To ensure that the load carrying capacity of the subgrade met a minimum California Bearing  
112 Ratio (CBR) value of 15, 100% granitic aggregate was used in lieu of the poor soil at the quarry.  
113 CBR values obtained from the MCP all exceeded 50. An additional 2 in. (51 mm) of graded  
114 aggregate base (GAB) was placed so that all three sections would have a consistent subbase.

115 The first 400 ft. (122 m), beginning at Seven Islands Road, was called the “conventional”  
116 section and was completed using 6 in. (150 mm) of compacted surge stone followed by 8 in.  
117 (200 mm) of compacted GAB. The remaining 800 ft. (244 m) was divided into two, 400-ft. (122  
118 m) IP test sections. Both IP sections were completed with an 8 in. (200 mm) cement treated  
119 base (CTB) layer and 6 in. (150 mm) GAB layer. The only difference between the two IP  
120 sections was in the construction of the GAB: the first section was constructed with the “slushing”  
121 method (described in the following section) the second section using conventional construction  
122 methods. The cross-section for both IP sections on the MCP is shown in Figure 1. Both the  
123 conventional and IP sections were overlaid with 3 in. (75 mm) of 19 mm Superpave hot mix  
124 asphalt (HMA).



125  
126 1 in. = 25.4 mm  
127 1 pcf = 16 kg/m<sup>3</sup>  
128 1 psi = 0.006985 MPa  
129

130 **FIGURE 1 Inverted Pavement Cross-Section: Morgan Co. Project.**

131  
132 ***Graded Aggregate Base (GAB) Construction***

133 The GAB construction was the most critical and experimental part of the IP tested on the MCP.  
134 The rationale for the different GAB construction methods used in the two 400-ft. (122-m) IP test  
135 sections is explained in the following paragraphs. These two sections are hereafter referred to as  
136 (1) the South Africa section (the first section, in which “slushing” was used); and (2) the Georgia  
137 section (the second, in which conventional methods were used).

138 In South African practice, the GAB layer is compacted to 86% - 88% of apparent density,  
139 otherwise referred to as compacted to *solid particle density*. Research conducted during the MCP  
140 showed that 86% of apparent gravity was equivalent to approximately 101% - 106% maximum  
141 dry density for a GDOT Group II (granite-gneiss) aggregate. According to information obtained  
142 from South Africa, this apparent gravity is only achieved through a process referred to as  
143 “slushing.” The purpose of slushing is to knit different sized aggregate particles into a firmly  
144 interlocked mass. Saturated fines serve as a lubricant in the slushing process, and the volume of  
145 voids between aggregate particles diminishes when the fines are expelled to the surface (1).

146 To test this theory, GDOT first obtained samples of GAB from South Africa and  
147 conducted extensive testing on the aggregate to determine if it was comparable in mineralogy  
148 and gradation to that commonly used in GDOT construction. The results indicated that it would  
149 indeed meet GDOT Standard Specification (Section 815) requirements for a Group II GAB. The  
150 next step was to determine if slushing was necessary in achieving 86% of apparent gravity or if  
151 conventional construction methods could accomplish the same result. Consequently, two 400-ft.  
152 (122-m) IP test sections were established on the MCP, with the slushing method being used to  
153 compact the GAB in the first.

154 Using common construction equipment, the GAB was saturated with numerous  
155 applications of water and compacted until air bubbles began to form on the surface. Per South  
156 African experience, the expelled fines will appear to be coarser at the end of the slushing process  
157 than initially, and no air bubbles or movement will be seen behind the wheels of the roller (1).  
158 The second 400-ft. (122-m) test section was constructed using conventional methods, with the

159 moisture content being maintained at 100% - 120% optimum throughout construction. Testing  
 160 was conducted using the in-situ, sand cone density method, and results are shown in Table 1.  
 161 Samples were taken at random locations within the slushing and conventional sections. All  
 162 compaction tests were determined using an apparent gravity of 168.9 pcf (2706 kg/m<sup>3</sup>) and a  
 163 theoretical maximum dry density of 135.3 pcf (2168 kg/m<sup>3</sup>). The optimum moisture was  
 164 determined by the flame dry method at each test location. As anticipated, 86% of apparent  
 165 gravity was achieved in both test sections, confirming that slushing was not necessary. The  
 166 consensus of both GDOT and GCAA was that compacting the GAB on a rigid CTB was most  
 167 likely the contributing factor.

168 **TABLE 1 IP Density & Apparent Gravity Results: Morgan Co. Project**  
 169

Sample	In-Place Density (pcf)	% Compaction	
		Apparent Gravity	Maximum Dry Density (pcf)
Slushing 1	144.9	85.8	104.1
Slushing 2	144.6	85.6	103.2
Slushing 3	145.9	86.4	101.8
Conventional 1	146.7	86.9	104.5
Conventional 2	147.6	87.4	106.5

170 1 pcf = 16 kg/m<sup>3</sup>  
 171

172 **Post-Construction Performance Data**

173 A five-year evaluation was conducted on the MCP consisting of calculation of ESAL's, string-  
 174 line rutting measurements, visual inspection, and falling weight deflectometer (FWD) testing.  
 175 The results of the evaluation are summarized below. Information on performance to-date is also  
 176 included in this section. The test section has performed remarkably well for over 10 years, with  
 177 no maintenance or resurfacing required.

178 *Equivalent Single Axle Loads*

179 Loading data supplied by Lafarge, in tonnage of crushed stone, concrete, and asphalt hauled,  
 180 indicated that approximately 854,000 ESAL's traversed the MCP during the first five years of its  
 181 life, or 63.38% of the design ESAL's (4). Design life was based on an annual average daily  
 182 traffic (AADT) of 146 (100% trucks), with an annual growth of 4.5%. A summary of the  
 183 ESAL's from 2001-2011, based on the annual growth rate, is shown in Table 2. As of March  
 184 2011, an estimated 1,139,968 ESAL's had traversed the MCP.  
 185

186 **TABLE 2 Equivalent Single Axle Loads, 2001-2011: Morgan Co. Project**  
 187  
 188

	YEAR							TOTAL
	5-Year Evaluation							
	2001	2002	2003	2004	2005	2006	2006 - 2011	
ESAL's	2,840	127,496	312,676	119,373	134,155	157,215	286,249	1,139,968

190 *Rutting Measurements*

191 Rutting measurements were made from Station 0+50 through Station 18+00 on the MCP on  
 192 December 3, 2003 and November 13, 2006. Measurements were taken every 50 feet (15 m)  
 193 along all three sections of the project, as outlined below.

194

- 195 • Sta. 0+00: intersection with Seven Islands Rd.
- 196 • Sta. 0+50 - 10+00: conventional haul road section
- 197 • Sta. 10+50 - 14+00: South Africa section
- 198 • Sta. 14+50 - 18+00: Georgia

199

200 Rutting measurements for the conventional section are shown in Table 3, while measurements  
 201 for the South Africa and Georgia sections are shown in Table 4. In each table, the left number for  
 202 each station is the 2003 measurement, while the right number is the 2006 measurement.

203

204 **TABLE 3 Rutting Measurements (in./16), Conventional Haul Road, Morgan Co. Project**

205

Sta. #	15 ft. Left of C/L (2003/2006)	10 ft. Left of C/L (2003/2006)	5 ft. Left of C/L (2003/2006)	Centerline (C/L) (2003/2006)	5 ft. Right of C/L (2003/2006)	10 ft. Right of C/L (2003/2006)	15 ft. Right of C/L (2003/2006)
0+50	0/0 <sup>1</sup>	5/5	0 / 8	0/0	0/1	4/4	0/0
1+00	0/16+	16/16	14/14	0/0	0/0	3/3	0/0
1+50	0/0	0/0	0/0	0/0	0/0	0/0	0/2
2+00	0/0	0/0	0/0	0/0	0/0	0/0	0/0
2+50	0/0	0/2	0/0	0/0	0/0	0/0	0/0
3+00	0/0	0/0	0/0	0/0	0/0	0/2	0/0
3+50	0/0	0/0	0/0	0/0	0/0	0/0	0/0
4+00	0/0	0/0	0/0	0/0	0/0	0/0	0/0
4+50	0/0	0/0	0/0	0/0	0/0	0/0	0/0
5+00	0/0	2/2	0/0	0/0	0/0	0/0	0/0
5+50	0/0	0/4	0/0	0/0	0/0	0/0	0/0
6+00	0/0	0/3	0/0	0/0	0/0	0/0	0/0
6+50	0/2	0/4	0/0	0/0	0/1	0/0	0/0
7+00	0/n/a	3/n/a	0/n/a	0/n/a	0/n/a	0/n/a	0/n/a
7+50	0/0	1/1	0/0	0/0	0/0	0/2	0/0

8+00	0/0	0/0	0/0	0/0	0/0	0/0	0/0
8+50	0/0	0/0	0/0	0/0	0/0	0/0	0/0
9+00	0/0	1/1	1/1	0/0	0/0	0/0	0/0
9+50	0/0	0/2	0/0	0/0	0/0	0/0	0/0
10+00	0/0	0/0	1/1	0/0	0/0	0/0	0/0

206 <sup>1</sup>Units are in 1/16 in. (1.6 mm).

207

208 **TABLE 4 - Rutting Measurements (in./16), South African Base (10+50 to 14+00) and**  
 209 **Georgia Base (14+50 to 18+00), Morgan Co. Project**

210

Sta. #	15 ft. Left of C/L (2003/2006)	10 ft. Left of C/L (2003/2006)	5 ft. Left of C/L (2003/2006)	Centerline (C/L) (2003/2006)	5 ft. Right of C/L (2003/2006)	10 ft. Right of C/L (2003/2006)	15 ft. Right of C/L (2003/2006)
10+50	0/3 <sup>1</sup>	0/0	0/0	0/0	0/0	0/0	0/0
11+00	0/4	3/6	0/0	0/0	0/0	0/0	0/0
11+50	0/0	1/1	0/0	0/0	0/0	0/0	0/0
12+00	0/1	0/0	0/0	0/0	0/1	0/0	0/0
12+50	0/3	0/1	0/0	0/0	0/0	0/0	0/0
13+00	0/2	0/1	0/0	0/0	0/1	0/0	0/0
13+50	0/0	0/2	0/0	0/0	0/0	0/0	0/0
14+00	0/0	0/0	0/0	0/0	0/0	0/0	0/0
14+50	0/0	0/0	0/0	0/0	0/0	0/0	0/0
15+00	0/0	0/0	0/0	0/0	0/0	0/0	0/0
15+50	0/0	0/0	0/0	0/0	0/0	0/0	0/0
16+00	0/0	0/0	0/0	0/0	0/0	0/0	0/0
16+50	0/0	0/0	0/0	0/0	0/0	0/0	0/0
17+00	0/0	0/0	0/0	0/0	0/0	0/0	0/0
17+50	0/0	0/0	0/0	0/0	0/0	0/0	0/0
18+00	0/0	0/0	0/0	0/0	0/0	0/0	0/0

211 <sup>1</sup>Units are in 1/16 in. (1.6 mm).

212

213 The rutting observed in the two IP sections was insignificant; however, minor and *major* rutting  
 214 was found within the conventional section, especially in the eastbound lane, in which the haul  
 215 trucks are loaded. Rutting levels over 1 in. (25 mm) were measured at the quarry gate where  
 216 trucks stop.

217

### 218 *Visual Inspection*

219 No cracking in the asphaltic concrete layer was observed in the IP test sections during  
 220 observations on December 3, 2003 and November 13, 2006 (4). Extensive cracking, however,  
 221 was observed in the conventional haul road section, as shown in Figure 2. Most of the extensive  
 222 cracking was located in the eastbound lane, and advanced deterioration was observed where  
 223 loaded trucks were stopping at the quarry gate.

224



225

226

227 **FIGURE 2 - Rutting and cracking on conventional haul road section: Morgan Co. Project.**

228

229 Annual inspections have been conducted since the five-year evaluation, and the IP test  
 230 sections continue to perform well with no rutting or cracking being observed. Within the past  
 231 five years, a secondary road which crosses over the IP sections was built for off-road trucks to  
 232 carry pit overburden to a waste site. When loaded, these trucks weigh over 40 tons, and it is  
 233 estimated that several hundred loads have traveled across the IP test sections. Visually, no  
 234 distresses can be observed in the crossing area.

235

### 236 *Falling Weight Deflectometer Testing*

237 FWD testing was conducted in November, 2007 on the MCP. This testing was conducted to  
 238 examine how the IP sections compared with the conventional haul road section. At each drop  
 239 location, two seating drops, at a target load of 7,000 lbf, were used, and twelve (12) recorded  
 240 drops (three each at target loads of 7000 lbf (3150 kg), 9000 lbf (4050 kg), 11000 lbf (4950 kg)  
 241 and 16000 lbf (7200 kg)).

242

243 After analysis of the deflection data collected using the program ModTag and its  
 244 supporting program ModCOMP, the Subgrade Modulus, Effective Structural Number,  
 245 Remaining Life (RL) as a percentage of the original pavement life, and the Layer Moduli were  
 246 calculated. The assumptions used during the analysis process are as follows:


247

248

- Conventional Haul Route Pavement (drop stations 0 - 1000) - flexible pavement with 3 in. (75 mm) asphaltic concrete (AC) and 8 in. (200 mm) GAB; 6 in. (150 mm) surge stone

- 249 • South African IP (drop stations 1000 - 1400) - flexible pavement with 3 in. (75  
250 mm) AC, 6 in. (150 mm) GAB, and 10 in. (250 mm) CTB (8 in. CTB combined  
251 with 2 in. GAB filler);
- 252 • Georgia IP (drop stations 1400 to 1800) – same as South African IP

253  
254 Figure 3 shows the normalized (9 kips) deflections for both entering and exiting segments  
255 of the MCP. Based on the deflection data gathered for the loading above, the IP sections were  
256 determined to be in excellent condition. The average RL determined by ModTAG for the  
257 Georgia IP was 99.34% of the original design life, 94.61% for the South African IP, and 67.92%  
258 for the conventional haul route pavement (5).  
259



260

261  
262  
263  
264  
265  
266

**FIGURE 3 Normalized Deflections: Entering and Exiting Morgan Co. Project.**

267 **SOUTH LAGRANGE LOOP TEST SECTION**

268 Based on the success of the MCP, and due to the rising cost of asphalt cement, GDOT decided to  
 269 fund and build its own IP test section on the South LaGrange Loop in Troup County. This  
 270 project, hereafter referred to as the LaGrange Bypass Project (LBP), was one of several for the  
 271 preparation of the Kia automotive plant being built in the neighboring town of West Point,  
 272 Georgia, and it connects the Kia plant with a newly developed industrial park. The two-lane,  
 273 2.03-mi. (3.24 km) roadway was constructed with a conventional, portland cement concrete  
 274 (PCC) pavement structure, except for the 3,434-ft. (1047-m) IP test section.

275 Construction of the LBP began in January 2008, including the IP test section, which  
 276 consisted of (1) stabilized subgrade; (2) cement-treated base (CTB); (3) graded aggregate base  
 277 (GAB); and (4) HMA. The subgrade, CTB, and GAB courses were constructed in accordance  
 278 with GDOT Specifications Special Provision 320 (Inverted Pavements). The IP and PCC cross-  
 279 sections on the LBP are shown in Figure 4.  
 280



281  
 282 1 in. = 25.4 mm

283  
 284 **FIGURE 4 Inverted Pavement and Portland Cement Concrete Pavement Cross-Sections:**  
 285 **South LaGrange Loop (6).**

286  
 287 **Construction Details: Test Section on LaGrange Bypass Project**

288  
 289 ***Stabilized Subgrade Course***

290 For the IP section, the soil’s load carrying capacity was critical. The California Bearing Ratio  
 291 (CBR) test (AASHTO T-193) is used to determine this capacity, as with the MCP, and GDOT  
 292 specifications include a Soil Support Value (SSV) based on the CBR test. The objective of the  
 293 subgrade course construction was to achieve an SSV of 5.0 (CBR = 15) or greater in the top 6 in.  
 294 (150 mm) of the subgrade as required by the project plans for both excavation and embankment  
 295 areas. To achieve this, the plans called for the incorporation of a stabilizer aggregate uniformly  
 296 throughout this course.

297 Originally, GDOT intended to give contractor the opportunity to choose between  
 298 chemical stabilization (lime or cement) or mechanical stabilization (aggregate). Prior to the

299 bidding process, several interested contractors suggested that GDOT list only one stabilization  
 300 process so all bidders would bid on the same process. Since it was uncertain if high quality  
 301 material was available for chemical stabilization, GDOT decided to specify mechanical  
 302 stabilization, since the project was near aggregate quarries.

303 The top 6 in. (150 mm) of the embankment is considered subgrade and had to be, per  
 304 GDOT soil classification, a IIB4 (Type IA best, Type IIIC worst) or better before stabilization.  
 305 The specifications for a IIB4 soil are 0-75% passing the #200 sieve, a percent volume change of  
 306 0-25%, and a dry maximum density of 90 pcf (1440 kg/m<sup>3</sup>). Eight test locations were  
 307 established, and all eight embankment samples were IIB4 or better, per Table 5.

308  
 309 **TABLE 5 Soil Classification Sampling: LaGrange Bypass Project**

310

Sieve Size					% Clay	% Vol. Δ	% Swell	% Shrinkage	Dry Max. ρ (pcf)	% Optimum Moisture
1.5 in.	#10	#40	#60	#200						
100	95	88	81	69	54	13.9	9.8	4.1	96.0	22.0
100	100	89	83	69	50	25.0	21.6	3.4	94.0	24.0
100	89	79	73	61	42	23.4	20.7	2.7	96.0	23.0
100	99	86	80	65	38	9.9	7.1	2.8	92.0	24.0
100	99	80	71	54	35	13.8	9.3	4.5	91.0	25.0
100	96	80	72	58	37	23.4	19.6	3.8	98.0	21.0
100	99	82	69	52	32	25.0	23.0	2.0	107.0	15.0
100	99	84	73	55	34	24.2	20.5	3.7	99.0	19.0

311 1 in. = 25.4 mm

312 1 pcf = 16 kg/m<sup>3</sup>

313  
 314 Soil samples for CBR testing were then obtained throughout the test section and CBR  
 315 tests performed using varying percentages of GAB. It was determined that a 50/50 blend (i.e. 3  
 316 in. (75 mm) GAB to 3 in. soil) achieved the SSV required, and this blend was used by the  
 317 contractor. Follow up gradation and classification of the in-situ blended subgrade indicated that  
 318 the blend met GDOT specifications. Figure 5 shows the blending of the subgrade with GAB  
 319 from two angles: before and during blending.



321  
 322  
 323 **FIGURE 5 Mechanical Subgrade Stabilization with Graded Aggregate Base: LaGrange**  
 324 **Bypass Project**

325

**Cement Stabilized Graded Aggregate Construction**

This work included constructing a premixed, CTB course composed of GAB, Type I Portland cement, and water, which needed to be proportioned, uniformly blended, placed, compacted and cured in accordance with the project specifications. On the MCP, the CTB was mixed in-place, with excellent performance and large cost savings; however, GDOT required plant-mixed CTB on the LBP to ensure a consistent mix. Using a portable plant was more expensive but helped ensure best results for the test section. The contractor was again required to submit a CTB mix design for review and approval before construction. The mix design was performed in accordance with GDOT Test Method GDT-65 (Laboratory Design of Soil-Cement and Cement Stabilized Graded Aggregate). With 4% cement and an optimum moisture content of 7%, the minimum required laboratory unconfined compressive strength of 450 psi (3.1 MPa) was achieved. Acceptance testing required a minimum unconfined compressive strength of 300 psi (2.1 MPa).

It took only three days to place 2,355 yd.<sup>3</sup> (1800 m<sup>3</sup>) of CTB in the test section, and on the first day the moisture content was adjusted significantly to accommodate field conditions. Overall, the production and placement of the CTB went well with very little problems encountered. The cement content ranged from 3.82 % to 3.93% ( $\bar{x}$  = 3.89%), and the moisture content ranged from 5.54% to 7.69% ( $\bar{x}$  = 6.2%).

The CTB was mixed using a continuous mix batch plant and placed with a paver equipped with high-density, vibratory, dual tamping bars. These tamping bars were capable of compacting the CTB to within 90% of the maximum dry density. Compaction was completed with two vibratory steel wheel rollers (one rubber-coated) and a pneumatic rubber tire roller. Six compaction tests were performed using a nuclear density gauge and by in-situ, sand-cone density testing. The average dry density of the six compactions was 153.2 lb/ft<sup>3</sup> (2451 kg/m<sup>3</sup>) at an average moisture content of 4.60%. The CTB was kept continuously moist through the process and was clipped to final grade using a trimmer equipped with electronic slope controls.

Once the CTB conformed to the grade, thickness, and cross-section shown in the project plans, another application of water was applied followed by a bituminous prime coat to seal in the moisture. After seven days of curing the CTB, five 6-in. (150 mm) cores were extracted and tested for unconfined compressive strength. Values ranged from 446 psi (3.1 MPa) to 723 psi (5 MPa), well above the minimum strength required for acceptance (300 psi/2.1 MPa).

**Graded Aggregate Base (GAB) Construction**

The data collected on the MCP was used to prepare the Special Provision for GAB construction on the LBP. During the pre-bidding process, much concern was expressed by potential contractors with the unfamiliar compaction requirement. Subsequently, a provision was provided to allow a 100% of maximum dry density requirement in lieu of 86% of apparent gravity if problems were encountered.

After the project was awarded, extensive apparent gravity testing was conducted on the contractor's source of GAB. It was decided to run these tests with both the South African method for determining apparent gravity and with AASHTO T-85, which is used by GDOT. Three additional sources with different mineral compositions were also tested for comparison. With the South African method, testing was performed using variances in water temperatures, soaking periods, and sample weights. From all 58 tests performed, it was determined that both test procedures produced repeatable and comparable results. For the GAB that was used in the test section, the apparent gravity was 166.9 pcf using the South African method and 165.4 pcf using

372 AASHTO T-85. The GAB was placed, compacted, graded, and primed using typical construction  
 373 equipment. The moisture was kept within 100% - 120% through the process. The results of all  
 374 quality acceptance field testing are shown in Table 6.

375 **TABLE 6 IP Compaction Results: LaGrange Bypass Project**  
 376  
 377

Station	Depth (in.)	In-place Density (Nuclear Gauge) @ In-Place Moisture %	Apparent Gravity (166.9 pcf @ 5.8% Moisture)		Maximum Dry Density (137.1 pcf @ 5.8% Moisture)
			% Compaction Achieved		
280+50	6.5	144.4 @ 2.0	86.5		105.3
286+50	6.0	142.9 @ 2.4	85.6		104.2
296+50	5.5	143.2 @ 2.3	85.8		104.4
303+50	6.0	143.1 @ 2.3	85.8		104.4
313+50	6.0	143.0 @ 2.3	85.7		104.3
			$\bar{x}$	85.9	104.5

378 1 in. = 25.4 mm  
 379

### 380 *Hot Mix Asphaltic Concrete Construction*

381 The entire IP concept is based on a design that relies on deep supporting layers to reduce the  
 382 stresses in the base and surfacing layers (1). This allows for the use of a relatively thin asphaltic  
 383 concrete pavement surface ranging from ¾ in. to 2 in. (18 mm – 50 mm) or a Surface Treatment  
 384 application which has been successfully used in South Africa. The purpose of this layer is mostly  
 385 to protect the crushed stone layer from water penetration, and since these layers are prone to  
 386 aging and fatigue cracking under both traffic loading and environmental conditions, it is  
 387 important to note that this layer is not considered to have any structural value. Life-cycle costing  
 388 should therefore include preventative maintenance costs such as occasional crack sealing (1).

389 On the LBP, the asphaltic concrete layers consisted of 2 in./220 lb./yd.<sup>2</sup> (51 mm/119  
 390 kg/m<sup>2</sup>) of 19 mm Superpave topped with 1.5 in./165 lb./yd.<sup>2</sup> (38 mm/89 kg/m<sup>2</sup>) of polymer-  
 391 modified 12.5 mm Superpave as a surface course. Both the 19 mm and 12.5 mm Superpave  
 392 mixes were placed using a wedge lock paver. A total of 1390.64 tons (1261.31 Mg), including  
 393 1084.02 tons (983.21 Mg) of 19 mm and 306.62 tons (278.10 Mg) of 12.5 mm, were placed,  
 394 followed by testing with a nuclear gauge to determine density and extraction of in-situ cores to  
 395 test for specific gravity and air voids. All quality acceptance testing at the plant during  
 396 production and field verification testing met the requirements of Section 828 (Hot Mix Asphalt  
 397 Concrete Mixtures) of the GDOT Standard Specifications.  
 398

### 399 **Post-Construction Performance Data**

400 Since its completion in 2009, the LBP has been structurally evaluated. Between August 20,  
 401 2008, and May 14, 2009, FWD testing was conducted along the length of the newly constructed  
 402 roadway to assess the strength of the newly placed pavement layers. Based on the deflection data  
 403 gathered for the target load of 9 kips (4050 kg), the new pavement structure evaluated as a whole  
 404 was determined to be in excellent condition with an average normalized deflection of 8.54 mils  
 405 at Sensor One (9000 lbf/4050 kg), as shown in Table 7.  
 406  
 407

408  
409


**TABLE 7 Normalized Deflections: LaGrange Bypass Project**

Deflections (mils):							
Sta. (ft.)	Comments	R1	R2	R3	R4	R7	
0		9.6	6.04	4.14	2.71	0.91	
108		10.27	6.26	4.21	2.88	1.21	
201		9.7	6.22	4.46	3.09	1.45	
406		10.34	6.76	5.05	3.85	1.51	
610		9.79	6.03	4.21	2.84	1.28	
902		10.61	7.15	5.21	3.66	1.5	
1110		10.27	6.08	4.16	2.96	1.47	
1206		9.47	6.72	5.08	3.72	1.22	
1500	None	10.97	7.71	5.86	4.48	1.67	
1610		10.66	6.54	4.53	3.23	1.63	
1800		12.98	8.99	6.75	4.95	1.77	
2108		13.05	9.22	6.77	4.81	1.56	
2109		9.41	5.62	3.9	2.88	1.47	
2500		11.22	7.22	4.87	3.2	0.85	
2610		9.7	5.89	4.06	2.9	0.83	
2901		9.85	6.2	4.25	2.81	0.81	
3000		11.83	7	4.5	3.08	0.96	
3021		10.92	6.76	4.33	2.9	1.02	
3050			3.85	2.97	2.77	2.6	0.95
3075		Area milled following previous testing; Consists of GAB, 25mm SP, 19mm SP, and 12.5mm Superpave	3.29	2.39	2.18	2.02	1.01
3100			2.89	2.22	2.05	1.93	0.94
3110	3.76		2.7	2.4	2.17	0.9	
3125	3.26		2.33	2.16	1.99	0.96	
3135	4.92		3.53	3.15	2.83	1.1	
3160	6.41		5.44	4.95	4.29	1.23	
3185	3.11		2.54	2.44	2.28	1.14	
Mean			8.54	5.64	4.17	3.12	1.21
Std. Dev.		3.32	2.04	1.3	0.83	0.3	

1 mil = 0.0254 mm

410  
411  
412  
413  
414

Normalized deflections at Sensor One for each layer tested at each drop location are shown in Figure 6.



415  
416

**FIGURE 6 Normalized Deflections at Sensor 1 (9000 lbf/4050 kg): Pavement Layers for LaGrange Bypass Project.**

419

420 Also, the Remaining Pavement Life (RL) in years was determined through the use of the  
421 analysis program MODULUS. MODULUS separates the RL into two types, RUT (the effect  
422 that rutting has on the pavement life) and CRK (the effect that cracking has on the pavement  
423 life). Throughout the length of the project, the remaining pavement life for both cracking and  
424 rutting is over 10 years (7).

425

**CONCLUSIONS**

426

427 Overall, the Morgan County and LaGrange Bypass projects were both successful in that all  
428 construction processes were completed without any major complications. Construction went  
429 smoothly, no additional equipment was needed for construction, and all specification  
430 requirements were met. Since the LBP is only Phase I of the Bypass and traffic will be limited  
431 until Phase II can be completed, it will be several years before performance data can be collected  
432 and a long-range assessment can be made. Based on 10 years of superior performance, however,  
433 with the MCP and IP’s proven effectiveness in South Africa under high traffic conditions and  
434 harsh weather conditions, it is certain that this cost-effective construction process will be used on  
435 future GDOT projects.

436

**REFERENCES**

437

438  
439 1. “Pavements Constructed with Processed (Graded) Crushed Stone (Aggregate) Bases on  
440 Stabilized Subbases,” (video script), South African Roads Board, 1998.  
441 2. Buchanan, S. “Inverted Pavement Economics.” Presentation to Georgia Department of  
442 Transportation, 2011.  
443 3. Rasouljian, M. “Stone Interlayer Pavements.” Presentation at Louisiana Pavement  
444 Conference, [http://www.ltrc.lsu.edu/lpc\\_presentations/pdf/Stone%20Interlayer%20Pavements.pdf](http://www.ltrc.lsu.edu/lpc_presentations/pdf/Stone%20Interlayer%20Pavements.pdf), 2004.

- 445 4. Lewis, D. Inverted Base Pavement at Lafarge Quarry Entrance Road: Five-Year Field  
446 Evaluation. Georgia Department of Transportation, 2006.
- 447 5. Georges, T. Falling Weight Deflectometer (FWD) Test Results: Entrance Road of the  
448 Lafarge Quarry in Morgan County, GA. Georgia Department of Transportation, 2007.
- 449 6. Lewis, D. "Inverted Pavements: From Concept to Reality." Presentation to Construction  
450 Aggregate Association. Georgia Department of Transportation, 2008.
- 451 7. Georges, T. Falling Weight Deflectometer (FWD) Findings for Tests Conducted on  
452 Research Project in LaGrange, GA. Georgia Department of Transportation, 2009.