

Interoffice Memo Office of Design Policy & Support

DATE: 9/20/2021

FILE: P.I.# 0013924

Laurens County / GDOT District 2 - Tennille

SR 26 @ INDIAN BRANCH 5.2 MI SE OF BREWTON

Bridge Replacement

Dane Peters

FROM: FROM: R. Christopher Rudd, PE, State Design Policy Engineer

TO: SEE DISTRIBUTION

SUBJECT: APPROVED LOCATION & DESIGN REPORT

Attached is the approved Location and Design Report with Notice of Location &

Design Approval for the above subject project.

Attachment

Distribution:

Hiral Patel, Director of Engineering

Joe Carpenter, Director of P3

Albert Shelby, Director of Program Delivery

Darryl VanMeter, Assistant Director of P3/State Innovative Delivery Administrator

Matthew Markham, Deputy Director of Planning

Kim Nesbitt, Program Delivery Administrator

Bobby Hilliard, Program Control Administrator

Eric Duff, State Environmental Administrator

Donn Digamon, State Bridge Engineer

Andrew Heath, State Traffic Engineer

Angela Robinson, Financial Management Administrator

Erik Rohde, State Project Review Engineer

Benny Walden, Statewide Location Bureau Chief

Corbett Reynolds, District Engineer

Todd Price, District Preconstruction Engineer

Ellen Wright, District Planning & Programming Coordinator

Clayton McCoy, Area Manager - D2, A2

Corey Jackson, Project Manager

BOARD MEMBER - 12th Congressional District



Interoffice Memo

FILE:

P.I. 0013924, Laurens County

SR 26 @ INDIAN BRANCH 5.2 MI SE OF BREWTON

DATE:

November 19, 2019

for

FROM:

Kimberly W. Nesbitt, State Program Delivery Administrator

TO:

Office of Design Policy and Support via ConceptReports@dot.ga.gov

SUBJECT: Submittal - Location and Design (L&D) Report

The Office of Program Delivery hereby submits the attached Location and Design (L&D) Report for your review and approval.

If any additional information is needed, please contact Jeff Henry at (404) 663-8649.

KWN:CLB:SHP:DDC:JCH

Attachments: Preconstruction Status Report, Completed Location & Design approval request

cc: Honorable Don Grantham, Transportation Board Member - Congressional District 12

Bill Duvall, State Bridge Engineer

Brent Story, State Design Policy Engineer

Hiral Patel, Director of Engineering

Albert V. Shelby, III, Director of Program Delivery

engsvcsconcepts@dot.ga.gov (Mailbox for Engineering Services)

Eric Duff, State Environmental Administrator

"OFM Concept Reports" Inbox - OFMConceptReports@dot.state.ga.us

Paul Tanner, State Transportation Planning Administrator

Bobby Hilliard, Program Control Administrator

ROW Inbox - Plansoffice@dot.ga.gov

Benny Walden, State Location Bureau Chief

Andrew Heath, State Traffic Engineer

Transportation Data Inbox – HighwaySystemsAdministrator@dot.ga.gov

Clayton McCoy, District 2 Area 2 Engineer

Corbett Reynolds, District 2 Engineer

Ellen Wright, District 2 Planning and Programming Engineer

Todd Price, District 2 Preconstruction Engineer



Location and Design Report

DATE:

11/19/2019

FILE:

P.I.# 0013924

Laurens County / GDOT District 2 - Tennille

SR 26 @ Indian Branch 5.2 MI SE of Brewton

FROM:

Kimberly Nesbitt, State Program Delivery Administrator

TO:

Brent Story, P.E., State Design Policy Engineer

Attn: Dave Peters, P.E., State Conceptual Design Group Manager

SUBJECT:

Request for Location and Design Approval

Description and Project Proposal:

This project is located approximately 5.2 miles southeast of Brewton, Georgia in Laurens County and will replace the bridge located on SR 26/US 80 (Savannah Ave) over Indian Branch. The project begins and ends approximately 0.1 mile before and after the existing bridge for a total project length of 0.2 miles. The typical section will be a two-lane rural section with a 12-ft lanes and 10-ft shoulders (4-ft paved). The proposed bridge will be a 95-foot long single span over Indian Branch and will have 8-foot shoulders. 120

Concept Approval Date: 8/16/2018

Concept Update: N/A

Environmental Document: NEPA

Document Type: NEPA - Programmatic Categorical Exclusion Approval Date: TBD 8-25-2021 Location and Design Report - Page 2

County: Laurens

Public Involvement:

The PIOH Detour Meeting was held on July 31th, 2018.

- Meeting location: Graham Memorial Nazarene Church Social Hall, 112 Graham Church Rd. East Dublin, GA 31027.
- The total number of comments received: 2
- Number of comments opposing or supporting the project: 2 conditional support.
- The total number of attendees including any public officials in attendance: 9 total, 1
 public official.
- No project changes were made as a result of the comments received at the Detour Meeting.

Consistency with Approved Planning: The design description as presented herein and submitted for approval is consistent with the approved Concept Report.

Recommendations: Recommend that the location and design for the project be approved and that the attached Notice be approved for advertising.

Concur: Hielketal

GDOT Director of Engineering

Approve: Ap My falls

GDOT Chief Engineer

P.I. Number: 0013924


DATE OF LOCATION AND DESIGN APPROVAL: Dave Peters September 20, 2021

(To be entered by State Conceptual Design Group Manager)

Attachments:

- Sketch Map
- Notice of Location and Design Approval

PROJECT LOCATION MAP



PI 0013924 / LAURENS COUNTY SR 26 @ INDIAN BRANCH 5.2 MI SE OF BREWTON

NOTICE OF LOCATION AND DESIGN APPROVAL

P. I. 0013924 LAURENS COUNTY

Notice is hereby given in compliance with Georgia Code 22-2-109 and 32-3-5 that the Georgia Department of Transportation has approved the Location and Design of this project.

The date of location and design approval is: September 20, 2021

This project is located approximately 5.2 miles southeast of Brewton, Georgia in Laurens County and will replace the bridge located on SR 26/US 80 (Savannah Ave) over Indian Branch. The project begins and ends approximately 0.1 mile before and after the existing bridge for a total project length of 0.2 miles. The project is located at GMD 1412.

The new bridge will be constructed on the existing alignment and traffic will be diverted to an offsite detour during construction for a duration of approximately 9 months. The offsite detour is approximately 5 miles longer for commuter traffic than the SR 10 route. There are local roads that local traffic can use to navigate around the bridge closure. The roadway will be a two 12-foot lanes with 10-foot shoulders (4-foot paved) and the bridge will have 8-foot shoulders.

Drawings or maps or plats of the proposed project, as approved, are on file and are available for public inspection at the Georgia Department of Transportation:

Clayton McCoy
D2, A2
cmccoy@dot.ga.gov
2003 US Hwy 441 South
Dublin, GA 31021
Phone: (478) 278-1774
275-6596

Any interested party may obtain a copy of the drawings or maps or plats or portions thereof by paying a nominal fee and requesting in writing to:

Kimberly Nesbitt
Office of Program Delivery
Attn: Corey Jackson
Email: CoJackson@dot.ga.gov
600 West Peachtree St N.W., 25th Floor
Atlanta, GA 30308
404-376-6618

Any written request or communication in reference to this project or notice SHOULD include the Project and P. I. Number as noted at the top of this notice.