### DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA

## OFFICE OF DESIGN POLICY & SUPPORT INTERDEPARTMENTAL CORRESPONDENCE

FILE P.I.# 0000475

**OFFICE** Design Policy & Support

STP00-0000-00(475)

Dougherty & Worth Counties

GDOT District 4 - Tifton

**DATE** 8/18/2017

SR 133 from North of SR 112 to North of

CR 459/County Line Road

Widening & Improvements

**FROM** 

for Brent Story, State Design Policy Engineer

TO SEE DISTRIBUTION

#### SUBJECT APPROVED LOCATION & DESIGN REPORT

Attached is the approved Location and Design Report with Notice of Location & Design Approval for the above subject project.

#### Attachment

#### DISTRIBUTION:

Hiral Patel, Director of Engineering

Joe Carpenter, Director of P3

Albert Shelby, Director of Program Delivery

Darryl VanMeter, Assistant Director of P3/State Innovative Delivery Administrator

Kim Nesbitt, Program Delivery Administrator

Bobby Hilliard, Program Control Administrator

Cindy VanDyke, State Transportation Planning Administrator

Eric Duff, State Environmental Administrator

Bill DuVall, State Bridge Engineer

Andrew Heath, State Traffic Engineer

Angela Robinson, Financial Management Administrator

Lisa Myers, State Project Review Engineer

Benny Walden, Statewide Location Bureau Chief

Ritchie Swindell, District Engineer

Brent Thomas, District Preconstruction Engineer

Dennis Carter, District Planning & Programming Engineer

Derrick Wilkerson, Area Engineer - D4, A5

Christy Lovett, Project Manager

BOARD MEMBER - 2nd Congressional District

Rec'd: 8-2-2017 PLP

## DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA

#### INTERDEPARTMENT CORRESPONDENCE

FILE STP00-0000-00(475), Worth & Dougherty County

OFFICE

**Program Delivery** 

P.I. No. 0000475

SR 133 FM N of SR 112 to N of CR 459/County Line Rd

DATE

July 21, 2017

FROM Kimberly Nesbitt., State Program Delivery Administrator

TO Office of Design Policy and Support (via Concepts Reports mailbox)

SUBJECT: Submittal - Location and Design (L&D) Report

The Office of Program Delivery hereby submits the attached Location and Design (L&D) Report for your review and approval.

If any additional information is needed, please contact Christy Lovett at 912-530-4420.

AVS:CLB:DGM:CSL

Stray

Attachments: Preconstruction Status Report, Completed Location & Design approval request

#### STATE OF GEORGIA

#### **LOCATION AND DESIGN REPORT**

**FILE** 0000475

STP00-000-00(475)

Worth & Dougherty County

SR 133 Widening & Reconstruction

**OFFICE** Engineering Services

**DATE** 07/19/2017

**FROM** Kimberly Nesbitt, State Program Delivery Administrator

**TO** Brent Story, State Design Policy Engineer
Attn: Dave Peters, State Conceptual Design Group Manager

#### SUBJECT Request for Location and Design Approval

**Description and Project Proposal**: Project No. STP00-000-00(475) is an 3.47 mile widening of SR 133 from an existing two-lane roadway to four-lane roadway with a design speed of 65 mph. The widened typical section includes a 32-foot depressed median, 10-foot outside shoulder, and a 6-foot inside shoulder. Project limits are approximately 3100 feet north of SR 112 to 1600 feet north of County Line Road.

This project continues from the alignment in the adjoining Project No. STP00-0000-00(519) by retaining the existing alignment in one direction and constructing new lanes in the other direction. Continuing north, the alignment would transition onto a new alignment to the east side of SR 133 beginning at CR 392/Piney Woods Drive. Two new parallel bridges, 280 feet long by 39.25 feet wide, would be built over Dry Creek. The alignment returns to the existing corridor approximately 1600 feet north of S. County Line Road (CR417/CR459), retaining the existing alignment as northbound lanes and constructing new southbound lanes.

#### **Concept Approval Date:**

Original Concept Approval: March 7, 2007

Revised Concept Report Approval: May 25, 2011

**Concept Update:** The alignment has been modified to minimize displacements and now ties in at 1600 feet north of S. County Line Rd instead of 700 feet north. This project is now a complete full depth replacement, so no existing pavement will be retained. Outside paved shoulders have been increased from 4' to 6.5' to allow for rumble strip and bike accommodation. The two bridges have been lengthened from 200 to 280 feet and are now 39.25 feet wide to clear Dry Creek.

**Environmental Document:** This is a state-funded project and does not require a GEPA document.

#### **Public Involvement:**

- PIOH Summary
  - o January 26<sup>th</sup> and 27<sup>th</sup>, 2015
    - 262 total attendees: 470 comments, 16 in support, 13 opposed, 8 uncommitted, and 433 conditional support.
  - August 11, 2016

- Two locations: Doerun Elementary School and Okapilco Elementary School
- A total of 306 people attended the open houses for all four projects. Of the 237 respondents who formally commented, 81 were in support of the projects, 19 were opposed, 8 were uncommitted, and 72 expressed conditional support.
- SR 133 proposed alignment was adjusted to address public's comments and reduce impacts to farmland and historic resources.

Consistency with Approved Planning: The design description as presented herein and submitted for approval is consistent with the approved Concept Report.

Recommendations: Recommend that the location and design for the project be approved and that the attached Notice be approved for advertising.

DATE OF LOCATION AND DESIGN APPROVAL:


HUGUST 18 2017
(To be entered by State Conceptual Design

Group Manager)

#### Attachments:

- Sketch Map
- **Construction Cost Estimate**
- Notice of Location and Design Approval

#### ATTACHMENT 1: PROJECT LOCATION MAP



Project: STP00-0000-00(475) P.I. No.: 0000475

Description: Widening of SR 133 from 1,500 feet north of SR 112 in Worth County to 1,600 feet north of County Line Road (CR 417 in Worth/CR 459 in Dougherty)

DATE : 07/18/2017

PAGE: 1

#### JOB DETAIL ESTIMATE

\_\_\_\_\_\_

JOB NUMBER: 0000475 PFPR SPEC YEAR: 13

DESCRIPTION: SR 133 FROM N OF SR 112 TO N OF CR 417/CR 459 S COUNTY LINE

WORTH AND DOUGHERTY COUNTIES

#### ITEMS FOR JOB 0000475\_PFPR

0070 456-2015 GLM INDENT. RUMB. STRIPS - GRND-IN-PL 8.000 1210.70 9 (SKIP)  0074 500-3201 CY CL B CONC, RET WALL 100.000 687.96 68 0075 550-1180 LF STM DR PIPE 18,H 1-10 7720.000 33.58 259 0080 550-1240 LF STM DR PIPE 24,H 1-10 1570.000 43.67 68 0085 550-1300 LF STM DR PIPE 30,H 1-10 820.000 53.58 43	0005 0010					
0055       413-0750       GL       TACK COAT       11300.000       3.00       33         0059       432-0208       SY       MILL ASPH CONC PVMT/2 DEP       7620.000       2.00       15         0060       433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90		150-1000 LS	TRAFFIC CONTROL - 0000475	1.000	325000.00	325000.00
0055       413-0750       GL       TACK COAT       11300.000       3.00       33         0059       432-0208       SY       MILL ASPH CONC PVMT/2 DEP       7620.000       2.00       15         0060       433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90	0015	153-1300 EA	FIELD ENGINEERS OFFICE TP 3	1.000	96074.68	96074.68
0055       413-0750       GL       TACK COAT       11300.000       3.00       33         0059       432-0208       SY       MILL ASPH CONC PVMT/2 DEP       7620.000       2.00       15         0060       433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90		201-1500 LS	CLEARING & GRUBBING - 0000475	1.000	1000000.00	1000000.00
0055       413-0750       GL       TACK COAT       11300.000       3.00       33         0059       432-0208       SY       MILL ASPH CONC PVMT/2 DEP       7620.000       2.00       15         0060       433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90	0020	205-0001 CY	UNCLASS EXCAV	117000.000	5.22	610803.18
0055       413-0750       GL       TACK COAT       11300.000       3.00       33         0059       432-0208       SY       MILL ASPH CONC PVMT/2 DEP       7620.000       2.00       15         0060       433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90	0025	206-0002 CY	BORROW EXCAV, INCL MATL	155400.000	7.43	1156093.64
0055       413-0750       GL       TACK COAT       11300.000       3.00       33         0059       432-0208       SY       MILL ASPH CONC PVMT/2 DEP       7620.000       2.00       15         0060       433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90	0029	208-0100 CY	IN PLACE EMBANKMENT	272400.000	9.81	2673085.72
0055       413-0750       GL       TACK COAT       11300.000       3.00       33         0059       432-0208       SY       MILL ASPH CONC PVMT/2 DEP       7620.000       2.00       15         0060       433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90	0030	310-1101 TN	GR AGGR BASE CRS, INCL MATL	41100.000	25.22	1036557.21
0055       413-0750       GL       TACK COAT       11300.000       3.00       33         0059       432-0208       SY       MILL ASPH CONC PVMT/2 DEP       7620.000       2.00       15         0060       433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90	0034	402-1802 TN	RECYL AC PATCHING, INCL BM&HL	1600.000	104.11	166588.21
0055       413-0750       GL       TACK COAT       11300.000       3.00       33         0059       432-0208       SY       MILL ASPH CONC PVMT/2 DEP       7620.000       2.00       15         0060       433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90	0035	402-1812 TN	RECYL AC LEVELING, INC BM&HL	3000.000	80.61	241852.68
0055       413-0750       GL       TACK COAT       11300.000       3.00       33         0059       432-0208       SY       MILL ASPH CONC PVMT/2 DEP       7620.000       2.00       15         0060       433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90	0040	402-3121 TN	RECYL AC 25MM SP, GP1/2, BM&HL	27600.000	65.92	1819495.22
0055       413-0750       GL       TACK COAT       11300.000       3.00       33         0059       432-0208       SY       MILL ASPH CONC PVMT/2 DEP       7620.000       2.00       15         0060       433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90	0045	402-3130 TN	RECYL AC 12.5MM SP, GP2, BM&HL	7400.000	84.47	625083.70
0055       413-0750       GL       TACK COAT       11300.000       3.00       33         0059       432-0208       SY       MILL ASPH CONC PVMT/2 DEP       7620.000       2.00       15         0060       433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90	0050	402-3190 TN	RECYL AC 19 MM SP,GP 1 OR 2 ,INC BM&HL	9900.000	76.11	753564.14
0059 432-0208       SY       MILL ASPH CONC PVMT/ 2 DEP       7620.000       2.00       15         0060 433-1000       SY       REINF CONC APPROACH SLAB       480.000       182.90       87         0064 441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065 441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90         0069 446-1100       LF       PVMT REF FAB STRIPS, TP2,18 INCH WIDTH       8000.000       3.76       30         0070 456-2015       GLM       INDENT. RUMB. STRIPS - GRND-IN-PL       8.000       1210.70       9         (SKIP)       (SKIP)       100.000       687.96       68         0074 500-3201       CY       CL B CONC, RET WALL       100.000       687.96       68         0075 550-1180       LF       STM DR PIPE 18,H 1-10       7720.000       33.58       259         0080 550-1240       LF       STM DR PIPE 24,H 1-10       1570.000       43.67       68         0085 550-1300       LF       STM DR PIPE 30,H 1-10       820.000       53.58       43	0055	413-0750 GL	TACK COAT	11300.000	3.00	33900.00
0060 433-1000 SY REINF CONC APPROACH SLAB 480.000 182.90 87 0064 441-0740 SY CONC MEDIAN, 4 IN 700.000 40.91 28 0065 441-3999 LF CONCRETE V GUTTER 4820.000 18.78 90 0069 446-1100 LF PVMT REF FAB STRIPS, TP2,18 INCH WIDTH 8000.000 3.76 30  0070 456-2015 GLM INDENT. RUMB. STRIPS - GRND-IN-PL 8.000 1210.70 9 (SKIP) 0074 500-3201 CY CL B CONC, RET WALL 100.000 687.96 68 0075 550-1180 LF STM DR PIPE 18,H 1-10 7720.000 33.58 259 0080 550-1240 LF STM DR PIPE 24,H 1-10 1570.000 43.67 68 0085 550-1300 LF STM DR PIPE 30,H 1-10 820.000 53.58 43		432-0208 SY	MILL ASPH CONC PVMT/ 2 DEP	7620.000	2.00	15240.00
0064       441-0740       SY       CONC MEDIAN, 4 IN       700.000       40.91       28         0065       441-3999       LF       CONCRETE V GUTTER       4820.000       18.78       90         0069       446-1100       LF       PVMT REF FAB STRIPS, TP2,18 INCH WIDTH       8000.000       3.76       30         0070       456-2015       GLM       INDENT. RUMB. STRIPS - GRND-IN-PL       8.000       1210.70       9         0074       500-3201       CY       CL B CONC, RET WALL       100.000       687.96       68         0075       550-1180       LF       STM DR PIPE 18,H 1-10       7720.000       33.58       259         0080       550-1240       LF       STM DR PIPE 24,H 1-10       1570.000       43.67       68         0085       550-1300       LF       STM DR PIPE 30,H 1-10       820.000       53.58       43		433-1000 SY	REINF CONC APPROACH SLAB	480.000	182.90	87793.60
0065 441-3999		441-0740 SY	CONC MEDIAN, 4 IN	700.000	40.91	28639.58
0069 446-1100		441-3999 LF	CONCRETE V GUTTER	4820.000	18.78	90524.52
0070 456-2015 GLM INDENT. RUMB. STRIPS - GRND-IN-PL 8.000 1210.70 9 (SKIP) 0074 500-3201 CY CL B CONC, RET WALL 100.000 687.96 68 0075 550-1180 LF STM DR PIPE 18,H 1-10 7720.000 33.58 259 0080 550-1240 LF STM DR PIPE 24,H 1-10 1570.000 43.67 68 0085 550-1300 LF STM DR PIPE 30,H 1-10 820.000 53.58 43		446-1100 LF				
0074       500-3201       CY       CL B CONC, RET WALL       100.000       687.96       68         0075       550-1180       LF       STM DR PIPE 18,H 1-10       7720.000       33.58       259         0080       550-1240       LF       STM DR PIPE 24,H 1-10       1570.000       43.67       68         0085       550-1300       LF       STM DR PIPE 30,H 1-10       820.000       53.58       43	0070	456-2015 GLM	<pre>INDENT. RUMB. STRIPS - GRND-IN-PL (SKIP)</pre>	8.000	1210.70	9685.60
0075       550-1180       LF       STM DR PIPE 18,H 1-10       7720.000       33.58       259         0080       550-1240       LF       STM DR PIPE 24,H 1-10       1570.000       43.67       68         0085       550-1300       LF       STM DR PIPE 30,H 1-10       820.000       53.58       43	0074	500-3201 CY	CL B CONC, RET WALL	100.000	687.96	68796.71
0080 550-1240 LF STM DR PIPE 24,H 1-10 1570.000 43.67 68 0085 550-1300 LF STM DR PIPE 30,H 1-10 820.000 53.58 43	0075	550-1180 LF	STM DR PIPE 18,H 1-10	7720.000	33.58	259258.52
0085 550-1300 LF STM DR PIPE 30,H 1-10 820.000 53.58 43	0080	550-1240 LF	STM DR PIPE 24,H 1-10	1570.000	43.67	68562.45
	0085	550-1300 LF	STM DR PIPE 30,H 1-10	820.000	53.58	43936.15
0090 550-1360 LF STM DR PIPE 36,H 1-10 440.000 72.00 31	0090	550-1360 LF	STM DR PIPE 36,H 1-10	440.000	72.00	31683.17
0105 550-3318 EA SAFETY END SECTION 18,STD,4:1 44.000 669.68 29	0105	550-3318 EA	SAFETY END SECTION 18,STD,4:1	44.000	669.68	29466.24
0110 550-3324 EA SAFETY END SECTION 24,STD,4:1 4.000 788.55 3	0110	550-3324 EA	SAFETY END SECTION 24,STD,4:1	4.000	788.55	3154.21
0115 550-4218 EA FLARED END SECT 18 IN, ST DR 119.000 630.16 74	0115	550-4218 EA	FLARED END SECT 18 IN, ST DR	119.000	630.16	74989.75
0120 550-4224 EA FLARED END SECT 24 IN, ST DR 27.000 727.80 19	0120	550-4224 EA	FLARED END SECT 24 IN, ST DR	27.000	727.80	19650.73
0125 550-4230 EA FLARED END SECT 30 IN, ST DR 10.000 949.33 9	0125	550-4230 EA	FLARED END SECT 30 IN, ST DR	10.000	949.33	9493.38
0130 550-4236 EA FLARED END SECT 36 IN, ST DR 8.000 1280.25 10	0130	550-4236 EA	FLARED END SECT 36 IN, ST DR	8.000	1280.25	10242.04
0135 632-0003 EA CHANGEABLE MESS SIGN, PORT, TP 3 6.000 10457.94 62	0135	632-0003 EA	CHANGEABLE MESS SIGN, PORT, TP 3	6.000	10457.94	62747.68
0140 634-1200 EA RIGHT OF WAY MARKERS 177.000 112.43 19	0140	634-1200 EA	RIGHT OF WAY MARKERS	177.000	112.43	19901.82
0145 641-1100 LF GUARDRAIL, TP T 150.000 66.30 9	0145	641-1100 LF	GUARDRAIL, TP T	150.000	66.30	9945.90
0150 641-1200 LF GUARDRAIL, TP W 6100.000 17.77 108	0150	641-1200 LF	GUARDRAIL, TP W	6100.000	17.77	108421.89
0155 641-5001 EA GUARDRAIL ANCHORAGE, TP 1 8.000 1043.27 8		641-5001 EA	GUARDRAIL ANCHORAGE, TP 1	8.000	1043.27	8346.16
0160 641-5012 EA GUARDRAIL ANCHORAGE, TP 12 12.000 2190.91 26		641-5012 EA	GUARDRAIL ANCHORAGE, TP 12	12.000	2190.91	26290.95
0165 668-2100 EA DROP INLET, GP 1 69.000 2459.71 169		668-2100 EA	DROP INLET, GP 1	69.000	2459.71	169720.31
0170 543-9000 LS CONSTR OF BRIDGE COMPLETE - 0000475 1.000 1584000.00 1584		543-9000 LS	CONSTR OF BRIDGE COMPLETE - 0000475	1.000	1584000.00	1584000.00
0175 636-1020 SF HWY SGN, TP1MAT, REFL SH TP3 440.000 13.97 6		636-1020 SF	HWY SGN, TP1MAT, REFL SH TP3	440.000	13.97	6150.70
0180 636-1033 SF HWY SIGNS, TPIMAT, REFL SH TP 9 360.000 17.23 6		636-1033 SF	HWY SIGNS, TP1MAT, REFL SH TP 9	360.000	17.23	6202.86

DATE : 07/18/2017

PAGE : 2

#### JOB DETAIL ESTIMATE

.====			JOB DETAIL ESTIMATE			
0185	636-2070	LF	GALV STEEL POSTS, TP 7 MILEPOST SIGNS THERM PVMT MARK, ARROW, TP 2 THERM PVMT MARK, ARROW, TP 7 THERM PVMT MARK, WORD, TP 1 THERM SOLID TRAF ST 5 IN, WHI THERMO SOLID TRAF ST, 5 IN YEL THERM SOLID TRAF ST, 5 IN, WHI THERMO SKIP TRAF ST, 5 IN, WHI RAISED PVMT MARKERS TP 1 RAISED PVMT MARKERS TP 1 RAISED PVMT MARKERS TP 1 PAF PL SD PVMT MKG, 8, B/W, TP PB PRF PL SD PVMT MKG, 8, B/W, TP PB PRF PL SD PVMT MKG, 8, B/Y, TPPB STN DUMPED RIP RAP, TP 1, 24 PLASTIC FILTER FABRIC PERMANENT GRASSING AGRICULTURAL LIME FERTILIZER MIXED GRADE FERTILIZER MIXED GRADE FERTILIZER NITROGEN CONTENT PERM SOIL REINFORCING MAT EROSION CONTROL MATS, SLOPES TEMPORARY GRASSING MULCH CONSTRUCTION EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN	1550.000		 10154.48
0190	636-5100	EA	MILEPOST SIGNS	12.000	149.75	1797.09
0195	653-0120	EA	THERM PVMT MARK, ARROW, TP 2	79.000	78.36	6190.49
0200	653-0170	EA	THERM PVMT MARK, ARROW, TP 7	50.000	104.33	5216.60
0204	653-0210	EA	THERM PVMT MARK, WORD , TP 1	22.000	117.14	2577.13
0205	653-1501	LF	THERMO SOLID TRAF ST 5 IN, WHI	113700.000	0.34	38845.61
0210	653-1502	LF	THERMO SOLID TRAF ST, 5 IN YEL	51300.000	0.39	20079.33
0215	653-1704	LF	THERM SOLID TRAF STRIPE, 24, WH	41300.000	5.31	219675.11
0220	653-3501	GLF	THERMO SKIP TRAF ST, 5 IN, WHI	48800.000	0.25	12521.10
0225	654-1001	EA	RAISED PVMT MARKERS TP 1	128-000	4.19	536 92
0230	654-1003	EA	RAISED PVMT MARKERS TP 3	1850.000	3 56	6594 20
0235	657-1085	LF	PRF PL SD PVT MKG.8.B/W.TP PB	600.000	7 29	4376 55
0240	657-3085	GLF	PRE PL SK PVMT MKG.8.B/W.TPPB	600.000	5 20	3121 90
0245	657-6085	LF	PRE PL SD PVMT MKG.8.B/Y.TPPB	600.000	6.88	4120 10
0250	603-2024	SY	STN DIMPED RIP RAP. TP 1. 24	1500.000	77.65	116490 95
0255	603-7000	SY	PLASTIC FILTER FARRIC	1500.000	17.05	6514 05
0260	700-6910	AC	PERMANENT CRASSING	76.000	1001 51	0314.03
0265	700-7000	TN	ACRICULTURAL TIME	76.000	0.62	02193.00
0203	700-7000	TN	PEDETITOED MIVED CDADE	350.000	9.02	3368.43
0275	700-8000	TD	PERTITIZER MIKED GRADE	23.000 E700 000	007.76	15194.02
0273	710-8100	TD	PERMICAL DEINEORGING MAR	3700.000	2.42	13/99.8/
0200	716-2000	51	FERM SOIL REINFORCING MAT	2000.000	3.84	7680.00
0285	716-2000	51	EROSION CONTROL MATS, SLOPES	12100.000	1.35	16358.35
0290	163-0232	AC	TEMPORARI GRASSING	38.000	144.10	5475.91
0295	163-0240	TN	MULCH	1200.000	151.48	181777.38
0300	163-0300	EA	CONSTRUCTION EXIT	14.000	1520.41	21285.80
0305	163-0503	ΕA	CONSTR AND REMOVE SILT CONTROL GATE, TP	30.000	429.05	12871.58
0310	163-0520	LF	CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN	850.000	17.84	15170.29
0315	163-0528	LF	CONSTR AND REM FAB CK DAM -TP C SLT FN	7000.000	5.07	35504.21
		EA	CONSTR & REM SEDIMENT BASIN, TP 1, STA		13865.67	
0325	163-0550	EΔ	CONS & REM INLET SEDIMENT TRAP	75 000	189 42	1/206 63
0330	165-0030	T.F	MAINT OF TEMP STIT FENCE. TP C	25000 000	0.25	6474 25
0335	165-0041	T.F	MAINT OF CHECK DAMS - ALL TYPES	3500.000	1 27	4459 07
0333	165-0060	EΣ	NO- 0000475 CONS & REM INLET SEDIMENT TRAP MAINT OF TEMP SILT FENCE, TP C MAINT OF CHECK DAMS - ALL TYPES MAINT OF TEMP SEDIMENT BASIN,STA NO -	16.000	1657 02	26512 50
0340	103 0000	DA	MAINI OF TEMP SEDIMENT BASIN, STA NO -	10.000	1637.03	26312.39
0345	165-0087	EA	MAINT OF SILT CONTROL GATE, TP 3	30.000	97.94	2938.39
0350	165-0101	EA	MAINT OF CONST EXIT	14.000	496.41	6949.85
0355	165-0105	EA	MAINT OF INLET SEDIMENT TRAP	75.000	47.90	3592.98
0360	167-1000	EA	MAINT OF SILT CONTROL GATE, TP 3 MAINT OF CONST EXIT MAINT OF INLET SEDIMENT TRAP WATER QUALITY MONITORING AND SAMPLING	6.000	385.37	2312.23
0365	167-1500	MO	WATER QUALITY INSPECTIONS	24.000	848.33	20360.13
0370	171-0030	LF	WATER QUALITY INSPECTIONS TEMPORARY SILT FENCE, TYPE C	50000.000	3.77	188967.50
ITEM	TOTAL TED ITEM TOTAL					14789207.28 14789207.28
TOTAL	s for Job 0000475	_PFPR				
	ATED COST:					14789207 3

ESTIMATED COST: 14789207.32

CONTINGENCY PERCENT ( 0.0 ):

0.00

STATE HIGHWAY AGENCY

DATE : 07/18/2017

PAGE : 3

JOB DETAIL ESTIMATE

	=									
ESTIMATED TOTAL:										

#### NOTICE OF LOCATION AND DESIGN APPROVAL

# STP00-000-00(475) WORTH AND DOUGHERTY COUNTY P. I. 0000475

Notice is hereby given in compliance with Georgia Code 22-2-109 and 32-3-5 that the Georgia Department of Transportation has approved the Location and Design of this project.

The date of location and design approval is: August 18, 2017.

This project is located in Worth County (79%) and Dougherty County (21%), 15.5 miles southeast of the city of Albany. This project is located in Land Lots 182, 183, 185, 186 & 230 of Land District 7 for Worth County and Land Lots 18, 19 & 231 in Land District 1 for Dougherty County.

Project No. STP00-000-00(475) is an 3.47 mile widening of SR 133 from an existing two-lane (24-ft) roadway to a four-lane roadway (two 12-ft lanes in each direction) with a design speed of 65 mph. The widened typical section includes a 32-foot depressed median, 10-foot outside shoulder, and a 6-foot inside shoulder.

Drawings or maps or plats of the proposed project, as approved, are on file and are available for public inspection at the Georgia Department of Transportation:

Derrick Wilkerson District 4 Area 5 dwilkerson@dot.ga.gov 2060 Newton Road Moultrie, GA 31788 229-430-4198

Any interested party may obtain a copy of the drawings or maps or plats or portions thereof by paying a nominal fee and requesting in writing to:

Kimberly Nesbitt
State Program Delivery Administrator
Attn: Christy Lovett
clovett@dot.ga.gov
Georgia Department of Transportation
One Georgia Center, 25TH Floor
Atlanta, Georgia 30308
404-360-4824

Any written request or communication in reference to this project or notice SHOULD include the Project and P. I. Numbers as noted at the top of this notice.