DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA

OFFICE OF DESIGN POLICY & SUPPORT INTERDEPARTMENTAL CORRESPONDENCE

FILE P.I.# 0000519

OFFICE Design Policy & Support

STP00-0000-00(519)

Worth County

GDOT District 4 - Tifton

DATE 8/18/2017

SR 133 from North of Colquitt County Line

to North of SR 112-

Widening & Improvements

FROM

for Brent Story, State Design Policy Engineer

TO SEE DISTRIBUTION

SUBJECT APPROVED LOCATION & DESIGN REPORT

Attached is the approved Location and Design Report with Notice of Location & Design Approval for the above subject project.

Attachment

DISTRIBUTION:

Hiral Patel, Director of Engineering

Joe Carpenter, Director of P3

Albert Shelby, Director of Program Delivery

Darryl VanMeter, Assistant Director of P3/State Innovative Delivery Administrator

Kim Nesbitt, Program Delivery Administrator

Bobby Hilliard, Program Control Administrator

Cindy VanDyke, State Transportation Planning Administrator

Eric Duff, State Environmental Administrator

Bill DuVall, State Bridge Engineer

Andrew Heath, State Traffic Engineer

Angela Robinson, Financial Management Administrator

Lisa Myers, State Project Review Engineer

Andy Casey, State Roadway Design Engineer

Attn: Joshua Taylor, Design Group Manager

Benny Walden, Statewide Location Bureau Chief

Ritchie Swindell, District Engineer

Brent Thomas, District Preconstruction Engineer

Dennis Carter, District Planning & Programming Engineer

Derrick Wilkerson, Area Engineer - D4, A5

Christy Lovett, Project Manager

BOARD MEMBER - 8th Congressional District

Rec'd: 8-2-2017

DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA

INTERDEPARTMENT CORRESPONDENCE

FILE

STP00-0000-00(519), Worth County

OFFICE

Program Delivery

P.I. No. 0000519

SR 133 FM N of Colquitt Co line to N of SR 112

DATE

July 17, 2017

FROM

Kimberly Nesbitt., State Program Delivery Administrator

TO

Office of Design Policy and Support (via Concepts Reports mailbox)

SUBJECT: Submittal - Location and Design (L&D) Report

The Office of Program Delivery hereby submits the attached Location and Design (L&D) Report for your review and approval.

If any additional information is needed, please contact Christy Lovett at 912-530-4420.

AVS:CLB:DGM:CSL

Attachments: Preconstruction Status Report, Completed Location & Design approval request

DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA

LOCATION AND DESIGN REPORT

FILE 0000519

OFFICE Program Delivery

STP00-0000-00(519) Worth County

DATE July 13, 2017

SR 133 FM N of Colquitt Co line to N of SR 112

FROM Kimberly Nesbitt, State Program Delivery Administrator

TO Brent Story, State Design Policy Engineer
Attn: Dave Peters, State Conceptual Design Group Manager

SUBJECT Request for Location and Design Approval

Description and Project Proposal: This project consists of widening and reconstruction of 7.55 miles of SR 133 from the existing two lane road to a 2 lane divided road. The project begins immediately north of the Colquitt County Line approximately 3 miles north of Doerun and ends 0.75 miles North of SR 112 approximately 2 miles north east of Bridgeboro. The project lies entirely within Worth County.

The design speed will be 65 mph from the beginning to the end of the project.

The typical section will be a typical rural section with 12' lanes, 10' shoulders, and 32' median on the main alignment.

Concept Approval Date: Concept March 5, 2007 and Revised Concept May 21, 2011

Concept Update: N/A

Environmental Document: This is a state-funded project and does not require a GEPA document.

Public Involvement:

- Public Information Open House was held August 11, 2016 at two locations: Doerun Elementary School and Okapilco Elementary School
- The PIOHs were for PI No. 0000473, 0000475, 0000519, and 0000520 Colquitt, Dougherty and Worth Co
- A total of 306 people attended the open houses for all four projects. Of the 237 respondents who formally commented, 81 were in support of the projects, 19 were opposed, 8 were uncommitted, and 72 expressed conditional support.

"Relocating the existing SR 133 and Old Albany Road intersection would place the new intersection with a hill to the left, which would not allow drivers the opportunity to see approaching vehicles."

"What happens to the roadway that is proposed to be abandoned (Old Albany Road near the SR 133 intersection)?"

o "I support what you currently propose for the SR 112/SR 133 intersection."

o "I do not believe a concrete median at SR 112 and SR 133 is safer. I would like to see a study performed to determine the safest options for the SR 112/SR 133 intersection."

o "The intersection of SR 112 and SR 133 needs a traffic light and a slower speed limit."

Consistency with Approved Planning: The design description as presented herein and submitted for approval is consistent with the approved Concept Report.

Recommendations: Recommend that the location and design for the project be approved and that the attached Notice be approved for advertising.

Approve: GDOT Chief Engineer

DATE OF LOCATION AND DESIGN APPROVAL:

To be entered by State Conceptual Design


Group Manager)

Attachments:

· sketch map

· notice

LOCATION MAP



Project: STP00-0000-00(519) P.I. No.: 0000519

Description: Widening of SR 133 from 2,000 feet north of the Colquitt/Worth County line to 1,500 feet north of SR 112 in Worth County

Construction Cost Estimate

Job ID: 0000519 Time Processed: May-17-2017 02:45:49 PM FED/STATE STP00-0000-00(519) PROJECT NUMBER: JOB NUMBER: 0000519 SPEC YEAR: ALL_2016Q4_24MO HISTORY: DESCRIPTION: SR133 FM NORTH OF COLQUITT COUNTY LINE TO NORTH OF SR 112 OFFICE OF ROADWAY DESIGN ITEMS FOR JOB 0000519 0010 - ROADWAY ITEMS \$32.54805 STM DR PIPE 18,H 1-10 \$362,585.28 550-1180 | 11140.00 LF 0005 \$44.13441 STM DR PIPE 24,H 1-10 550-1240 1420.00 LF 0010 \$51.95643 STM DR PIPE 30,H 1-10 550-1300 \$36,889.07 0020 550-1360 710.00 LF \$69 69654 STM DR PIPE 36 H 1-10 \$49,484,54 \$26,700.96 0025 550-4218 46.00 EA \$580,45565 FLARED END SECT 18 IN. ST DR \$732.17206 FLARED END SECT 24 IN, ST DR \$17,572.13 0030 550-4224 24.00 EA 550-4230 0035 12.00 \$836.54870 FLARED END SECT 30 IN, ST DR \$10,038.58 0040 550-4236 12.00 EA \$1,265.22975 FLARED END SECT 36 IN, ST DR \$15,182,76 0045 668-2100 134,00 EA \$2,373,82333 DROP INLET, GP 1 \$318,092.33 \$29.41723 SIDE DR PIPE 18,H 1-10 \$89,428.38 0050 550-2180 3040.00 LF \$32.93187 SIDE DR PIPE 24,H 1-10 \$25,028.22 0055 550-2240 0060 550-3618 122.00 EA \$489,48043 SAFETY END SECTION 18,SD,6:1 \$59,716,61 \$22,400.00 0065 550-3624 32.00 EA \$700,00000 SAFETY END SECTION 24.SD.6:1 \$70.99330 RECYL AC 25MM SP,GP1/2,BM&HL \$694,456.46 0075 402-3121 9782.00 TN 8584.00 TN \$76.88359 RECYL AC 19 MM SP,GP 1 OR 2 ,INC BM&HL \$659,968,74 0085 402-3130 6412.00 TN \$84.05782 RECYL AC 12.5MM SP,GP2,BM&HL \$538 978 74 \$38,205.00 0090 413-0750 13500.00 GL \$2.83000 TACK COAT \$23,005.07 \$27.38699 AGGR SURF CRS 0095 318-3000 840.00 TN \$16.61144 GUARDRAIL, TP W \$94,685.21 0100 641-1200 5700.00 LF 641-5001 16.00 EA \$962.03704 GUARDRAIL ANCHORAGE, TP 1 \$15 392 59 0110 641-5012 16.00 EA \$2,231,11855 GUARDRAIL ANCHORAGE, TP 12 \$35,697.90 \$850,000.00 \$850,000,00000 TRAFFIC CONTROL - STP00-0000-00(519) 0115 150-1000 1.00 LS 153-1300 \$96,074.68000 FIELD ENGINEERS OFFICE TP 3 \$96,074.68 1.00 EA 0120 201-1500 1.00 LS \$3,500,000.00000 CLEARING & GRUBBING - STP00-0000-00(519) \$3,500,000.00 0125 0130 634-1200 180.00 EA \$112 33666 RIGHT OF WAY MARKERS \$20,220,60 \$8,054.84253 CHANGEABLE MESS SIGN, PORT, TP 3 \$16,109.69 0135 632-0003 2.00 EA \$885,126.90 205-0001 169547.00 CY \$5.22054 UNCLASS EXCAV 0140 \$7.43947 BORROW EXCAV, INCL MATL 206-0002 182688.00 CY \$1,359,101.90 0150 643-8200 4006 00 LE \$1.52766 BARRIER FENCE (ORANGE), 4 FT \$6,119,81 \$214,029.13 0155 441-3999 12500.00 LF \$17.12233 CONCRETE V GUTTER \$4,788,008.94 310-5080 353653.00 SY \$13.53872 GR AGGR BS CRS 8IN INCL MATL 0395 430-0200 317127.00 SY \$42.50000 PLN PC CONC PVMT/CL1C/ 10 TK \$13,477,897,50 0405 310-5100 17528.00 SY \$17.82883 GR AGGR BS CRS 10IN INCL MATL \$312,503,73 \$456,747.38 0410 310-5060 42046.00 SY \$10.86304 GR AGGR BS CRS 6IN INCL MATL \$29,178,119.69 ROADWAY ITEMS Total 0020 - SIGNING/MARKING \$10,821.36 636-1020 760.00 SF \$14.23863 HWY SGN,TP1MAT,REFL SH TP3 0160 0165 636-1033 1710.00 SF \$16.80002 HWY SIGNS, TP1MAT, REFL SH TP 9 \$28,728.03 0170 636-1041 1140.00 SF \$36,43979 HWY SIGNS,TP 2MAT,REFL SH TP 9 \$41.541.36 \$27,300.47 0175 636-2070 4340.00 LF \$6,29043 GALV STEEL POSTS, TP 7 \$4,363.06 \$9.48491 GALV STEEL POSTS, TP 8 0180 636-2080 460.00 LF \$4.76069 RAISED PVMT MARKERS TP 1 \$523.68 0185 654-1001 110.00 0190 654-1003 1010.00 EA \$5.11675 RAISED PVMT MARKERS TP 3 \$5.167.92 0195 653-0120 61.00 EA \$75,54184 THERM PVMT MARK, ARROW, TP 2 \$4,608.05

\$115.71149 THERM PVMT MARK, ARROW, TP 7

\$107.19706 THERM PVMT MARK, WORD , TP 1

653-0170

653-0210

12.00 EA

8.00 EA

0200

0205

\$1,388.54

\$857.58

0210	Item	Quantity	Units	Price	Description	Amount
	653-6004	2850.00	SY	\$4.23175	THERM TRAF STRIPING, WHITE	\$12,060.49
0215	653-1501	88132.00	LF	\$0.28153	THERMO SOLID TRAF ST 5 IN, WHI	\$24,811.80
0220	653-1502	88132.00	LF	\$0.35986	THERMO SOLID TRAF ST, 5 IN YEL	\$31,715.18
0225	653-1704	3040.00	LF	\$6.33593	THERM SOLID TRAF STRIPE,24,WH	\$19,261.23
0230	653-3501	80120.00	GLF	\$0.23176	THERMO SKIP TRAF ST, 5 IN, WHI	\$18,568.61
0235	636-5100	16.00	EA	\$149.75734	MILEPOST SIGNS	\$2,396.12
SIGNING/MAR	KING Total					\$234,113.48
0030 - PERM	A EROSION	CONTROL				
Line Number	Item	Quantity	Units	Price	Description	Amount
0240	700-6910	120.00			PERMANENT GRASSING	\$57,601.99
0245	700-7000	360.00	TN	\$9.74121	AGRICULTURAL LIME	\$3,506.84
0250	700-8000	72.00	TN		FERTILIZER MIXED GRADE	\$47,844.92
0255	700-8100	6000.00	LB	\$2,46654	FERTILIZER NITROGEN CONTENT	\$14,799.24
0260	163-0240	360.00	-	\$193,63546		\$69,708,77
0270	716-2000	25300.00	SY	\$1,10003	EROSION CONTROL MATS, SLOPES	\$27,830.76
0275	603-2024	1590.00	-	-	STN DUMPED RIP RAP. TP 1, 24	\$85,076.70
0280	603-7000		-		PLASTIC FILTER FABRIC	\$5,819.15
0390	711-0100	4500.00	-		TURF REINFORCING MATTING, TP 1	\$15,750.00
PERM EROSIC			1			\$327,938.37
0040 - TEMP						
Line Number	Item	Quantity	Holte	Price	Description	Amount
0285	163-0232	the second second second	AC	\$234,19131		\$14,051.48
0290	700-8000		TN	\$623.90591		\$7,486.87
0295	163-0240	12.00				47,400.07
		1920.00	TN	\$138 01301		\$264 984 98
			TN	\$138.01301		\$264,984.98 \$50,028.54
0300	163-0300	31.00	EA	\$1,613.82389	CONSTRUCTION EXIT	\$50,028.54
0300 0305	163-0300 165-0101	31.00 31.00	EA EA	\$1,613.82389 \$661.40324	CONSTRUCTION EXIT	\$50,028.54 \$20,503.50
0300 0305 0310	163-0300 165-0101 163-0503	31.00 31.00 130.00	EA EA	\$1,613.82389 \$661.40324 \$388.03359	CONSTRUCTION EXIT MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3	\$50,028.54 \$20,503.50 \$50,444.37
0300 0305 0310 0315	163-0300 165-0101 163-0503 165-0087	31.00 31.00 130.00 130.00	EA EA EA	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160	CONSTRUCTION EXIT MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31
0300 0305 0310 0315 0320	163-0300 165-0101 163-0503 165-0087 163-0520	31.00 31.00 130.00 130.00 1900.00	EA EA EA LF	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160 \$16.39023	CONSTRUCTION EXIT MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31
0300 0305 0310 0316 0320 0325	163-0300 165-0101 163-0503 165-0087 163-0520 163-0550	31.00 31.00 130.00 130.00 1900.00 134.00	EA EA EA LF EA	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160 \$16.39023 \$184.05623	CONSTRUCTION EXIT I MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE,TP 3 MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONS & REM INLET SEDIMENT TRAP	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31 \$31,141.44 \$24,663.53
0300 0305 0310 0316 0320 0325 0330	163-0300 165-0101 163-0503 165-0087 163-0520 163-0550 165-0105	31.00 31.00 130.00 130.00 1900.00 134.00	EA EA EA LF EA	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160 \$16.39023 \$184,05623 \$83,77671	CONSTRUCTION EXIT I MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONS & REM INLET SEDIMENT TRAP MAINT OF INLET SEDIMENT TRAP	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31 \$31,141.44 \$24,663.53 \$11,226.08
0300 0305 0310 0316 0320 0325 0330 0335	163-0300 165-0101 163-0503 165-0087 163-0520 163-0550 165-0105 167-1000	31.00 31.00 130.00 130.00 1900.00 134.00 134.00	EA EA EA LF EA EA	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160 \$16.39023 \$184.05623 \$83.77671 \$365.37151	CONSTRUCTION EXIT MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONS & REM INLET SEDIMENT TRAP WAITH OF INLET SEDIMENT TRAP WATER QUALITY MONITORING AND SAMPLING	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31 \$31,141.44 \$24,663.53 \$11,226.08
0300 0305 0310 0315 0320 0325 0330 0335 0340	163-0300 165-0101 163-0503 165-0087 163-0520 163-0550 165-0105 167-1000 167-1500	31.00 31.00 130.00 130.00 1900.00 134.00 10.00 30.00	EA EA EA LF EA EA EA MO	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160 \$16.39023 \$184.05623 \$83.77671 \$365.37151	CONSTRUCTION EXIT MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN MAINT OF INLET SEDIMENT TRAP WATER QUALITY MONITORING AND SAMPLING WATER QUALITY MONITORING AND SAMPLING	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31 \$31,141.44 \$24,663.53 \$11,226.08 \$3,853.72 \$31,177.14
0300 0305 0310 0315 0320 0325 0330 0335 0340	163-0300 165-0101 163-0503 165-0087 163-0520 163-0550 165-0105 167-1000 167-1500	31.00 31.00 130.00 130.00 1900.00 134.00 10.00 30.00 92.00	EA EA EA LF EA EA EA MO EA	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160 \$16.39023 \$184.05623 \$83.77671 \$335.37151 \$1,039.23807 \$313.24170	CONSTRUCTION EXIT I MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONS & REM INLET SEDIMENT TRAP MAINT OF INLET SEDIMENT TRAP WATER QUALITY MONITORING AND SAMPLING WATER QUALITY INSPECTIONS CNSTREM RIP RAP CKDM, STN P RIPRAP/SN BG	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31 \$31,141.44 \$24,663.53 \$11,226.08 \$3,853.72 \$31,177.14
0300 0305 0310 0315 0320 0325 0330 0330 0335 0340	163-0300 165-0101 163-0503 165-0087 163-0520 163-0550 165-0105 167-1000 167-1500 163-0527	31.00 31.00 130.00 130.00 1900.00 134.00 10.00 30.00 92.00 12900.00	EA EA LF EA EA EA LF EA EA LA EA LF EA LF EA LF EA LF EA LF	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160 \$16.39023 \$184.05623 \$83.77671 \$365.37151 \$1,039.23807 \$313.24170	CONSTRUCTION EXIT I MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONS & REM INLET SEDIMENT TRAP WATER QUALITY MONITORING AND SAMPLING WATER QUALITY INSPECTIONS CNSTREM RIP RAP CKDM, STN P RIPRAP/SN BG CONSTR AND REM FAB CK DAM-TP C SLT FN	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31 \$31,141.44 \$24,663.53 \$11,226.08 \$3,853.72 \$31,177.14 \$28,818.24 \$55,639.92
0300 0305 0310 0316 0320 0325 0330 0335 0340 0346	163-0300 165-0101 163-0503 165-0087 163-0520 163-0550 165-0105 167-1000 167-1500 163-0527 163-0528 165-0041	31.00 31.00 130.00 130.00 1900.00 134.00 10.00 30.00 92.00 12900.00 7370.00	EA EA EA LF EA EA EA LF EA LF EA LF LF LF LF	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160 \$16.39023 \$184.05623 \$83.77671 \$365.37151 \$1,039.23807 \$313.24170 \$4,54573 \$1,59551	CONSTRUCTION EXIT MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN MAINT OF INLET SEDIMENT TRAP WATER QUALITY MONITORING AND SAMPLING WATER QUALITY MONITORING AND SAMPLING WATER QUALITY INSPECTIONS CONSTR AND REM FAB C KDMTP C SLT FN MAINT OF CHECK DAMS - ALL TYPES	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31 \$31,141.44 \$24,663.53 \$11,226.08 \$3,563.72 \$31,177.14 \$28,818.24 \$56,639.92 \$11,756.91
0300 0305 0316 0315 0320 0322 0330 0335 0340 0346 0350 0350	163-0300 165-0101 163-0503 165-0087 163-0520 163-0550 165-0105 167-1000 167-1500 163-0527 163-0528 165-0041 163-0531	31.00 31.00 130.00 130.00 1900.00 134.00 134.00 10.00 92.00 12900.00 7370.00	EA EA EA LF EA EA EA LF EA LF LF LF LF EA	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160 \$16.39023 \$184.05623 \$83.77671 \$365.37151 \$1,039.23807 \$313.24170 \$4,54573 \$1,59551	CONSTRUCTION EXIT MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN MAINT OF INLET SEDIMENT TRAP MAINT OF INLET SEDIMENT TRAP WATER QUALITY MONTORING AND SAMPLING WATER QUALITY MONTORING AND SAMPLING CONSTREM RIP RAP CKDM,STH P RIPRAP/SN BG CONSTR AND REM FAB CK DAM-TP C SLT FN MAINT OF CHECK DAMS - ALL TYPES CONSTR & REM SEDIMENT BASIN,TP 1,STA NO- 2 PER MILE	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31 \$31,141.44 \$24,663.53 \$11,226.08 \$3,853.72 \$31,177.14 \$28,818.24 \$58,639.92 \$11,750.91 \$204,610.88
0300 0305 0310 0315 0320 0325 0330 0335 0340 0346 0350 0355 0360 0366	163-0300 165-0101 163-0503 165-0087 163-0520 163-0550 165-0105 167-1000 167-1500 163-0527 163-0528 165-0041 163-0531 165-0060	31.00 31.00 130.00 130.00 190.00 134.00 134.00 10.00 30.00 92.00 12900.00 15.00	EA EA EA LF EA EA MO EA LF LF LF EA EA	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160 \$16.39023 \$184.05623 \$83.77671 \$365.37151 \$1,039.23807 \$313.24170 \$4.54573 \$1.59551 \$13,640.72506 \$1,248.01426	CONSTRUCTION EXIT I MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 I MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN I CONS & REM INLET SEDIMENT TRAP MAINT OF INLET SEDIMENT TRAP WATER QUALITY MONITORING AND SAMPLING WATER QUALITY INSPECTIONS CONSTR AND REM FAB CK DAMTP C SLT FN MAINT OF CHECK DAMS - ALL TYPES CONSTR & REM SEDIMENT BASIN, TP 1, STA NO- 2 PER MILE MAINT OF TEMP SEDIMENT BASIN, STA NO -	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31 \$31,141.44 \$24,663.53 \$11,226.08 \$3,853.72 \$31,177.14 \$28,818.24 \$58,639.92 \$11,750.91 \$204,610.88 \$18,720.21
0300 0305 0316 0320 0325 0335 0335 0335 0340 0346 0350 0355 0360	163-0300 165-0101 163-0503 165-0087 163-0550 163-0550 163-0105 167-1000 167-1500 163-0527 163-0528 165-0041 163-0531 165-0060 171-0010	31.00 31.00 130.00 130.00 190.00 134.00 10.00 30.00 92.00 1290.00 737.00 15.00 22100.00	EA EA EA LF EA EA MO EA LF LF EA LF LF EA LF EA	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160 \$16.39023 \$184.05623 \$83.77671 \$385.37151 \$1,039.23807 \$4,54573 \$1,59551 \$13,640.72506 \$1,248.01426 \$2,36543	CONSTRUCTION EXIT MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONS & REM INLET SEDIMENT TRAP MAINT OF INLET SEDIMENT TRAP WATER QUALITY MONITORING AND SAMPLING WATER QUALITY INSPECTIONS CONSTR AND REM FAB CK DAM-TP C SLT FN MAINT OF CHECK DAMS - ALL TYPES CONSTR & REM SEDIMENT BASIN, TP 1,STA NO - 2 PER MILE MAINT OF TEMP SEDIMENT BASIN, TP 1,STA NO - TEMPORARY SILT FENCE, TYPE A	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31 \$31,141.44 \$24,663.53 \$11,226.08 \$3,853.72 \$31,177.14 \$28,818.24 \$56,639.92 \$11,758.91 \$204,610.88 \$18,720.21
0300 0305 0310 0316 0320 0325 0330 0336 0340 0345 0355 0360 0355 0360 0370	163-0300 165-0101 163-0503 165-0067 165-0067 163-0550 165-0105 167-1000 167-1500 163-0527 163-0528 165-0041 163-0550 165-0060 171-0010	31.00 31.00 130.00 130.00 1900.00 134.00 10.00 30.00 92.00 12900.00 7370.00 15.00 22100.00 66100.00	EA EA LF EA EA MO EA LF LF EA LF LF EA LF LF EA LF LF LF	\$1,613.82389 \$681.40324 \$388.03359 \$74.57160 \$16.39023 \$184.05623 \$83.77671 \$365.37151 \$1,039.23807 \$313.24170 \$4.54573 \$1.59551 \$13,640.72506 \$2.38543 \$3.31932	CONSTRUCTION EXIT MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONS A REM INLET SEDIMENT TRAP MAINT OF INLET SEDIMENT TRAP WATER QUALITY MONITORING AND SAMPLING WATER QUALITY MONITORING AND SAMPLING CONSTRAIND REM FASE KD AM-TP C SLT FN MAINT OF CHECK DAMS - ALL TYPES CONSTR AND REM FASE KD AM-TP C SLT FN MAINT OF CHECK DAMS - ALL TYPES CONSTR & REM SEDIMENT BASIN, TP 1,STA NO-2 PER MILE MAINT OF TEMP SEDIMENT BASIN, STA NO- TEMPORARY SILT FENCE, TYPE A TEMPORARY SILT FENCE, TYPE C	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31 \$31,141.44 \$24,663.53 \$11,226.08 \$3,563.72 \$31,177.14 \$28,818.24 \$58,639 \$11,750.91 \$204,610.88 \$18,720.21 \$32,718.00 \$219,407.05
0300 0305 0316 0320 0325 0335 0335 0335 0340 0346 0350 0355 0360	163-0300 165-0101 163-0503 165-0087 163-0550 163-0550 163-0105 167-1000 167-1500 163-0527 163-0528 165-0041 163-0531 165-0060 171-0010	31.00 31.00 130.00 130.00 190.00 134.00 10.00 30.00 92.00 1290.00 737.00 15.00 22100.00	EA EA LF EA EA MO EA LF LF EA LF LF EA LF LF LF LF LF	\$1,613.82389 \$661.40324 \$388.03359 \$74.57160 \$16.39023 \$184.05623 \$83.77671 \$385.37151 \$1,039.23807 \$4,54573 \$1,59551 \$13,640.72506 \$1,248.01426 \$2,36543	CONSTRUCTION EXIT MAINT OF CONST EXIT CONSTR AND REMOVE SILT CONTROL GATE, TP 3 MAINT OF SILT CONTROL GATE, TP 3 CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONSTR AND REMOVE TEMP PIPE SLOPE DRAIN CONSTR EXIT SEDIMENT TRAP MAINT OF INLET SEDIMENT TRAP WATER QUALITY MONITORING AND SAMPLING WATER QUALITY MONITORING AND SAMPLING CONSTREM RIP RAP CKDM,STH P RIPRAP/SNH BG CONSTR AND REM FAB CK DAM-TP C SLT FN MAINT OF CHECK DAMS - ALL TYPES CONSTR & REM SEDIMENT BASIN,TP 1,STA NO- 2 PER MILE MAINT OF TEMP SEDIMENT BASIN,STA NO- TEMPORARY SILT FENCE, TYPE A TEMPORARY SILT FENCE, TYPE C MAINT OF TEMP SILT FENCE, TYPE C	\$50,028.54 \$20,503.50 \$50,444.37 \$9,694.31 \$31,141.44 \$24,663.53 \$11,226.08 \$3,853.72 \$31,177.14 \$28,818.24 \$56,639.92 \$11,758.91 \$204,610.88 \$18,720.21

TOTALS FOR JOB 0000519

ITEMS COST:	\$30,864,311.39
	\$30,804,311.39
COST GROUP COST:	
ESTIMATED COST:	\$30,864,311.39
CONTINGENCY PERCENT:	0.00%
ENGINEERING AND INSPECTION:	5.00%
ESTIMATED COST WITH CONTINGENCY AND E&I:	\$32,407,526.96

File Location: Div of Preconstruction > CES

CONFIDENTIALITY NOTICE: This document may contain confidential and/or privileged information. Any unauthorized duplication, disclosure,

distribution/retransmission of taking of any action in reliance upon the material in this document is strictly forbidden,

NOTICE OF LOCATION AND DESIGN APPROVAL

WORTH COUNTY P. I. 0000519

Notice is hereby given in compliance with Georgia Code 22-2-109 and 32-3-5 that the Georgia Department of Transportation has approved the Location and Design of this project.

The date of location and design approval is: August 18, 2017.

This project consists of the widening and realignment of 7.55 miles segment of SR 133, which lies entirely inside Worth County, from the existing two lane road to a 2 lane divided highway. The project begins immediately north of the Colquitt County Line approximately 3 miles north of Doerun and ends 0.75 miles North of SR 112 approximately 2 miles north-east of Bridgeboro. The widening will consist mostly of adding a median and a two new lanes. Beginning at the southernmost part of the project the two new lanes will be built mostly to the east of the existing SR 133, while the existing SR 133 will be torn up and replaced, until approximately 0.44 miles south of the intersection of SR 133 and Bridgeboro Anderson Rd, at which point it will switch over to be the new lanes being built mostly on the western side of the existing SR 133. The speed limit will be 65 mph throughout the length of the project.

This project lies within Land District 8 and encompasses land in Land Lots 5, 42, 49, 50, 51, 88, 89, 97, 134, 135,141, 142, 181, 182, and 183.

Drawings or maps or plats of the proposed project, as approved, are on file and are available for public inspection at the Georgia Department of Transportation:

Derrick Wilkerson District 4 Area 5 dwilkerson@dot.ga.gov 2060 Newton Road Moultrie, GA 31788 229-430-4198

Any interested party may obtain a copy of the drawings or maps or plats or portions thereof by paying a nominal fee and requesting in writing to:

Kimberly Nesbitt
State Program Delivery Administrator
Attn: Christy Lovett
clovett@dot.ga.gov
Georgia Department of Transportation
One Georgia Center, 25TH Floor
Atlanta, Georgia 30308
1-404-360-4824

Any written request or communication in reference to this project or notice SHOULD include the Project and P. I. Numbers as noted at the top of this notice.