

Interoffice Memo Office of Design Policy & Support

DATE: 12/16/2020

FILE: P.I.# 0015605

Bulloch County / GDOT District 5 - Jesup

Bridge Replacement - CR 927/Old Hwy 46 @ Ash Branch 11.6 MI SE of Brooklet

Dane Peters

FROM: R. Christopher Rudd, PE, State Design Policy Engineer

TO: SEE DISTRIBUTION

SUBJECT: APPROVED CONCEPT REPORT

Attached is the approved Concept Report for the above subject project.

Attachment

Distribution:

Hiral Patel, Director of Engineering

Joe Carpenter, Director of P3

Albert Shelby, Director of Program Delivery

Carol Comer, Director, Division of Intermodal

Darryl VanMeter, Assistant Director of P3/State Innovative Delivery Administrator

Matthew Markham, Deputy Director of Planning

Kim Nesbitt, Program Delivery Administrator

Bobby Hilliard, Program Control Administrator

Eric Duff, State Environmental Administrator

Donn Digamon, State Bridge Engineer

Andrew Heath, State Traffic Engineer

Angela Robinson, Financial Management Administrator

Erik Rohde, State Project Review Engineer

Monica Flournoy, State Materials Engineer

Patrick Allen, State Utilities Engineer

Eric Conklin, State Transportation Data Administrator

Attn: Systems & Classification Branch

Benny Walden, Statewide Location Bureau Chief

Robert McCall, District Engineer

Troy Pittman, District Preconstruction Engineer

Dallory Rozier, District Utilities Engineer

Joshua Pisani, Project Manager

BOARD MEMBER - 12th Congressional District



Limited Scope Project Concept Report

Project Type:	Bridge Replacement	P.I. Number:	0015605
GDOT District:	5	County:	Bulloch
Federal Route Number:	N/A	State Route Number:	N/A
Project Number:	N/A	-	
CR 927/OLD HWY 46@ASH bridge on CR 927 (Old Highw Brooklet, Georgia.			-
Submitted for approval:	* Con	cept Report updated	11/13/2020
Middleton			9/16/2020
Janet Middleton, P.E., Arcadis	Kumberly W.	Nedolt	Date 9/25/2020
State Program Delivery Admir	nistrator		Date
John Rins	SHP		09-23-2020
Joshua Pisani, GDOT Project	Manager		Date
Recommendation for approve	al: * Recommend	dations are on file \sim	OB
* Eric Duff			11/09/20
State Environmental Administra	ator		Date
* Chris Raymond			10/19/20
or State Traffic Engineer			Date
* Donn Digamon			10/16/20
State Bridge Engineer			Date
* Robert McCall			10/20/20
District Engineer			Date
Range Transportation	n Plan (LRTP).	PO adopted Regional Transp	, , ,
(SWTP) and/or is incl	uded in the State Transporta	goals outlined in the Statev ation Improvement Program (
Matt Markha			10/19/2020
State Transportation Planning	Administrator		Date
Approval:	10 1		
Concur:	Wester		10/0/000
1 2000	r of Engineering		12/9/2020 Date
Approve:	g -		12/16/2020
GDOT Chief E	ngineer		Date
	<u>-</u>		

- * Recommendations were also received from the following: ~ OB
 - * Office of Engineering Services: Erik Rohde (11/10/20)


 * Office of Utilities: Marcela Coll (10/05/20)

 * Office of Intermodal: Alan C. Hood (10/16/20)

 * District 5 Preconstruction Engineer: Troy Pittman (10/20/20)

 - * Office of Planning: Tom McQueen (10/16/20)

PROJECT LOCATION MAP



CR 927/OLD HWY 46@ASH BRANCH 11.6 MI SE OF BROOKLET
PI# 0015605
BULLOCH COUNTY

Limited Scope Project Concept Report – Page 3

County: Bulloch

PLANNING & BACKGROUND DATA

Prepared By: GDOT Bridge Office Date: 11/29/2018

Project Justification Statement: The bridge on County Route 927 (Old Highway 46) over Ash Branch, Structure ID 031-0017-0 was built in 1956. The bridge consists of four steel spans on concrete caps with steel piles. The bridge was designed using an HS-20 vehicle; however, it is not meeting current standards. The deck is in satisfactory condition with transverse cracking reaching the bottom of the deck as well of evidence of the deck joints leaking. Also, spalling has been identified on some edge beams located in span 2 and 3 as well as the edge of the deck near the joints. The superstructure is in good condition with minor corrosion on all beams. There is also evidence of horizontal cracking and spalling in all end diaphragms between all beams. The substructure is in fair condition with vertical cracking on abutments. In addition, there are exposed piles due to encasement beginning to honeycomb and crumble. The exposure has caused rusting and section loss under the encasement. Scour is also evident. Due to the age of the structure, not meeting current design standards, and condition of the substructure, replacement of this bridge is recommended.

P.I. Number: 0015605

Existing conditions: The existing 108-ft length bridge is composed of steel and concrete and has a deck width of 34.1-ft with two 11-ft lanes and concrete handrails along both sides. CR 927/Old Highway 46 is a two lane, 22-ft wide rural major collector running parallel to a portion of I-16 surrounded mostly by undeveloped woodlands and farmland. There are multiple residences along the roadway. The project is located approximately 11.6 miles southeast of the City of Brooklet.

Other projects in the area:

- 1. M0005870 I-16 FROM SR 67/BULLOCH TO SR 17 CONN/CHATHAM
 - a. Project Description: This project, selected by the State Maintenance Office, is the resurfacing of SR 404 (I-16) to improve the current paces rating.
 - b. LET Date: 8-21-2020
- 2. PI 0016650 CR 151/ARCOLA ROAD @ UPPER BLACK CREEK
 - a. Project Description: The proposed project will replace the existing bridge of Arcola Road at Upper Black Creek in Bulloch County. The new bridge will be constructed on the existing alignment and an offsite detour will be implemented during construction. The total length of the project is approximately 0.14 miles.
 - b. LET Date: 6-19-2020
- 3. PI 0013803 SR 26 OVER CANEY BRANCH
 - a. Project Description: This project is located on State Route 26 (US 80) over Caney Branch in Bulloch County, 13 miles southeast of Brooklet, Georgia. Proposed is a new quadruple concrete bridge culvert over Caney Branch that will be constructed at the current location, elevation, and roadway centerline using a 55mph design speed. The total length of the project is approximately 525 feet (0.099 miles). During construction, an off-site detour will be utilized to route traffic to SR 119C. The total detour route distance is 11.8 miles.

b. LET Date: 2-21-2020

MPO: N/A - not in an MPO **TIP #**: N/A

Congressional District(s): 12

Federal Oversight: ☐ PoDI ☐ Exempt ☐ State Funded ☐ Other

Projected Traffic: 24 HR T: 7.5 % Current Year (2018): 800

Open Year (2023): <u>850</u> Design Year (2043): <u>1050</u>

Date approved by the GDOT Office of Planning: 8/19/2020

AASHTO Functional Classification (Mainline): Major Collector

AASHTO Context Classification (Mainline): Rural

AASHTO Project Type (Mainline): Construction on existing roads

County: Bulloch				
Is the project lo	cated on a NHS roadway?	⊠ No □ Yes		
Complete Street	ts - Bicycle, Pedestrian, and/or	Transit Standard	s Warrants:	
Warrants	s met: ☐ None ⊠ Bicycle	☐ Pedestrian	☐ Transit	
Standard 1 The project	ect is on a designated state bicycl	e route:		
	CR 927/OLD HWY 46 – State Bicy			
	e existing bikeways along the proj	•		
	e bicycle travel generators and de cle crash occurred in 2017. Howe	• .	-	rted hicycle crashes
-	uals or exceeds a rate of five for a			_
(2015 – 2	2019).			
Guideline				
	ect is not within close proximity of	a school, college,	university, or major	public institution.
	ect will provide connectivity betwe	en two or more ex	disting bikeways or d	connects to an existing
bikeway. 3. This proi	ect does not have an occurrence	of bicvcle crashes	i.	
4. Along the	e project corridor, there are bicycle			be expected prior to
-	n year of the project.	d fambiovala acca		
5. Engineer	ring judgment does indicate a nee	d for bicycle acco	mmodation.	
•	arrants are met. 6.5-ft paved shoul	lders will be provi	ded along the roadw	ay, 6-ft shoulders will be
provided on the b	oridge.			
Pavement Evalu	ation and Recommendations			
Initial Pa	vement Evaluation Summary Rep	ort Required?	⊠ No	☐ Yes
Feasible	Pavement Alternatives:	\boxtimes HMA		☐ HMA & PCC
Is the project lo	cated on a Special Roadway or	Network? ⊠	No ☐ Ye	s Network
Is the project lo	cated on or intersect an RTOP o	corridor? ▽	No ☐ Ye	2
10 till project 10			INO LITE:	5
Is Federal Aviat	ion Administration coordinatior	n anticipated?	⊠ No	□ Yes
DESIGN AN	ID STRUCTURAL			
-	the proposed project: The project		_	
	t shoulders. The roadway approa of which will be paved. The propo			
	o p. op p			omeung ung.m.e.m
Major Structure			<u> </u>	
Structure 031-0017-0	Existing 108-ft length; 34.1-ft deck v	width: two 11-ft	130-ft length; 37.2	roposed 5-ft deck width:
001-0017-0	lanes; 2.9-ft shoulders; 4 m		two 11-ft lanes; 6-	
	and concrete		single span	
	dge Construction (ABC) technic			
	es are applicable to this project, be noderate concerns from the school			

P.I. Number: 0015605

Template Version: 20200.02.27

Limited Scope Project Concept Report - Page 4

Limited Scope Project Concept Report – Page 5

County: Bulloch

Prefabricated Bridge Elements and Systems (PBES): Prefabricated elements could be utilized to facilitate faster construction. However, given that the off-site detour adds 10 additional minutes to four school bus routes and the concerns from the school system were moderate, it is unlikely these elements will be used.

P.I. Number: 0015605

Mainline Design Features:

CR 927/Old Hwy 46	Functional Classifica	ation: Major Collecto	or
Feature	Existing	*Policy	Proposed
Typical Section:			
- Number of Lanes	2		2
- Lane Width(s) (-ft)	11-ft	11-ft	11-ft
- Median Width (-ft) & Type	N/A	N/A	N/A
- Shoulder Width (-ft) (Outside)	Varies 4-ft to 8-ft (unpaved)	4-ft	8-ft (6.5-ft paved)
- Border Area Width (-ft)	N/A	N/A	N/A
- Cross Slope (%)	Unknown	2% (normal)	2%
- Outside Shoulder Slope (%)	Unknown	6%	6%
- Inside Shoulder Width (-ft)	N/A	N/A	N/A
- Sidewalks (-ft)	N/A	N/A	N/A
- Auxiliary Lanes (#lanes/-ft width)	N/A		N/A
- Bike Accommodations	N/A	4-ft	6.5-ft paved shidi 6-ft bridge shidr
Posted Speed (mph)	55		55
Design Speed (mph)	Unknown	55	55
Minimum Horizontal Curve Radius (-ft)	Unknown	960-ft	1900-ft
Maximum Superelevation Rate (%)	Unknown	8% (EMax)	5%
Maximum Grade (%)	Unknown	6% (Level)	0.820% (level)
Access Control	Non-restrictive		Non-restrictive
Design Vehicle	HS-20		SU
Check Vehicle	Unknown		OSOW
Pavement Type	HMA		HMA

^{*}According to current AASHTO Design Policy if applicable

Design Exceptions/Design Variances to FHWA or GDOT Controlling Criteria anticipated: N/A

Lightir	ng Required: ⊠ No □ Yes				
	e Detours Anticipated: No Utachment 6 for detour plans.	ndetermin	ed	⊠ Yes	
	Roadway type to be closed:	⊠ Local	Road	☐ State Route	
	Detour Route selected:	☐ Local	Road		
	District Concurrence w/Detour Route:	□ No/Pe	ending	⊠ Received 20	20-08-04
Transp	portation Management Plan [TMP] Re	equired:	□ No		⊠ Yes
	If Yes:Project classified as:		⊠ Non	-Significant	
	TMP Components Anticipated:		\boxtimes TTC		

P.I. Number: 0015605

⊠ No

☐ Yes

INTERCHAN	IGES AND INTERSECTION	S		
Interchanges/Ma	jor Intersections: N/A			
Intersection Con	trol Evaluation (ICE) Required:	⊠ No □ Y	es	
Roundabout Cor	ncept Validation Required: ⊠ No □ `	Yes □ Comple	ted <i>Date</i>	
UTILITY AN	D PROPERTY			
Railroad Involve	ment: N/A			
Utility InvolvemeGeorgia FBulloch T	Power			
SUE Required:	⊠ No □Yes			
Public Interest D	etermination Policy and Procedure re	ecommended:	⊠ No □ Yes	
Right-of-Way (R	DW): Existing width: <u>Varies 100-200</u> ft	. F	Proposed width:	<u>Varies 100-200</u> ft.
Required Right-of	- -Way anticipated: ☐ None ⊠ Yes	☐ Undet	termined	
Easements anticip	• •	oorary 🗆 Perma	anent * 🔲 Utili	ty ☐ Other
	* Permanent easeme	ents include the r	ight to place utilit	ies.
Γ	Anticipated total number of imp	nacted narcels:	4	
	7 thumpared total Hamber of Imp	Businesses:	0	
	Displacements anticipated:	Residences:	0	
		Other:	0	
	Total [Displacements:	0	
Location and De	sign approval: ☐ Not Required	⊠ Required		
Impacts to USAC	CE property anticipated: ⊠ No	☐ Yes ☐	Undetermined	
ENVIRONM	ENTAL AND PERMITS			
Anticipated Envi	ronmental Document: NEPA ~ PCE			
☑ The environmenta and agency c☐ The environmenta	mental Analysis: nental considerations noted below and analysis and are subject to revision af oncurrence. nental considerations noted below are not agency concurrence.	ter the completion	on of resource ide	entification, delineation,

Template Version: 20200.02.27

MS4 Permit Compliance – Is the project located in a MS4 area?

Limited Scope Project Concept Report – Page 7

County: Bulloch

If yes, is the GDOT MS4 Permit anticipated to apply to all or part of this project?

Is Non-MS4 water quality mitigation anticipated?

Environmental Permits, Variances, Commitments, and Coordination anticipated:

Air Quality:

Is the project located in an Ozone Non-attainment area?

No P.I. Number: 0015605

This project is for a bridge replacement. No changes are proposed to the number of through lanes. Due to the project type being a bridge replacement, a CO hotspot analysis is not required. An ozone analysis would not be required as the project does not occur within a non-attainment county. An air quality screening would be required.

⊠ No

☐ Yes

Is a Carbon Monoxide hotspot analysis required?

NEPA/GEPA Comments & Information: A Programmatic Categorical Exclusion (PCE) environmental document is anticipated for this project. One parcel with structures or buildings 50 years or older was identified during desktop review. There is a potential for Section 4(f) analysis if adverse impacts are anticipated to NRHP-eligible resources. Suitable habitat for federal protected species anticipated. Further coordination with design will need to take place before finalizing environmental recommendations and commitments. A 404 permit is anticipated for the proposed project. Full delineations of archaeological, history, and ecological resources would be required.

Ecology: A list of state and federally protected species was obtained using the Bulloch County IPAC and the DNR Rare Natural Elements lists. Protected species indicated on one or both of these lists include four federally protected species (eastern indigo snake [Drymarchon corais couperi], gopher tortoise [Gopherus polyphemus], Florida panther [Puma concolor coryi], and striped newt [Notophthalmus perstriatus]) and sixteen state-protected species (Atlantic pigtoe [Fusconaia masoni], bald eagle [Haliaeetus leucocephalus], mimic glass lizard [Ophisaurus mimicus], robust redhorse [Moxostoma robustum], southern hognose snake [Heterodon simus], spotted turtle [Clemmys guttata], swallowtailed kite [Elanoides forficatus], Georgia indigo bush [Amorpha georgiana], Georgia plume [Elliottia racemose], greenfly orchid [Epidendrum magnolia], hooded pitcherplant [Sarracenia minor], parrot pitcherplant [Sarracenia psittacina], purple honeycomb head [Balduina atropurpurea], sandhill milkvetch [Astragalus michauxii], silky camelia [Stewartia malacodendron], and yellow flytrap [Sarracenia flava]). No occurrences of protected species are noted in the DNR Early Coordination letter. Suitable habitat for eastern indigo snake, gopher tortoise, and striped newt is anticipated. Informal Section 7 consultation anticipated. Streams and wetlands were noted from desktop review of NWI and NHD maps and confirmed to occur during a site visit on 8/10/2017. There is a large wetland system along both sides of the road at the project site. A Section 404 Permit would be required for impacts associated with the replacement of the existing structure. A buffer variance from the GA Department of Natural Resources- Environmental Protection Division (EPD) may be required. All protected species habitat and water resources should be field verified.

Stream buffer variance is anticipated due to the impacts to the ephemeral channel.

History: A desktop review for historic resources, comprised of buildings, structures, sites, and objects constructed before 1968, was conducted within an environmental survey boundary (ESB) and corresponding viewshed from the furthest extent of the ESB. The ESB extends 1,000 feet from either end of bridge serial number 031-0017-0 and is 600 feet wide. This review included the Bulloch County tax assessor's record, 2012 Georgia Historic Bridge Survey (GHBS), National Historic Landmarks (NHL), National Register of Historic Places (NRHP), and Georgia's Historical Marker program. No properties listed or nominated for listing in the NRHP or NHL were identified within the proposed project's ESB. According to the GHBS form, the bridge was built in 1956 and is not considered eligible for the NRHP. Furthermore, no historical markers were identified within the ESB. The Georgia Department of Natural Resources (DNR) 1981 Bulloch County survey was also consulted via a review of Georgia's Natural, Archaeological, and Historic Resources Geographical Information Services (GNAHRGIS) database. No GNAHRGIS sites were identified within the ESB. The review of the Bulloch County tax assessor's record resulted in the identification of one (1) parcel (177 000030 000) with buildings or structures 50 years old or older that would require field assessment and evaluation for NRHP eligibility.

Limited Scope Project Concept Report – Page 8

County: Bulloch

<u>Archaeology</u>: No cemeteries or publicly documented sites are located in or adjacent to the project area. According to GNAHRGIS, the general vicinity of the project area has a low potential for archaeological sites. A search of the Georgia Archaeological Site Files was not conducted, so it is possible that previously recorded sites are located in or near the project area. A Phase I archaeological survey is required to investigate the area and assess affects to any sites that might exist there.

P.I. Number: 0015605

Public Involvement: Public Detour Open House (PDOH) and public outreach anticipated to inform the public about the bridge closure and use of an off-site detour. Major stakeholders consist of private individuals with property adjoining the project, local businesses, and local and through traffic.

COORDINATION, ACTIVITIES, RESPONSIBILITIES, AND COSTS

Constructability/Construction: No early completion incentives are recommended.

Project Meetings: Concept Team Meeting held 6/12/2020, Avoidance & Minimization Measures Meeting (A3M) held 8/21/2020, PDOH anticipated Fall 2020.

Other coordination to date: Detour early coordination letters were sent to Bulloch County Board of Commissioners, Bulloch County EMS, and Bulloch County Schools in August 2018. Early coordination letters were also sent to the USFWS and the DNR.

Project Activity	Party Responsible for Performing Task(s)
Concept Development	Arcadis/GDOT
Design	Arcadis
Right-of-Way Acquisition	GDOT
Utility Coordination (Preconstruction)	GDOT
Utility Relocation (Construction)	Utility Owners/Company
Letting to Contract	GDOT
Construction Supervision	GDOT
Providing Material Pits	Contractor
Providing Detours	Contractor
Environmental Studies, Documents, & Permits	GDOT
Environmental Mitigation	GDOT
Construction Inspection & Materials Testing	GDOT

Project Cost Estimate Summary and Funding Responsibilities:						
	PE Act	ivities				
	PE Funding	Section 404 Mitigation	ROW	Reimbursable Utilities	CST*	Total Cost
Date of Estimate:		7/31/2020	6/15/2020	8/10/2020	10/27/2020	
Funded By:	Federal / State		Local / Federal / State	Federal / State	Federal / State	
Programmed Cost:	\$500,000		\$158,000	\$50,000	\$1,500,000	\$2,208,000
Estimated Cost:	\$500,000	\$126,000	**\$114,000	\$90,000	\$2,159,407	\$2,989,407
Total Cost Difference:						\$781,407

^{*}CST Cost includes: Construction, Engineering and Inspection, Contingencies and Liquid AC Cost Adjustment.

^{**}Submitted to GDOT for review on 9/2/2020.

Limited Scope Project Concept Report – Page 9 P.I. Number: 0015605

County: Bulloch

ALTERNATIVES DISCUSSION

Alternative selection:

Preferred Alternative: Replace the bridge on the existing alignment and utilize an off-site detour.					
Estimated Property Impacts: 4 Estimated Total Cost:					
Estimated ROW Cost:	\$114,000	Estimated CST Time:	12 Months		

Rationale: This alternative would replace the existing bridge in-place and detour traffic off-site. The 5.7-mile detour would require vehicles to travel on local roads with equal or greater functional capacity and I-16. From Arcola Road and Old Highway 46 to SR119 and Old Highway 46, the distance is 5.5 miles, so the detour adds an additional 0.2 miles to the traveling public. If I-16 is not utilized for the off-site detour, local traffic would have a longer detour length if they use local roads. The District Preconstruction Engineer concurs with the local offsite detour route presented. Coordination with the school board, EMS and County officials for input on the detour alternative was initiated; the school board and County are in support of the bridge replacement utilizing an off-site detour. The school board did indicate that 4 routes would be impacted. The bridge is currently posted for a 10 tons weight limit and may not be suitable to carry bus traffic, depending on the school bus configuration. EMS indicated a low impact response to the off-site detour. There are no substandard or load posted bridges on the detour route suggested. No institutions (schools, churches, etc.) will be impacted near the roadway/bridge closure. This alternative was chosen because it will have a smaller footprint, requiring less right of way acquisition and minimizes environmental and utility impacts.

No-Build Alternative: Retain the existing bridge.							
Estimated Property Impacts: 0 Estimated Total Cost: \$							
Estimated ROW Cost:	\$0	Estimated CST Time:	N/A				
Rationale: Due to the age of the structure, not meeting current design standards, and condition of the							
substructure, this alternative is not preferred.							

Alternative 1: Replace the bridge on offset alignment and utilize an on-site detour. The shift in bridge alignment would remove Superelevation on bridge.

Estimated Property Impacts:	4	Estimated Total Cost:	\$3,282,956
Estimated ROW Cost:	\$114,000	Estimated CST Time:	12 Months

Rationale: This alignment would shift the existing alignment to the north. However, this Alternative will require construction temporary easement acquisition and right of way. Shifting the bridge to the north will allow the bridge alignment to be on a tangent section and curves, with an SE rate of 6%, would begin/end before the bridge deck. This allows the bridge to keep a normal crown (2%). This option would allow for an on-site detour. Partial demolition of the existing bridge would reduce the structure to one-lane, two-way traffic. A temporary signal would be needed for one-lane one-way traffic at a time. This alternative would increase the cost of the project. This creates maintenance issues due to the longitudinal bridge joint on the structure. County resources to maintain it may not be available.

Comments: On-Site Detour

Shifting the bridge alignment further north, outside of existing right-of-way and keeping the existing bridge open during construction would eliminate the need for an off-site detour. However, the new alignment would impact additional environmental resources, adjacent residential property, local utilities, and require temporary construction easement acquisition, extend the project limits and increase the cost of the overall project.


LIST OF ATTACHMENTS/SUPPORTING DATA


- 1. Concept Layout and Typical Sections
- 2. Detailed Cost Estimates:
 - a. Revisions to Programmed Costs forms, & Liquid AC Cost Adjustment forms
 - b. AASHTOWare Detailed Cost Estimate for Construction
 - c. Right-of-Way Preliminary Cost Estimate Summary


Limited Scope Project Concept Report – Page 10 County: Bulloch

P.I. Number: 0015605

- d. Mitigation Cost Estimate
- e. Preliminary Utility Cost Estimate
- 3. Concept Utility Report
- 4. Traffic Memo Summary & Approval
- 5. Existing Bridge S I & A Report
- 6. MS4 Concept Report Summary
 - a. MS4 Concept Report Summary
- 7. Minutes Concept Team Meeting
- 8. Minutes A3M
- 9. Detour Plan / District Concurrence of detour











- 🙆 RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II, GROUP 2 ONLY, INCL BITUM MATL & H LIME (135 LBS/SY)
- 🖹 RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME (220 LBS/SY)
- 🔘 RECYCLED ASPH CONC 25 MM SUPERPAVE, GP I OR 2, INCL BITUM MATL & H LIME (330 LBS/SY)
- 🔘 GRADED AGGREGATE BASE COURSE, 6 INCH, INCL MATL
- 🖹 GRADED AGGREGATE BASE COURSE, 8 INCH, INCL MATL
- ASPHALT PAVEMENT EDGE TREATMENT, GA CONSTRUCTION DETAIL P-7
- SKIP SHOULDER INDENTATION RUMBLE STRIPS PER GA CONSTRUCTION DETAILS T-23B AND T-25
- (A) CONTINUOUS CENTERLINE INDENTATION RUMBLE STRIPS PER GA CONSTRUCTION DETAIL T-24
- T) RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME



SUPER ELEVATED SECTION (NTS)







CONCEPT TYPCIAL SECTIONS - PREFERRED) ALTERNATIVE
MAINTAIN EXISTING BRIDGE ALIGNMENT

P. I. NO.: 0015605 CR 927/OLD HWY 46 @ ASH BRANCH II.6 MI SE OF BROOKLET BULLOCH COUNTY



FILE							
FILE							
PI NUMBER	0015605				PROJECT DESCRIPTION	This project is a bridge replacement old Highway 46 at Ash Branch, a	
OFFICE	Program Deliver				DESCRIPTION	Southeast of Brooklet.	pproximately 11.0 miles
DATE	Tuesday, Octob	er 27, 2020					
From:	Kimberly Nesbit	t <mark>, State Program</mark>	Delivery Adminis	trator			
То:			Review Engineer	ot.ga.gov			
Subject:	REVISIONS TO	PROGRAMME	D COSTS				
Project Manag	ger:		Joshua Pisani			1	
Management	Let Date:		4/15/2022				
Management	Right of Way Date	e:	5/15/2021				
Cost Estimate	Review Iteration	1				_	
		<u>.</u>		1			
Date of Submit							
Date of Submit	ılaı #3						
Summary of F	Programmed Cos	ts and Proposed	d Revised Costs	<u>i</u>			
	F "				ate Amounts	1 15 5 1 5 1	D : 10 15 " 1
CONSTRUCT		ite Type		(1-Pro witt	nout Inflation) \$1,500,000.00	Last Estimate Date	Revised Cost Estimate \$2,159,406.50
RIGHT OF WA					\$158,000.00		\$114,000.00
UTILITIES					\$50,000.00		\$90,000.00
Explanation for	or Cost Change a	nd Contingency	/ Justification:				
Concept deve	lopment						
Attachments:							
	Cost Estimate						
Right of Way C Preliminary Uti	Cost Estimate Sum	ımary					
	n Status Report						



Design Phase Leader Validation of Final QC/QA for Construction Cost Estimate Used In This Revision to Programmed Costs:

Consultant Company or GDOT Design Office:	Arcadis U.S. Inc.,
Printed Name:	Janet Middleton
Title:	Roadway Design Lead
Signature:	Middleton
Date:	10/27/2020
	FOR PROJECTS WITH A LOCAL ORGANICS
	FOR PROJECTS WITH A LOCAL SPONSOR anager should ensure that the local authority completes the following validation indicating that it has reviewed the oncurrence with the construction costs presented.
Please select the appropriate validation below u	pon review of the cost estimate:
☐ I acknowledge that I have reviewed the pro	oject construction cost estimate and <u>concur</u> with the costs presented.
☐ I acknowledge that I have reviewed the pro	oject construction cost estimate but <u>do not concur</u> with the costs presented.
Please provide an explanation for non-concurrence.	
Local Authority Name and Title:	
Local Authority Signature:	
Date:	



Cost Estimate Worksheet:

	nate worksneer											
CONSTRUC	TION COST ESTI	MATE (Required	base estimate enter	ed from CES a	and should not in	clude E&I). →				Α	\$	1,780,010.99
ENGINEERING AND INSPECTION (The default E&I percentage is 5.0%, but may be adjusted per project scope.) →								D	\$	89,000.55		
Construction Cost E&I Percentage				I Cost								
\$	1 780 010 99		5%	D =	89 000 55	1						
	\$ 1,780,010.99 5% \$ 89,000.55 CONTINGENCY (Refer to the Risk and Contingencies Table included in GDOT Policy 3A-9 Cost Estimating Purpose) →								ı	\$	280,351.73	
	ruction Cost	_	kl Cost		ction + E&I	Contingency	·	Conting	ency Cost			
Corist	E E	Ec	F		E + F	H			G x H			
\$	1,780,010.99	\$	89,000.55	\$	1,869,011.54	159	%	\$	280,351.73			
ASPHALT F	UEL PRICE ADJU		blank if not applicat	ole) →						Q	\$	10,043.22
Date			et 2020		Current Asph	nalt Fuel Index Prio	ces can be fou	nd at the link belo	w:			
Regular Unle Diesel	eaded		03/ GAL 39/ GAL			ww.dot.ga.gov/PS						
Liquid AC			.00/ TON		парли	ww.dot.ga.govii c	//waterials//tsp	mail delindex				
Liquid AC		Tons	Percentage of Asphaltic Concrete	Tons of Asphaltic Concrete	Total Monthly Tonnage of Asphalt Cement (TMT) M = Sum of	Monthly Asphalt Cement Price month project let (APL)	Мах. Сар	Monthly Asphalt Cement Price month placed (APM)	Price Adjustment (PA)			
	Description	J	К	L=JxK	Columns L, T & W	N	0	P = (N x O)+N	Q = [((P - N) / N)]			
	Leveling	25.00 TN	5.00%	1.25 TN	39.67 TN	\$422.00/ TON	60%	\$ 675.20	\$ 10,043.22			
	Patching 9.5 mm SP	148.00 TN	5.00%	7.40 TN	-							
	12.5 OGFC	1.0.50 114	0.0070									
	12.5 PEM				_							
	12.5 mm SP	455 00 TN	E 000/	22.75 TN	+							
	19 mm SP 25 mm SP	455.00 TN 144.00 TN	5.00% 5.00%	22.75 TN 7.20 TN	1							
Bituminous Tack Coat	Description	Tack Coat R	GL/TN S	Tons T = R/S								
	Tack Coat	248.00 GL	232.8234 GL/TN	1.07 TN]							
Bituminous Tack Coat (Surface		SY	GL/SY	TN W = (U x V) / (232.8234								
Treatment)	Description	U	V	GL/TN)								
	Single Surface Treatment		0.20 GI/SY		_							
	Double Surface Treatment Triple		0.44 GI/SY									
	Surface Treatment		0.71 GI/SY									
	TION TOTAL CO	ST →								X = A+D+I+Q	\$	2,159,406.50
	WAY COST →									Y Z = Sum of	\$	90,000.00
UTILITIES	COST (Provided by	Utility Office) -	·							Reimbursable	٩	30,000.00
Const. D	Utility Owner		Reimbursab			Utility Owner		Reimbur	sable Cost	Costs		
Georgia Pov Bulloch Tele	ver Company - Dist		\$	90,000.00								
	•											



Georgia Department

Report v1

Cost Estimate: 0015605 - 0015605

Cost Estimation Phase: 2-DE

Cost Estimate Item Total: \$1,780,010.99

Cost Estimate Budget Class Report - Estimate Level Details

Budget Class	Amount	Assignment Level
	\$1,780,010.99	Cost Estimate

Cost Estimate Budget Class Report

Cost Estimate: 0015605 - 0015605 Page: 1 of 5



Report v1

Cost Estimate Budget Class Report - Item Level Details

Budget Class	Line Number	Item	Item Description	Quantity	Unit	Amount
	5	150-1000	TRAFFIC CONTROL -	1.000	LS	\$110,000.00
	10	210-0100	GRADING COMPLETE -	1.000	LS	\$410,000.00
	15	310-5060	GR AGGR BASE CRS, 6 INCH, INCL MATL	782.000	SY	\$19,815.88
	20	310-5080	GR AGGR BASE CRS, 8 INCH, INCL MATL	871.000	SY	\$26,521.95
	25	402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	25.000	TN	\$3,728.50
	30	402-3102	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II, BLEND 1, INCL BITUM MATL & H LIME	148.000	TN	\$16,208.06
	35	402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	144.000	TN	\$15,603.90
	40	402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2,INCL BITUM MATL & H LIME	455.000	TN	\$44,650.14
	45	413-0750	TACK COAT	248.000	GL	\$601.31
	50	432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	453.000	SY	\$3,752.29
	55	433-1200	REINF CONC APPROACH SLAB, INCL SLOPED EDGE	244.000	SY	\$51,153.46
	60	456-2022	INDENTATION EDGE LINE RUMBLE STRIPS-GROUND IN PLACE (SKIP)	0.460	GLM	\$2,437.87
	65	456-2025	INDENTATION CENTERLINE RUMBLE STRIPS-GROUND IN PLACE (CONTINUOUS)	0.230	GLM	\$5,585.50
	70	641-1100	GUARDRAIL, TP T	84.000	LF	\$6,313.93
	75	641-1200	GUARDRAIL, TP W	600.000	LF	\$12,301.06

Cost Estimate: 0015605 - 0015605 Page: 2 of 5



Report v1

Cost Estimate Budget Class Report - Item Level Details

Budget Class	Line Number	Item	Item Description	Quantity	Unit	Amount
	80	641-5001	GUARDRAIL ANCHORAGE, TP 1	2.000	EA	\$2,612.51
	85	641-5015	GUARDRAIL TERMINAL, TP 12A, 31 IN, TANGENT, ENERGY- ABSORBING	2.000	EA	\$5,856.72
	90	543-9000	CONSTRUCTION OF BRIDGE COMPLETE -	1.000	LS	\$726,375.00
	95	540-1101	REMOVAL OF EXISTING BR, STA NO -	1.000	LS	\$165,726.00
	100	441-0301	CONC SPILLWAY, TP 1	2.000	EA	\$5,466.64
	105	576-1018	SLOPE DRAIN PIPE, 18 IN	50.000	LF	\$2,654.91
	110	603-2024	STN DUMPED RIP RAP, TP 1, 24 IN	769.000	SY	\$53,995.61
	115	603-7000	PLASTIC FILTER FABRIC	769.000	SY	\$3,418.10
	120	634-1200	RIGHT OF WAY MARKERS	11.000	EA	\$1,603.89
	125	163-0232	TEMPORARY GRASSING	1.000	AC	\$928.16
	130	163-0240	MULCH	24.000	TN	\$4,795.74
	135	163-0301	CONSTRUCT AND REMOVE CONSTRUCTION EXITS	2.000	EA	\$4,000.00
	140	163-0520	CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN	100.000	LF	\$1,865.02
	145	163-0529	CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER OR BALED STRAW CHECK DAM	1,700.000	LF	\$6,510.58
	150	163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	2.000	EA	\$599.37
	155	165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	1,700.000	LF	\$2,283.64
	160	165-0071	MAINTENANCE OF SEDIMENT BARRIER - BALED STRAW	850.000	LF	\$1,059.52

Cost Estimate: 0015605 - 0015605 Page: 3 of 5



Report v1

Cost Estimate Budget Class Report - Item Level Details

Budget Class	Line Number	Item	Item Description	Quantity	Unit	Amount
	165	165-0101	MAINTENANCE OF CONSTRUCTION EXIT	2.000	EA	\$1,169.50
	170	165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	2.000	EA	\$161.79
	175	167-1000	WATER QUALITY MONITORING AND SAMPLING	2.000	EA	\$1,105.19
	180	167-1500	WATER QUALITY INSPECTIONS	12.000	MO	\$8,019.95
	185	171-0030	TEMPORARY SILT FENCE, TYPE C	3,400.000	LF	\$14,476.86
	190	643-8200	BARRIER FENCE (ORANGE), 4 FT	1,586.000	LF	\$3,363.62
	195	700-6910	PERMANENT GRASSING	2.000	AC	\$5,167.92
	200	700-7000	AGRICULTURAL LIME	4.000	TN	\$477.53
	205	700-8000	FERTILIZER MIXED GRADE	2.000	TN	\$1,345.37
	210	700-8100	FERTILIZER NITROGEN CONTENT	83.000	LB	\$341.78
	215	713-3002	WOOD FIBER BLANKET, TP II, SLOPES	7,577.000	SY	\$13,364.31
	220	636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	39.000	SF	\$779.45
	225	636-2070	GALV STEEL POSTS, TP 7	122.000	LF	\$1,169.01
	230	653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	1,082.000	LF	\$1,883.49
	235	653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	1,082.000	LF	\$1,663.20
	240	654-1001	RAISED PVMT MARKERS TP 1	60.000	EA	\$529.36
	245	657-1085	PREFORMED PLASTIC SOLID PVMT MKG, 8 IN, CONTRAST (BLACK-WHITE), TP PB	388.000	LF	\$3,283.70

Cost Estimate: 0015605 - 0015605 Page: 4 of 5





Report v1

Cost Estimate Budget Class Report - Item Level Details

Budget Class	Line Number	Item	Item Description	Quantity	Unit	Amount
	250	657-1085	PREFORMED PLASTIC SOLID PVMT MKG, 8 IN, CONTRAST (BLACK-WHITE), TP PB	388.000	LF	\$3,283.70

Cost Estimate: 0015605 - 0015605 Page: 5 of 5

GEORGIA DEPARTMENT OF TRANSPORTATION PRELIMINARY ROW COST ESTIMATE SUMMARY

Date:	6/15/2020	Project: Old Hwy 46 at Ash Branch
Revised:	N/A	County: Bulloch
		PI: 0015605
Description:	Bridge Replacement	
Project Termini:	Old Hwy 46 at Ash Br	ranch
		Existing ROW: Varies
Parcels:	4	Required ROW: Varies
		40.445.00
Land	and Improvements	\$8,145.00
	Proximity Damage \$0.	.00
	Consequential Damage \$0.	.00
	Cost to Cures \$0.	<mark>.00</mark>
	Trade Fixtures \$0.	<mark>.00</mark>
	Improvements \$0.	. <u></u>
	Valuation Services	\$17,500.00
	Legal Services	\$40,200.00
	Relocation	\$12,000.00
	Demolition	\$0.00
	Administrative	\$35,500.00
TOTAL	ESTIMATED COSTS	\$113,345.00
TOTAL ESTIMATED	COSTS (ROUNDED)	\$114,000.00
		0101111
Prepared By:	John Albrycht	John Albrycht 6/15/2020
	Print Name	Signature Date
Cost Estimation Supervisor		
NOTE 6	Print Name	Signature Date
-	-	was completed using the correct information provided for
		roperty values or the accuracy of the market value preciation is included in this Preliminary Cost Estimate.
estimations provided in tills	report. No Market App	neciation is included in this rieminiary cost Estimate.
Comments:		

*Note - ROW Cost developed by design team and submitted to GDOT 9/2/2020.

Middleton, Janet

Subject:

FW: PI 0015605, Bulloch County - Estimated Mitigation Cost for Concept Report

From: Westberry, Lisa < lwestberry@dot.ga.gov>

Sent: Friday, July 31, 2020 4:10 PM **To:** Pisani, Joshua < <u>JPisani@dot.ga.gov</u>>

Cc: Pecot, Patrick <Patrick.Pecot@arcadis.com>

Subject: PI 0015605, Bulloch County - Estimated Mitigation Cost for Concept Report

As requested, the estimated mitigation cost for the subject project is **\$126,000.00**. This estimate is based on preliminary field surveys within the environmental survey boundary for the project. Final mitigation credit costs will not be known until lockdown plans are available.

If you should have any questions or need any additional information, please do not hesitate to contact me.

Respectfully,

Lisa Westberry

Special Projects Coordinator



Office of Environmental Services One Georgia Center, 16th Floor 600 West Peachtree Street, NW Atlanta, GA, 30308 404.631.1772

You take every precaution - wash your hands, social distance, wear a mask. So, if you must drive, consider this ... higher speeds make for more serious crashes. To decrease the odds of a serious crash increase the distance between you and the vehicle in front of you. And slow down to the posted speed limit. Drive Alert Arrive Alive, Georgia.



FILE Project No: n/a Office: District 5, Jesup
County Bulloch Date: August 10, 2020

P.I.# 0015605

Description: CR 927/ Old Hwy 46 @ Ash Branch 11.6 Mi SE of Brooklet

FROM Dallory Rozier, District Utilities Manager

TO Joseph Pisani, Project Manager

SUBJECT PRELIMINARY UTILITY COST ESTIMATE

A review of utilities located on the above referenced project has been conducted with Concept Layout plans. Listed below is a breakdown of the anticipated reimbursable and non-reimbursable cost.

<u>Utility Owner</u>	Reimbursable	<u>Non-</u> Reimbursable	Estimate Based on
Georgia Power Company- Dist	\$90,000.00	\$0.00	Site Visit / Available Drawings
Bulloch Tel	\$0.00	\$36,000.00	Site Visit / Available Drawings
Total 100.00	\$90,000.00	\$36,000.00	
Department Responsibility 100.00	% \$90,000.00		
Utility Owner Responsibility 100.00	% \$0.00	\$36,000.00	

^{**} Indicates Potential Utility Aid Request from Local Gov't

Estimate is based on the best available information at the current stage, unforeseen prior rights information may be provided by the Utility Company at a later date that could cause some non-reimbursable costs to shift to the reimbursable cost column.

If additional information is needed, please contact John Royal at jroyal@dot.ga.gov.

cc: Patrick Allen, P.E., State Utilities Administrator Shajan Joseph, P.E., Assistant State Utilities Administrator Marcela Coll, Utilities Preconstruction Manager David Woodcox, Utilities Preconstruction Specialist Danah Bonny, Utilities Preconstruction Specialist

Original Version: May 24, 2013 Revision: Feb. April 5, 2018

Concept Utility Report

Project Number: Click here to enter text.	District: 5
County: Bulloch	Prepared by: John Royal
P.I. # 0015605	Date: June 23, 2020
Project Description: CR 927/Old Hwy 46 @ Ash Bran	nch 11.6 Mi SE of Brooklet
The information provided herein has been gathered from Georgia8 in this report is to be used as a substitute for 1^{st} Submission or SUE.	
Are SUE services recommended? No	
Level: □A □B □C □D	
Public Interest Determination (PID):	
\square Automatic \square Mandatory \square Consideration \boxtimes	No Use □Exempt
Is a separate utility funding phase recommended? No	
Potential Project (Schedule/Budget) Impacts: Click here to	enter text.
Capital Improvement Projects (Utilities) Anticipated in the	Area: Click here to enter text.
Project Specific Recommendations for Avoidance/Mitigation	on: Click here to enter text.
Right of Way Coordination: Pending	
Environmental Coordination: Click here to enter text.	
Additional Remarks: Click here to enter text.	

Original Version: May 24, 2013 Revision: Feb. March 8, 2018

Utilities have facilities within the project limits.

Utilities have been identified using Georgia811 and/or field visits.

Facility Owner	Facility Owner Contact Email Address	Existing Facilities/ Appurtenances	General Description of Location	Facilities to Avoid approx. limits	Facilities Retention Recommended approx. limits	Comments
Bulloch	jscott@bulloch.solutions	U/G fiber	Both sides of	Click here to	Click here to	Relocate
Telephone			the bridge	enter text.	enter text.	
GPC-D	RDLONG@southernco.com	O/H Power-	North side of	Click here to	Click here to	Relocate
		Distribution	the bridge	enter text.	enter text.	
Click here to	Click here to enter text.	Click here to	Click here to	Click here to	Click here to	Click here to
enter text.		enter text.	enter text.	enter text.	enter text.	enter text.

Note: To add additional rows, click the bottom right corner of the box above, then click the blue + that will appear. Please add additional rows prior to entering text.



FILE: Bulloch County

P.I. # 0015605

DATE: August 19, 2020

FROM: Thomas McQueen, Asst. State Transportation Planning Administrator

TO: Kimberly Nesbitt, State Program Delivery Administrator

Attention: Joshua Pisani

SUBJECT: Reviewed Traffic Forecast Report for CR 927/Old Hwy 46 @ Ash

Branch 11.6 Miles SE of Brooklet

Per request, we have reviewed the consultant's design traffic forecast for the above project. Based on the information furnished, we find the design traffic forecast to be satisfactory, and the design traffic forecasting task to be complete for the above project. The reviewed and approved design traffic forecast for the above project is attached.

If you have any questions concerning this information please contact Andre Washington at 404-631-1925.

Keith McCage HNTB Design Traffic Consultant to GDOT 404-946-5731

TEM/KAM

Arcadis U.S., Inc. (Arcadis) 2839 Paces Ferry Road, Suite 900 Atlanta, Georgia 30339

MEMORANDUM TO: Joshua Pisani

Georgia Department of Transportation, Office of Program

Delivery

FROM: Patrick Pecot, PE

Arcadis U.S., Inc. (Arcadis)

DATE: July 27th, 2020

SUBJECT: Traffic Assignments for PI#0015605, Bulloch County, CR

927/Old Hwy 46 @ Ash Branch 11.6 mi SE of Brooklet

Company is furnishing Traffic Assignments for the above project as follows:

BRIDGE- ID 031-0017-0

		2025	2027	2045	2047				
	(Existing Year)	(Base Year)	(Base Year +2)	(Design Year)	(Design Year +2)				
AADT	800	850	900	1050	1100				
DHV (AM/PM)	75/90	80/95	85/95	100/120	100/125				
K% (AM/PM)	9.1%/11.5%								
D% (AM/PM)	60.0%/70.5%								
24 HR. T% - S.U.	5.0%								
24 HR. T% - COMB	2.5%		Same as Ex	victing Voor					
24 HR. T% - TOTAL	7.5%		Saille as E	distilly real					
T% - S.U. (AM/PM)	8.0%/7.5%								
T% - COMB. (AM/PM)	2.5%/2.0%								
T% - TOTAL (AM/PM)	10.5%/9.5%								

If you have any questions concerning this information, please contact me by <a href="mailto:em

Georgia Department of Transportation Bridge Inventory Data Listing

0- Not Applicable

Processed Date: Aug-15-2019 14:02 PM

Parameters: Bridge Serial Number

Bridge Serial Number: 031-0017-0

	Location	&	Geography	
--	----------	---	-----------	--

Structure ID:

Structure ID.	031-0017-0
200 Bridge Information:	06
*6 Feature Intersected:	ASH BRANCH
*7A Route Number Carried:	CR00927
*7B Facility Carried:	FAS 577
9 Location:	11.6 MI SE OF BROOKLET
2 GDOT District:	4841500000 - D5 District Five Jesup
*91 Inspection Frequency:	24 Date: Mar-13-2018
92A Fracture Critical Insp. Freq:	0 Date: Feb-01-1901
92B Underwater Insp Freq:	60 Date: Oct-05-2015
92C Other Spc. Insp Freq:	0 Date: Feb-01-1901
* 4 Place Code:	00000
*5A Inventory Route(O/U):	1
5B Route Type:	4 - County
5C Service Designation:	1- Mainline
5D Route Number:	00577
5E Directional Suffix:	0. Not applicable
*16 Latitude:	32 - 13.9092
*17 Longtitude:	81 - 34.1808
98A Border Bridge:	98B: GA% 00
99 ID Number:	
*100 STRAHNET:	0- The Feature is not a STRAHNET route.
12 Base Highway Network:	Yes
13A LRS Inventory Route:	312092700
13B Sub Inventory Route:	0
101 Parallel Structure:	N. No parallel structure exists
*102 Direction of Traffic:	2- Two Way
*264 Road Inventory Mile Post:	24.41

031-0017-0

*204B Federal Route Number: 00577

*110 Truck Route: 0- The Feature is not part of the National Network for

0. Not applicable

Trucks

Area 10

S - Secondary.

0- Inventory Route is not on the NHS

7- Rural - Major Collector

217 Benchmark Elevation: 0000.00

*208 Inspection Area:

*104 Highway System:

*26 Functional Classification: *204A Federal Route Type:

105 Federal Lands Highway:

* Location ID No: 031-00577F-024.41E

County: Bulloch

218 Datum:

210 Datum.	0- Not Applicable	Signs & Attachi
*19 Bypass Length:	7	225 Expansion J
*20 Toll:	3- On a Free Road or Non-Highway	242 Deck Drains
*21 Maintenance Responsibility:	02-County Highway Agency.	243A Parapet Lo
*22 Owner:	02-County Highway Agency.	243B Parapet He
*31 Design Load:	5- HS 20	243C Parapet W
37 Historical Significance:	5- Not eligible for the National Register of Historic Places	238A Curb Heigl
205 Congressional District:	012	238B Curb Mate
27 Year Constructed:	1956	239A Handrail L
106 Year Reconstructed:	0	239B Handrail R
33 Bridge Median:	0-None	*240 Median Ba
34 Skew:	0	241A Bridge Me
35 Structure Flared:	No	241B Bridge Me
38 Navigation Control:	0- Navigation is not controlled by an Agency	*230A Guardrail
213 Special Steel Design:	0- Not applicable or other	*230B Guardrail
267A Type Paint Super Structure:	1- Lead Chromate Oil Alkyd System. Year: 1992	*230C Guardrai
267B Type Paint Sub Structure:	3- Epoxy Mastic Year : 1992	*230D Guardrai
*42A Type of Service On:	1-Highway	244 Approach S
*42B Type of Service Under:	5-Waterway	224 Retaining W
214A Movable Bridge:	0	233 Posted Spec
214B Operator on Duty:	0	236 Warning Sig
203 Type Bridge:	E - Steel pile. N. Steel-Concrete M. Steel O. Concrete	234 Delineator:
259 Pile Encasement:	1	235 Hazard Boa
*43A Structure Type Main material:	4-Steel (Continuous)	237A Gas:
*43B Structure Type Main Type:	2-Stringer/Multi-Beam or Girder	237B Water:
45 Number of Main Spans:	4	237C Electric:
44 Structure Type Approach:	A:0- Other B: 0- Other	237D Telephone
46 Number of Approach Spans:	0	237E Sewer:
226 Bridge Curve:	A: Vertical: NoB: Horizontal: Yes	247A Lighting: S
111 Pier Protection:	N - Navigation Control item coded 0, or Feature not a waterway	247B Navigation
107 Deck Structure Type:	1 - C-I-P Portland Cement Concrete - Epoxy Coated Rebars	247C Aerial:
108A Wearing Surface Type:	1. Concrete	*248 County Cor
108B Membrane Type:	0. None	36A Bridge Raili
108C Deck Protection:	8. Unknown	36B Transition:
265 Underwater Inspection Area:	2	36C Approach G

SUFF. RATING: 38.7

Signs & Attachments

225 Expansion Joint Type: 02- Open or sealed concrete joint (silicone

 242 Deck Drains:
 1- Open Scuppers.

 243A Parapet Location:
 0- None present.

 243B Parapet Height:
 0.00

 243C Parapet Width:
 0.00

 238A Curb Height:
 1.2

 238B Curb Material:
 1- Concrete.

 239A Handrail Left:
 1- Concrete.

 239B Handrail Right:
 1- Concrete.

 *240 Median Barrier Rail:
 0- None.

*240 Median Barrier Rail:

241A Bridge Median Height:

241B Bridge Median Width:

0

*230A Guardrail Location Direction Rear:

3- Both sides.

230B Guardrail Location Direction Fwrd: 3- Both sides.
230C Guardrail Location Opposing Rear: 0- None.
230D Guardrail Location Opposing Fwrd: 0- None.
44 Approach Slab: 3- Forward and Rear.
24 Retaining Wall: 0- None.

 224 Retaining Wall:
 0- No

 233 Posted Speed Limit:
 55

 236 Warning Sign:
 No

234 Delineator: Yes

 235 Hazard Boards:
 Yes

 237A Gas:
 00- Not Applicable

 237B Water:
 00- Not Applicable

 237C Electric:
 00- Not Applicable

 237D Telephone:
 00- Not Applicable

 237E Sewer:
 00- Not Applicable

247A Lighting: Street:No247B Navigation:No247C Aerial:No248 County Continuity No.:00

66A Bridge Railings: 2- Inspected feature meets acceptable

construction date standards.

6B Transition: 2- Inspected feature meets acceptable

construction date standards.

36C Approach Guardrail: 2- Inspected feature meets acceptable

construction date standards.

36D Approach Guardrail Ends: 2- Inspected feature meets acceptable

construction date standards.

Georgia Department of Transportation Bridge Inventory Data Listing


Processed Date:Aug-15-2019 14:02:34 PM

Bridge Serial Number: 031-0017-0		County: Bulloch		SUFF. RATING: 38.7	
Programming Data		Measurements:		Ratings and Posting	
201 Project Number:	00000	*29 AADT:	720	65 Inventory Rating Method:	1-Load Factor (LF)
202 Plans Available:	4- Plans in Infolmage/GAMS	*30 AADT Year:	2011	63 Operating Rating Method:	1-Load Factor (LF)
249 Proposed Project Number:	LOCBR	109 % Truck Traffic:	1	66A Inventory Type:	2 - HS loading.
250A Reconstruction Approval Status:	No	* 28A Lanes On:	2	66B Inventory Rating:	6
250B Route Approval Status:	No	*28B Lanes Under:	0	64A Operating Type:	2 - HS loading.
250C Approval Status Definition:	0	210A Tracks On:	00	64B Operating Rating:	17
250D Approval Status Federal:	0	210B Tracks Under:	0	231Calculated Loads	Posting Required
251Project Identification Number:	0015605	* 48 Maximum Span Length:	27	231A H-Modified:	10 Yes
252 Contract Date:	Feb-01-1901	* 49 Structure Length:	108	231B Type3/Tandem:	00 No
260 Seismic Number:	00000	51 Bridge Roadway Width:	27.8'	231C Timber:	00 No
75A Type Work Proposed:	0- Not Applicable	52 Deck Width:	34.1'	231D HS-Modified:	00 No
75B Work Done by:	0- Initial Inventory	* 47 Total Horizontal Clearance:	27.8'	231E Type 3S2:	00 No
94 Bridge Improvement Cost:(X\$1,000)	\$422	50A Curb / Sidewalk Width Left:	2	231F Piggyback:	00 No
95 Roadway Improvement Cost: (X\$1,000)	\$42	50B Curb / Sidewalk Width Right:	2	261 H Inventory Rating:	07
96 Total Improvement Cost: (X\$1,000)	\$633	32 Approach Rdwy. Width:	22'	262 H Operating Rating:	15
76 Improvement Length:	0'	*229 Approach Roadway		67 Structural Evaluation:	3
97 Year Improvement Cost Based On:	2013	Rear Shoulder Left: Width: 5	Right Width:5 Type: 8 - Grass (Dirt).	58 Deck Condition:	6 - Satisfactory Condition
114 Future AADT:	1080	Fwd Shoulder: Left Width: 5	Right Width:5 Type: 8 - Grass (Dirt).	59 Superstructure Condition:	7 - Good Condition
115 Future AADT Year:	2031	Rear Pavement: Width: 22	Type:2- Asphalt.	* 227 Collision Damage:	
		Forward Pavement: Width: 22	Type:2- Asphalt.	60A Substructure Condition:	5 - Fair Condition
		Intersection Rear: 0	Forward:0	60B Scour Condition:	6 - Satisfactory Condition
Hydraulic Data		53 Minimum Vertical Clearance Over Rd:	99' 99"	60C Underwater Condition:	5 - Fair Condition
113 Scour Critical:	U. No Load Rating; no scour critical data entered.	54A Under Reference Feature:	N- Feature not a highway or railroad.	71 Waterway Adequacy:	8-Equal to present desirable criteria.
216A Water Depth:	4	54B Minimum Clearance Under:	0' 0"	61 Channel Protection Cond.:	8-Equal to present desirable criteria.
216B Bridge Height:	12.7	*228 Minimum Vertical Clearance		68 Deck Geometry:	5
222 Slope Protection:	1	228A Actual Odometer Direction:	99'99"	69 UnderClr. Horz/Vert:	N
221A Spur Dike Rear:		228B Actual Opposing Direction:	99'99"	72 Approach Alignment:	8-No reduction of vehicle operating speed required.
221B Spur Dike Fwd:		228C Posted Odometer Direction:	00'00"	62 Culvert:	N - Not Applicable
219 Fender System:	0- None.	228D Posted Opposing Direction:	00'00"	70 Bridge Posting Required:	0. > 39.9% below
220 Dolphin:		55A Lateral Underclearance Reference:	N- Feature not a highway or railroad.	41 Struct Open, Posted, CL:	P. Posted for load
223A Culvert Cover:	000	55B Lateral Underclearance on Right:	0	* 103 Temporary Structure:	No
223B Culvert Type:	0- Not Applicable	56 Lateral Underclearance on Left:	0	232 Posted Loads	
223C Number of Barrels:	0	10A Direction of Travel for Max Min:	0	232A H-Modified:	10
223D Barrel Width:	0	10B Max Min Vertical Clearance:	99'99"	232B Type3/Tandem:	00
223E Barrel Height:	0	245A Deck Thickness Main:	6.0	232C Timber:	00
223F Culvert Length:	0	245B Deck Thickness Approach:	0	232D HS-Modified:	00
223G Culvert Apron:	0	246 Overlay Thickness:	0	232E Type 3s2:	00
39 Navigation Vertical Clearance:	0'			232F Piggyback:	00
40 Navigation Horizontal Clearance:	0			253 Notification Date:	Feb-01-1901
116 Navigation Vertical Clear Closed:	0			258 Federal Notify Date:	Feb-01-1901

MS4 Concept Report Summary

Attach the following checklist information to the Concept Report Template:

If	re a Project Level Exclusion that applies to this project: No Yes yes, please indicate which of the following exclusions apply: Roadways that are not owned or operated (maintained) by GDOT may not require post-construction BMPs Coordinate with the appropriate local government or entity to determine stormwater management requirements.
\boxtimes	The project location is not within a designated MS4 area.
	Maintenance and safety improvement projects whereby the sites are not connected and disturbs less than one acre at each individual site. This includes projects such as repaving, shoulder building, fiber optic line installation, sign addition, and sound barrier installation.
	Projects that have their environmental documents approved or right-of-way plans submitted for approval on or before June 30th, 2012.
	Road projects that disturb less than 1 acre or for site development projects that add less than 5,000 ft ² of impervious area.



RECORD OF MEETING



INTERAGENCY REVIEW TEAM (IRT) MEETING MINUTES					
PI No 0015605					
06/12/20	10:00 AM	Virtual Microsoft Team Meeting			
Meeting called by	GDOT Office of	of Program Delivery (GDOT OPD)			
Type of meeting	Concept Team	n Meeting			
Minutes prepared by	Patrick Pecot,	Natasha Morel, Janet Middleton			
Attendees	See Attached	Sign-In Sheet			

Arcadis U.S., Inc. 2410 Paces Ferry Road #400 Atlanta Georgia 30339 Tel 770 431 8666 Fax 770 435 2666

Welcome and Introductions

Josh Pisani from GDOT Office of Program Delivery (GDOT OPD) started with a brief introduction
on how the meeting would run. This virtual concept team meeting involved 3 projects PI 00015605,
0015620 and 0015641. Next, Janet Middleton, Natasha Morel and Patrick Pecot, all from Arcadis
talked through the key points of the concept report via power point presentation for project PI
0015605.

Project Background

Discussion

Discussion

Project Background - Arcadis Roadway Engineer, Natasha Morel lead the discussion.
 This project is in Bulloch county and proposes to replace the existing bridge (structure ID 031-0017-0) on CR 927 (Old Highway 46) over Ash Branch.

ROW Authorization: May 2021 (4 Parcels)

Let Date: April 2022Open to Traffic: 2023

No comments

Project Justification

• Project Justification - Arcadis Design Manager, Janet Middleton lead the discussion. The bridge on County Route 927 (Old Highway 46) over Ash Branch, Structure ID 031-0017-0 was built in 1956. The bridge consists of four steel spans on concrete caps with steel piles. The bridge was designed using an HS-20 vehicle; however, it is not meeting current standards. The deck is in satisfactory condition with transverse cracking reaching the bottom of the deck as well as evidence of the deck joints leaking. Also, spalling has been identified on some edge beams located in span 2 and 3, and the edge

of the deck near the joints. The superstructure is in good condition with minor corrosion on all beams. There is also evidence of horizontal cracking and spalling in all end diaphragms between all beams. The substructure is in fair condition with vertical cracking on abutments. In addition, there are exposed piles due to encasement beginning to honeycomb and crumble. The exposure has caused rusting and section loss under the encasement. Scour is also evident. Due to the age of the structure, not meeting current design standards, and condition of the substructure, replacement of this bridge is recommended.

- Comment: (Carol Kalafut GDOT Office Of Bridge Design): Strike functionally obsolete from the concept report. Term is no longer used by FHWA.
- Comment: (Janet Middleton Arcadis) Will clean up language in concept report
- <u>Comment:</u> (Carol Kalafut GDOT Office Of Bridge Design): GDOT gave justification state 11/29/2018

Existing Conditions

• Existing Conditions - Arcadis PM, Patrick Pecot and Natasha Morel lead the discussion.

Discussion

- Existing Bridge: Built in 1956 and has 4 main steel spans on concrete caps with steel piles. The bridge has a length of 108' and 34.1 ft deck width; 2 – 11 ft
- o Existing Roadway: 2 11 ft lanes, with variable width unpaved shoulders
- o Adjacent Projects: Arcadis will coordinate with all future projects
- No comments

Traffic Data

Discussion

- Traffic Data Arcadis Design Manager, Janet Middleton lead the discussion. Existing Traffic memo is under review. Due to the COVID-19, no new traffic data has been collected for this project.
- No comments

Environmental Coordination:

- Environmental Coordination Natasha Morel and Janet Middleton from Arcadis lead the discussion.
 - PCE expected
 - Section 404 Permit, Stream buffer variance and Informal section 7 are anticipated on this project
 - PDOH is anticipated to inform public to bridge closure and off-site detour
- Discussion
- $\circ \quad \text{No air quality or noise study needed} \\$
- o No historical resources were identified
- 2 archeological resources were identified
- A3M Meeting is anticipated for mid-August
- GA Power and Bulloch Telephone; SUE is not anticipated
- Comment (Derrick Cameron GDOT): With an Informal section 7 anticipated, will this project meet May 2021 ROW Authorization?

- Comment (Katheryn Graft, NV5): Schedule seems appropriate to meet ROW authorization.
- Comment (Dusty Mercer): Do any of these projects qualify for a LIBP?
- Comment (Josh): All of these projects have ROW authorization
- Comment (Erin): Check NEPA new guidelines for public house meeting and public hearings, as the GDOT has a new process.

Detour

Detour - Arcadis Design Manager, Janet Middleton lead the discussion. This project will utilize I-16 as detour. Early coordination with EMS indicated low impact. Arcadis continues to contact local schools for additional comments.

Discussion

- Comment (Brad Deal): The Kangeter property owners have expressed concerns on the how the bridge detour will impact access to their property. The owners have elderly parents that need to be tended to during construction.
- Comment (Janet Middleton Arcadis): The detour would speed up the construction and shorten the length of time the bridge is closed.

Design Features

- Design Features Arcadis Roadway Engineer, Natasha Morel lead the discussion.
 - 2-11 ft lanes
 - o Design Speed 45 MPH
 - o SE Max 6%

Discussion

Discussion

- o Bicycle warrants are met on this project and will be accommodated on the roadway with 6.5' paved shoulders and 4 -ft shoulders for the bridge.
- Comment (Carol Kalafut GDOT Office Of Bridge Design): 4 ft bike lanes/shoulders on the bridge may not be wide enough. Will provide follow-up information on bridge bike shoulder.

Alternatives Comparison

- Graphics of the impacts for each alternative were shown and discussed by the Arcadis Team.
 - Preferred Alternative This alternative would replace the existing bridge in-place and detour traffic off-site. The 5.7-mile detour would require vehicles to travel on local roads with equal or greater functional capacity and I-16. This alternative was chosen because it will have a smaller footprint, requiring less right of way acquisition and possible environmental and utility impacts.
 - Initial coordination with the local school, EMS and county officials for input on the detour alternative has been initiated.
 - Comment (Dave Peters GDOT): Is there no offset between the travel lanes and the bike accommodating shoulder? Update report to shoulder to ready bikeable shoulder not "bike lane".

arcadis.com

- Comment (Janet Middleton Arcadis): Changes have been made to the project to show rumble strip between the bike lane and roadway. These changes are reflected in the concept power point presentation will be update in the revised report
- Alternative 2 This alignment would shift the existing alignment to the north and remain within right-of-way. However, this Alternative will require construction temporary easement acquisition. Shifting the bridge to the north will allow the bridge alignment to be on a tangent section and curves, with an SE rate of 6%, would begin/end before the bridge deck. This allows the bridge to keep a normal crown (2%). This option would allow for an on-site detour.
 - Partial demolition the existing bridge, reducing the structure to one-lane, one-way. A temporary signal will be needed for one-lane traffic. This alternative would increase the cost of the project. This creates maintenance issues due to the longitudinal bridge joint on the structure. County resources to maintain it may not be available.
 - This alternative is impractical due to the length of detour and associated local community impacts.
- No Build This alternative is not preferred because the sufficiency rating for the existing bridge is 38.7, showing that this bridge needs to be replaced.

Project Cost Estimate

- Project Cost Estimate Arcadis Design Manager, Janet Middleton lead the discussion.
 At this time, section 404 mitigation, ROW, utilities are to be determined.
- Comment (Carol Kalafut GDOT Office Of Bridge Design): Check cost for bridge remove; typically use \$45/SF.

Discussion

- Comment (Carol Kalafut GDOT Office Of Bridge Design): Check cost for bridge; typically use \$150/SF.
- Comment (Janet Middleton Arcadis): For this project \$150 for the proposed bridge was used.

Questions / Additional Discussion

- Comment (Ryan Ward GDOT): Will the concept report meeting presentation made available?
- Comment (Patrick Pecot Arcadis): We will make the power point available.
- Comment (Ryan Ward GDOT): When will the preliminary plans be provide for tech studies?

Discussion

Comment (Patrick Pecot - Arcadis): Survey for this project was just received last week. Arcadis is to start preliminary plans at risk to facilitate recovery. We will follow-up after meeting to get dates for AOE Plans submittal

Action items Person responsible Deadline

MEETING MINUTES

Follow up with Ryan Ward – for preliminary plan submittal	Arcadis	ASAP
Provide concept team meeting power point presentation	Arcadis	ASAP
Update changes to concept report based on meeting comments provided.	Arcadis	ASAP
Carol Kalafut to follow up with additional information for proposed bridge width with bike lane.	Carol Kalafut	ASAP
Comments from attendees	All	6/19/2020



Concept Team Meetings

PI No.	Project Description	Name	Company	Phone	email
		Patrick Pecot	Arcadis	770-384-6588	patrick.pecot@arcadis.com
		Joshua Pisani	GDOT - Program Delivery	478-321-7327	jpisani@dot.ga.gov
		Derrick Cameron	GDOT - Program Delivery		dcameron@dot.ga.gov
		Janet Middleton	Arcadis	770-384-6566	janet.middleton@arcadis.com
		Patrick Pecot	Arcadis	770-384-6588	patrick.pecot@arcadis.com
		Natasha Morel	Arcadis		natasha.morel@arcadis.com
		Kumari Duvvuri	Arcadis	770-384-6620	Sri.Duvvuri@arcadis.com
		Ryan Ward	GDOT - OES	404-347-0176	ryward@dot.ga.gov
		Annie Williams	GDOT - OES	404-631-1468	awilliams@dot.ga.gov
0015605	CR 927/OLD HWY 46 @	Clayton Collins	GDOT - OES		ccollins@dot.ga.gov
0012002	ASH BRANCH	John Royal	GDOT - Utilities	912-242-9230	jroyal@dot.ga.gov
		Katheryn Graff	GDOT - OES		kgraff@dot.ga.gov
		Troy Pittman	GDOT - District 5 Preconstruction	912-530-4387	trpittman@dot.ga.gov
		Binyam, Araya	GDOT - District 5	912-651-2144	baraya@dot.ga.gov
		Justin Thrift	GDOT		jthrift@dot.ga.gov
		Brad Deal	Bulloch County - County Engineer	912-764-0127	
		Kevin Weitman			
		Dale Nembhard			
		Howard Anderson			
		Dave Peters	GDOT - Concept Design		dpeters@dot.ga.gov
PI No.	Project Description	Name	Company	Phone	email
		Patrick Pecot	Arcadis	770-384-6588	patrick.pecot@arcadis.com
		Joshua Pisani	GDOT - Program Delivery	478-321-7327	jpisani@dot.ga.gov
		Derrick Cameron	GDOT - Program Delivery		dcameron@dot.ga.gov
		Steven Gaines	American Consulting Prof. LLC	470-207-0635	sgaines@acp-ga.com_
		Allen Peterfreund	American Consulting Prof. LLC	706-229-6951	allen.peterfreund@acp-ga.com
		Kumari Duvvuri	Arcadis	770-384-6620	Sri.Duvvuri@arcadis.com



Concept Team Meetings

1	İ			1	
		Katheryn Graff	GDOT - OES		kgraff@dot.ga.gov
		Clayton Collins	GDOT - OES		ccollins@dot.ga.gov
		Ryan Ward	GDOT - OES	404-347-0176	ryward@dot.ga.gov
0015620	CR 203/SHILOH CHURCH ROAD @ SURVEYORS CREEK	Annie Williams	GDOT	404-631-1468	awilliams@dot.ga.gov
		Troy Pittman	GDOT - District 5 Preconstruction	912-530-4387	trpittman@dot.ga.gov
		Binyam, Araya	GDOT - District 5	912-651-2144	baraya@dot.ga.gov
		John Royal	GDOT - Utilities	912-242-9230	jroyal@dot.ga.gov
		Justin Thrift	GDOT		jthrift@dot.ga.gov
		Kevin Weitman			
		Dale Nembhard			
		Howard Anderson			
		Dave Peters	GDOT - Concept Design		dpeters@dot.ga.gov
		Dusty Mercer	GDOT Construction		dmercer@dot.ga.gov
PI No.	Project Description	Name	Company	Phone	email
	,		Company		
11101		Patrick Pecot	Arcadis	770-384-6588	patrick.pecot@arcadis.com
					patrick.pecot@arcadis.com jpisani@dot.ga.gov
		Patrick Pecot	Arcadis	770-384-6588	
		Patrick Pecot Joshua Pisani	Arcadis GDOT - Program Delivery	770-384-6588	jpisani@dot.ga.gov
		Patrick Pecot Joshua Pisani Derrick Cameron	Arcadis GDOT - Program Delivery GDOT - Program Delivery	770-384-6588 478-321-7327	jpisani@dot.ga.gov dcameron@dot.ga.gov
		Patrick Pecot Joshua Pisani Derrick Cameron Steven Gaines	Arcadis GDOT - Program Delivery GDOT - Program Delivery American Consulting Prof. LLC	770-384-6588 478-321-7327 470-207-0635	jpisani@dot.ga.gov dcameron@dot.ga.gov sgaines@acp-ga.com
		Patrick Pecot Joshua Pisani Derrick Cameron Steven Gaines Susan Beck	Arcadis GDOT - Program Delivery GDOT - Program Delivery American Consulting Prof. LLC GDOT Bridge Office	770-384-6588 478-321-7327 470-207-0635 706-229-6951	jpisani@dot.ga.gov dcameron@dot.ga.gov sgaines@acp-ga.com sbeck@dot.ga.gov
		Patrick Pecot Joshua Pisani Derrick Cameron Steven Gaines Susan Beck Kumari Duvvuri	Arcadis GDOT - Program Delivery GDOT - Program Delivery American Consulting Prof. LLC GDOT Bridge Office Arcadis	770-384-6588 478-321-7327 470-207-0635 706-229-6951	ipisani@dot.ga.gov dcameron@dot.ga.gov sgaines@acp-ga.com sbeck@dot.ga.gov Sri.Duvvuri@arcadis.com
		Patrick Pecot Joshua Pisani Derrick Cameron Steven Gaines Susan Beck Kumari Duvvuri Katheryn Graff	Arcadis GDOT - Program Delivery GDOT - Program Delivery American Consulting Prof. LLC GDOT Bridge Office Arcadis GDOT - OES	770-384-6588 478-321-7327 470-207-0635 706-229-6951	jpisani@dot.ga.gov dcameron@dot.ga.gov sgaines@acp-ga.com sbeck@dot.ga.gov Sri.Duvvuri@arcadis.com kgraff@dot.ga.gov
		Patrick Pecot Joshua Pisani Derrick Cameron Steven Gaines Susan Beck Kumari Duvvuri Katheryn Graff Clayton Collins	Arcadis GDOT - Program Delivery GDOT - Program Delivery American Consulting Prof. LLC GDOT Bridge Office Arcadis GDOT - OES GDOT - OES	770-384-6588 478-321-7327 470-207-0635 706-229-6951 770-384-6620	ipisani@dot.ga.gov dcameron@dot.ga.gov sgaines@acp-ga.com sbeck@dot.ga.gov Sri.Duvvuri@arcadis.com kgraff@dot.ga.gov ccollins@dot.ga.gov
0015641	CR305/TYRE BRIDGE ROAD @ SIXTY FOOT CREEK	Patrick Pecot Joshua Pisani Derrick Cameron Steven Gaines Susan Beck Kumari Duvvuri Katheryn Graff Clayton Collins Ryan Ward	Arcadis GDOT - Program Delivery GDOT - Program Delivery American Consulting Prof. LLC GDOT Bridge Office Arcadis GDOT - OES GDOT - OES	770-384-6588 478-321-7327 470-207-0635 706-229-6951 770-384-6620 404-347-0176	ipisani@dot.ga.gov dcameron@dot.ga.gov sgaines@acp-ga.com sbeck@dot.ga.gov Sri.Duvvuri@arcadis.com kgraff@dot.ga.gov ccollins@dot.ga.gov ryward@dot.ga.gov
	CR305/TYRE BRIDGE ROAD	Patrick Pecot Joshua Pisani Derrick Cameron Steven Gaines Susan Beck Kumari Duvvuri Katheryn Graff Clayton Collins Ryan Ward Annie Williams	Arcadis GDOT - Program Delivery GDOT - Program Delivery American Consulting Prof. LLC GDOT Bridge Office Arcadis GDOT - OES GDOT - OES GDOT - OES	770-384-6588 478-321-7327 470-207-0635 706-229-6951 770-384-6620 404-347-0176 404-631-1468	jpisani@dot.ga.gov dcameron@dot.ga.gov sgaines@acp-ga.com sbeck@dot.ga.gov Sri.Duvvuri@arcadis.com kgraff@dot.ga.gov ccollins@dot.ga.gov ryward@dot.ga.gov awilliams@dot.ga.gov
	CR305/TYRE BRIDGE ROAD	Patrick Pecot Joshua Pisani Derrick Cameron Steven Gaines Susan Beck Kumari Duvvuri Katheryn Graff Clayton Collins Ryan Ward Annie Williams Troy Pittman	Arcadis GDOT - Program Delivery GDOT - Program Delivery American Consulting Prof. LLC GDOT Bridge Office Arcadis GDOT - OES 770-384-6588 478-321-7327 470-207-0635 706-229-6951 770-384-6620 404-347-0176 404-631-1468 912-530-4387	ipisani@dot.ga.gov dcameron@dot.ga.gov sgaines@acp-ga.com sbeck@dot.ga.gov Sri.Duvvuri@arcadis.com kgraff@dot.ga.gov ccollins@dot.ga.gov ryward@dot.ga.gov awilliams@dot.ga.gov trpittman@dot.ga.gov	



Concept Team Meetings

Justin Thrift	GDOT	jthrift@dot.ga.gov
Kevin Weitman		
Dale Nembhard		
Howard Anderson		
Dave Peters	GDOT - Concept Design	dpeters@dot.ga.gov
Dusty Mercer	GDOT Construction	dmercer@dot.ga.gov
Jason Rubenbauer	Pierce County Manager	

AGENDA



Arcadis U.S., Inc.

A3M MEETING	MINUTES	Arcadis U.S., Inc. 2410 Paces Ferry Road #400
08/21/20	9:00 AM Virtual TEAMS Meeting	Atlanta Georgia 30339 Tel 770 431 8666
A3M Meeting for 00	015605, 0015620, and 0015641	Fax 770 435 2666
Meeting called by	GDOT Office of Program Delivery	
	(GDOT OPD)	
Type of meeting	A3M Meeting	
Attendees	See Attached Sign-In Sheet	
	Item	Presenter
	Welcome / Introduction / Sign-In	Joshua Pisani
PI 0015605 - CR 92	27/OLD HWY 46 @ ASH BRANCH 11.6 MI SE OF BROO	KLET, Bulloch County
Minutes prepared b	Natasha Morel, Patrick Pecot and Jane	et Middleton
	 Team Prime/PM/Traffic/Roadway/Bridge – Arcadis Survey – Accura Cons. and Eng., Inc. 	Patrick Pecot
Discussion	 Roadway Approach Limits Structure Layout Overview of Resources Ecology Buffer Impacts Wetland Impacts 	Janet Middleton, Patrick Pecot, Katheryn Graff
	The resources have been identified and are shown on the the bridge was discussed. Existing riprap will be removed, and h-piles will be pulled.	

bents from the existing bents. In assuming the worse, work bridge will be needed on

Coffer dams are used for under water construction not for demolition and will not be

this project as shown on sheet 20, in lieu of crane matting.

used on this project. Vibratory hammer will be utilized.

Arcadis will remove the 25' buffer around Open Water #1 (OW#1) is and Ephemeral Channel #2 (EC#2). OW #1 has no outlet and does not cross any boundaries. New federal regulation qualifies EC#2 as non-buffered state water.

Orange barrier fencing (OBF) will be added to the plans within right-of-way, around and leading up to the wetlands. For construction purposed place OBF with enough spacing to allow for construction equipment to move freely. Arcadis anticipates provide 15' offset from cut/fill and 5' offset from silt fence (10' offset from cut/fill).

Cut lines at rip rap will added to the plans. Will tie back to existing ground so that OW#1 is not impacted.

John Royal: Keep in mind that there are buried telecommunication lines on both sides of the existing bridge that will be only about 2 to 3 feet deep and any cut lines will need to be shown on the section 23 and 24 plan sheets. Owners tend to think that they can leave their facilities where there is only a fill line shown. The telephone lines will need to be relocated

The 2 archeological resources for the project have been located but not specified. They are located outside project limits. Christine Maverick confirmed there was no need for underwater archeology.

At the time of investigation, Ash Branch was impounded, and no water was flowing. Therefore, it was labeled as an open water resource.

Drainage for the bridge has not been completed; however, the bridge is in super and scuppers will possibly be used. Currently there is no environmental concerns with using scuppers and draining water into OW#4/Ash Branch.

Special provision will be needed for snakes and the spotted turtle.

Wetland buffers are not needed on this project, because resources will not be actively living in the wetland while construction is occurring.

Since design was started at risk by Arcadis, 1st submittal utilities are anticipated to be submitted in the following week.

PI0015620 - CR 203/SHILOH CHURCH RD @ SURVEYORS CREEK S OF HOMERVILLE, Clinch County

	_	
0	Lear	η

Prime/PM/Traffic - Arcadis

Roadway/Bridge - American Consulting

Survey - Accura Cons. and Eng., Inc.

Roadway Approach Limits

Structure Layout

Overview of Resources 0

Ecology 0

Buffer Impacts

Steven Gaines, Patrick Pecot, Mark

Patrick Pecot

Grindstaff


Discussion

	 Wetland Impacts 	
	 Additional Comments/Questions 	
PI0015641 - CF	R 305/TYRE BRIDGE RD @ SIXTY FOOT CREEK N OF	PATTERSON CITY, Pierce
County		
	o Team	
	 Prime/PM/Traffic/Survey – Arcadis 	
	 Roadway - American Consulting 	Patrick Pecot
	 Bridge – GDOT Bridge Group 	Tatrick T coot
	SUE – Accura Cons. and Eng., Inc.	
	Roadway Approach Limits	
	Structure Layout	
	Overview of Resources	Steven Gaines, Patrick Pecot, Mark
Discussion	o Ecology	
	 Buffer Impacts 	Grindstaff
	o Wetland Impacts	
	 Additional Comments/Questions 	
	Addition Questions/Comments	All
Action Item Re	eview	
Provide plans a	nd dgn files for 1 st Utility submission.	



A3M Meeting

PI No.	Project Description	Name	Company	Phone	email
0015605 0015620 0015641	(Bulloch, Clinch, Pierce Counties) - LOCBR Bundle 0015605-CR 927/Old Hwy 46 over Ash Branch in Bulloch County 0015620 - CR 203/Shiloh Church Rd @ Surveyors Creek S of Homerville 0015641-CR 305/Tyre Bridge Rd @ Sixty Foot Creek N of Patterson City	Patrick Pecot	Arcadis	770-384-6588	patrick.pecot@arcadis.com
		Joshua Pisani	GDOT - Program Delivery	478-321-7327	jpisani@dot.ga.gov
		Janet Middleton	Arcadis	770-384-6566	janet.middleton@arcadis.com
		Natasha Morel	Arcadis	770-384-6589	natasha.morel@arcadis.com
		Beau Marshall	NV5	678-795-3619	Beau.Marshall@nv5.com
		Trevor Brown	GDOT - District Construction		trbrown@dot.ga.gov
		Aaron Burgess	GDOT - NEPA		AaBurgess@dot.ga.gov
		Clayton Collins			CICollins@dot.ga.gov
		Donn Digamon	GDOT - Bridge	404-631-1847	dodigamon@dot.ga.gobv
		Donald Henderson			
		Katheryn Graff	NV5	404-808-8762	katheryn.graff@nv5.com
		Mary Trudeau			mtrudeau@edwards-pitman.com
		Dusty Mercer	GDOT - District Construction		dmercer@dot.ga.gov
		Steven Gaines	American Consulting Professionals	470-207-0635	sgaines@acp-ga.com
		Trieu Tran			
		Andrea Wahl	GDOT - OES - Ecology	404-631-1691	awhahl@dot.ga.gov
		Ryan Ward	GDOT - OES - Ecology	404-347-0176	ryward@dot.ga.gov
		Greg Wasdin			gwasdin@dot.ga.gov
		Kevin Weitman	GDOT - District Construction		kweitman@dot.ga.gov
		Christine Mavrick	GDOT - OES - Archaeology		cmavrick@dot.ga.gov
		Howard Anderson	American Consulting Professionals		Handerson@acp-ga.com
		Brandon McDaniel			bmcdaniel@dot.ga.gov
		Michael Garner			mgarner@dot.ga.gov
		Ogden			Logden@dot.ga.gov
		Douglas Chamblin			dchamblin@dot.ga.gov
		John Royal	GDOT - D5 Utilities	912-242-9230	jroyal@dot.ga.gov





Office of Program Delivery/AECOM

600 West Peachtree St, 25th Floor

Atlanta, GA 30308 Mobile: (478) 321-7327 E-mail: jpisani@dot.ga.gov

From: Pittman, Troy < trpittman@dot.ga.gov Sent: Tuesday, August 4, 2020 3:50 PM
To: Pisani, Joshua < JPisani@dot.ga.gov>

 $\textbf{Cc:} \ \ \text{Henry, Jeff} < \underline{\text{JHenry@dot.ga.gov}} >; \ \ \text{Mercer, Dusty} < \underline{\text{dmercer@dot.ga.gov}} >; \ \ \text{Araya, Binyam} < \underline{\text{baraya@dot.ga.gov}} >; \ \ \text{Araya.gov} >; \ \ \text{Araya, Binyam} < \underline{\text{baraya@dot.ga.gov}} >; \ \ \text{Araya.gov} >$

Weitman, Kevin < kweitman@dot.ga.gov">kweitman@dot.ga.gov>; McCall, Robert < kweitman@dot.ga.gov>

Subject: RE: PI#'s 0015605, 0015620, 0015641 (Bulloch, Clinch, Pierce Counties) - Request for concurrence statement,

off-site detour and preferred concept alternative

Joshua,

I have reviewed the proposed off-site detour routes, preferred alternative justifications, and CTM minutes for 0015605, 0015620, and 0015641 for Bulloch, Clinch, and Pierce Counties respectively. The District concurs with the proposed off-site detour routes provided that PDOHs are conducted for each project.

Thanks

Troy D. Pittman, P.E.

District Preconstruction Engineer



District 5 Jesup 204 Hwy 301 North P.O. Box 610 Jesup, GA, 31546 912.530.4387 office 912.282.3880 cell

From: Pisani, Joshua <<u>JPisani@dot.ga.gov</u>>
Sent: Monday, August 3, 2020 1:34 PM
To: Pittman, Troy <trpittman@dot.ga.gov>

Cc: Henry, Jeff < JHenry@dot.ga.gov>; Mercer, Dusty < dmercer@dot.ga.gov>; Araya, Binyam < baraya@dot.ga.gov>;

Weitman, Kevin <kweitman@dot.ga.gov>

Subject: PI#'s 0015605, 0015620, 0015641 (Bulloch, Clinch, Pierce Counties) - Request for concurrence statement, off-

site detour and preferred concept alternative

Importance: High

Good Afternoon Mr. Pittman,

I am the GDOT Project Manager for a bundle of LOCBR-programmed bridges being designed by the consultant ARCADIS. They are PI#'s 0015605, 0015620, and 0015641, located in Bulloch, Clinch, and Pierce Counties, respectively. Their locations are:

0015605: CR 927/OLD HWY 46 @ ASH BRANCH 11.6 MI SE OF BROOKLET

<u>0015620</u>: CR 203/SHILOH CHURCH ROAD @ SURVEYORS CREEK S OF HOMERVILLE <u>0015641</u>: CR 305/TYRE BRIDGE RD @ SIXTY FOOT CREEK N OF PATTERSON CITY

For the three LOCBR projects listed above, I am seeking a statement of concurrence that the preferred alternative for these projects utilizing an off-site detour is acceptable, and that the team has the districts' concurrence on the detour as mapped. I have attached the detour maps from the latest consultant-generated concept report revisions for your review. Meeting minutes from the Concept Team Meeting held 06/12/2020 have also been attached.

For all PI#s, the preferred alternative is to replace the bridge on the existing alignment while utilizing an off-site detour. This preferred alternative was chosen for these projects because it will have a smaller footprint, require less right of way acquisition and will decrease environmental impacts. The concurrence that I am looking for is to be added as additional rationale to preferred alternatives in the concept reports.

If you agree with the concept alternative rationales and detours after your review, please provide a statement of concurrence to be used in the reports. It would be greatly appreciated.

I can be contacted via email, or by phone directly at (478) 321-7327 if there are any additional questions or concerns.

Thanks,

Joshua Pisani, EIT Consultant Project Manager



Office of Program Delivery/AECOM

600 West Peachtree St, 25th Floor Atlanta, GA 30308

Mobile: (478) 321-7327 E-mail: jpisani@dot.ga.gov

You take every precaution - wash your hands, social distance, wear a mask. So, if you must drive, consider this ... higher speeds make for more serious crashes. To decrease the odds of a serious crash increase the distance between you and the vehicle in front of you. And slow down to the posted speed limit. Drive Alert Arrive Alive, Georgia.