

# DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA

## OFFICE OF DESIGN POLICY & SUPPORT INTERDEPARTMENTAL CORRESPONDENCE

**FILE** P.I. # 0007044  
CSBRG-0007-00(044)

**OFFICE** Design Policy & Support

Meriwether County  
GDOT District 3 - Thomaston  
SR 85 Bridge Replacement over CS 811/  
Lane Street in Manchester

**DATE** 1/30/2017

**FROM**  for Brent Story, State Design Policy Engineer

**TO** SEE DISTRIBUTION

**SUBJECT** APPROVED CONCEPT REPORT

Attached is the approved Concept Report for the above subject project.

Attachment

**DISTRIBUTION:**

Hiral Patel, Director of Engineering  
Joe Carpenter, Director of P3/Program Delivery  
Albert Shelby, State Program Delivery Engineer  
Darryl VanMeter, State Innovative Delivery Engineer  
Bobby Hilliard, Program Control Administrator  
Cindy VanDyke, State Transportation Planning Administrator  
Eric Duff, State Environmental Administrator  
Bill DuVall, State Bridge Engineer  
Andrew Heath, State Traffic Engineer  
Angela Robinson, Financial Management Administrator  
Lisa Myers, State Project Review Engineer  
Monica Flournoy, State Materials and Testing Administrator  
Patrick Allen, State Utilities Engineer  
Richard Cobb, Statewide Location Bureau Chief  
Andy Casey, State Roadway Design Engineer  
Attn: Joshua Taylor, Design Group Manager  
Michael Presley, District Engineer  
Adam Smith, District Preconstruction Engineer  
Scott Parker, District Utilities Engineer  
Derrick Cameron, Project Manager  
BOARD MEMBER - 3rd Congressional District

**DEPARTMENT OF TRANSPORTATION  
STATE OF GEORGIA  
LIMITED SCOPE PROJECT CONCEPT REPORT**

Project Type: <u>Bridge Replacement</u>	P.I. Number: <u>0007044</u>
GDOT District: <u>District 3</u>	County: <u>Meriwether</u>
Federal Route Number: <u>N/A</u>	State Route Number: <u>85</u>
Project Number: <u>CSBRG-0007-00(044)</u>	

This project proposes to replace the bridge on SR 85 over Lane Street/CS 811 in the city of Manchester in Meriwether County.

**Submitted for approval:**

C. Andy Cunniff 7/25/16  
State Roadway Design Engineer Date

Albert Shelby 8/15/16  
State Program Delivery Engineer Date

[Signature] 3 AUGUST 2016  
GDOT Project Manager Date

**Recommendation for approval:**

ERIC DUFF\*/EKP 8/18/2016  
State Environmental Administrator Date

CHRISTOPHER RAYMOND\*/EKP 8/25/2016  
State Traffic Engineer Date

BILL DUVALL\*/EKP 9/8/2016  
State Bridge Engineer Date

- ☐ MPO Area: This project is consistent with the MPO adopted Regional Transportation Plan (RTP)/Long Range Transportation Plan (LRTP).
- ☒ Rural Area: This project is consistent with the goals outlined in the Statewide Transportation Plan (SWTP) and/or is included in the State Transportation Improvement Program (STIP).

CINDY VAN DYKE\*/EKP 8/17/2016  
State Transportation Planning Administrator Date


**Approval:**

Concur: Hiral Patel 11/18/2017  
GDOT Director of Engineering Date

Approve: Margaret B. Purcell 1/24/17  
GDOT Chief Engineer Date

*\* - RECOMMENDATION ON FILE*

## PROJECT LOCATION MAP



PI 0007044/Meriwether County  
SR 85 at Lane Street Bridge Replacement

## PLANNING & BACKGROUND DATA

**Project Justification Statement:** This bridge (Structure ID 199-0032-0; SR 85 over Lane Street) was built in 1941. The bridge consists of three spans of steel beams on concrete caps and concrete columns. The bridge was designed using an H-15 vehicle, which is below the current design standards. The overall condition of this bridge would be classified as fair. The deck is in fair condition with minor concrete cracking and efflorescence. The superstructure is in fair condition. The substructure is in fair condition with moderate concrete cracking and spalls. The bridge's sufficiency rating is 46.90. Due to the structural integrity of the bridge, replacement is recommended.

**Existing conditions:** The existing typical section of SR 85/Broad Street consists of two 12-foot travel lanes, one in each direction, and sidewalk on both sides of the roadway. Additionally, SR 85 consists of Structure ID 199-0032-0 which is a bridge that consists of three spans of steel beams on concrete caps and concrete columns. Currently the beams are 21-inch steel beams. The bridge deck width is 42-ft 2.5-in and the bridge roadway curb to curb clear width is 29.90 feet with 5-foot sidewalks on both sides of the bridge. The total length of the bridge is 138 feet.

**Other projects in the area:**

- BR000-0005-00(532) PI No. 0005532, SR 85 at CSX railroad in Manchester  
Bridge Replacement  
Completion Date: 09/2016
- PI No. M005138, SR 41 from SR 85 to SR 18  
Resurfacing Project  
Let Date: 3/17/2017
- PI No. M005321, SR 85 Spur from SR 41 to SR 85  
Resurfacing Project  
Let Date: 3/17/2017

**MPO:** N/A

**TIP #:** N/A

**Congressional District(s):** 3

**Federal Oversight:** ☐ PoDI ☒ Exempt ☐ State Funded ☐ Other

**Projected Traffic:** AADT 24 HR T: 6.5%  
Current Year (2011): 4850 Open Year (2021): 5600 Design Year (2041): 7100  
Traffic Projections Performed by: GDOT Office of Planning

**Functional Classification (Mainline):** Rural Minor Arterial

**Complete Streets - Bicycle, Pedestrian, and/or Transit Standards Warrants:**

Warrants met: ☐ None ☒ Bicycle ☒ Pedestrian ☐ Transit

**Pavement Evaluation and Recommendations**

Preliminary Pavement Evaluation Summary Report Required? ☐ No ☒ Yes  
Preliminary Pavement Type Selection Report Required? ☒ No ☐ Yes  
Feasible Pavement Alternatives: ☒ HMA ☐ PCC ☐ HMA & PCC



## DESIGN AND STRUCTURAL

**Description of Proposed Project:** This project is located on State Route 85 over Lane Street in Meriwether County, 4.5 miles southeast of Warm Springs, Georgia. The sufficiency rating of the current bridge is 46.90 out of 100. The total length of the project is approximately 528 feet (.1 miles). Proposed is a new 138-ft long by 41-ft 6-in wide concrete bridge over Lane Street that will be reconstructed at the current location, elevation, and roadway centerline. An off-site detour will be utilized to route traffic from SR 85 northbound left onto SR 41/US 27(ALT)/W 2<sup>nd</sup> Street, then right onto SR 41/US 27(ALT)/S 5<sup>th</sup> Ave, then right onto SR 85 Spur/Perry Street, then right onto SR 85 Spur/Johnson Ave, then left back on to SR 85/Foster Street. The total detour route distance is 1.8 miles.

### Major Structures:

Structure ID	Existing	Proposed
Structure ID 199-0032-0	SR 85 consists of Structure ID 199-0032-0 which is a bridge that consists of three spans of steel beams on concrete caps and concrete columns. Currently the beams are 21" steam beams. The bridge deck width is 42-ft 2.5-in and the roadway curb to curb clear width is 29.90 feet with 5-foot sidewalks on both sides of the bridge. The total length of the bridge is 138 feet. The sufficiency rating of the bridge is 46.90.	The proposed structure is 138-ft long by 41-ft 6-in wide. The includes two 12-ft lanes and 5-ft 6-in sidewalks with a 2-ft border on both sides of the bridge.

### Mainline Design Features: SR 85

Feature	Existing	Standard*	Proposed
<b>Typical Section</b>			
- Number of Lanes	2 Lanes	2 Lanes	2 Lanes
- Lane Width(s)	12-ft	12-ft	Varies 12-ft to 14-ft 6-in
- Median Width & Type	N/A	N/A	N/A
- Border Area Width	Unknown	10-ft (2-ft paved, 8-ft unpaved)	Varies 10-ft to 16-ft
- Outside Shoulder Slope	Unknown N/A	6% N/A	2:1 Max N/A
- Inside Shoulder Width	N/A	N/A	N/A
- Sidewalks	5-ft	5-ft	5-ft
- Auxiliary Lanes	N/A	N/A	N/A
- Bike Lanes	N/A	N/A	N/A
Posted Speed	30 MPH		30 MPH
Design Speed	Unknown	30 MPH	30 MPH
Min Horizontal Curve Radius	Unknown	250-ft	Match Existing
Maximum Superelevation Rate	Unknown	4%	Match Existing
Maximum Grade	Unknown	8%	8%
Access Control	Permit	Permit	Permit
Design Vehicle	H-15	WB-67	WB-67
Pavement Type	Asphalt	Asphalt	Asphalt

**Bridge Design Features: SR 85 over Lane Street**

Feature	Existing	Standard*	Proposed
<b>Typical Section</b>			
- Number of Lanes	2 Lanes	2 Lanes	2 Lanes
- Lane Width(s)	12-ft	12-ft	12-ft
- Median Width & Type	N/A	N/A	N/A
- Border Area Width	N/A	N/A	2-ft Paved-Border
- Outside Shoulder Slope	N/A	N/A	N/A
- Inside Shoulder Width	N/A	N/A	N/A
- Sidewalks	5-ft	5-ft	5-ft 6-in
- Auxiliary Lanes	N/A	N/A	N/A
- Bike Lanes	N/A	N/A	N/A
Posted Speed	30 MPH		30 MPH
Design Speed	Unknown	30 MPH	30 MPH
Min Horizontal Curve Radius	Unknown	250-ft	Match Existing
Maximum Superelevation Rate	Unknown	4%	Match Existing
Maximum Grade	Unknown	8%	8%
Access Control	Permit	Permit	Permit
Design Vehicle	H-15	WB-67	WB-67
Pavement Type	Concrete	Concrete	Concrete

**Major Interchanges/Intersections:** N/A

**Lighting required:** ☒ No ☐ Yes

The current light fixtures within the project are attached to existing utility poles and are not directly associated with the bridge. Additionally, Bridge Replacement project PI No. 0005532 SR 85 at CSX railroad in Manchester did not include lighting, therefore this project will also not include lighting.

**Off-site Detours Anticipated:** ☐ No ☐ Undetermined ☒ Yes

**Transportation Management Plan [TMP] Required:** ☐ No ☒ Yes

If Yes: Project classified as: ☒ Non-Significant ☐ Significant

TMP Components Anticipated: ☒ TTC

**Design Exceptions to FHWA/AASHTO controlling criteria anticipated:** Unknown

**Design Variances to GDOT Standard Criteria anticipated:** Unknown

## UTILITY AND PROPERTY

**Railroad Involvement:** CSX

**Utility Involvements:**

Electricity	Georgia Power (Distribution)
Gas	City of Manchester
Water	City of Manchester
Sewer	City of Manchester
Telecommunications	AT&T
Telecommunications	Charter Communications

**SUE Required:** ☐ No ☒ Yes

**Public Interest Determination Policy and Procedure recommended?** ☒ No ☐ Yes

**Right-of-Way:** Existing width: Varies 150-200 ft. Proposed width: Within 150-200' existing RW

Required Right-of-Way anticipated: ☐ No ☐ Yes ☒ Undetermined

Easements anticipated: ☐ None ☒ Temporary ☒ Permanent ☐ Utility ☐ Other

Anticipated total number of impacted parcels:	<u>4</u>
Displacements anticipated:	Businesses: <u>0</u>
	Residences: <u>0</u>
	Other: <u>0</u>
Total Displacements:	<u>0</u>

**Impacts to USACE property anticipated?** ☒ No ☐ Yes ☐ Undetermined

## CONTEXT SENSITIVE SOLUTIONS

**Issues of Concern:** Area may be historic therefore homes may be under the Environmental Justice classification.

**Context Sensitive Solutions Proposed:**

## ENVIRONMENTAL AND PERMITS

**Anticipated Environmental Document:**

**NEPA:** ☐ PCE ☒ CE ☐ EA-FONSI

**GEPA\*:** ☐ Type A ☐ Type B ☐ None

**Level of Environmental Analysis:**

☐ The environmental considerations noted below are based on preliminary desktop or screening level environmental analysis and are subject to revision after the completion of resource identification, delineation, and agency concurrence.

☒ The environmental considerations noted below are based on the completion of resource identification, delineation, and agency concurrence.

**MS4 Compliance – Is the project located in an MS4 area?** ☒ No ☐ Yes

**Is Protected Species water quality mitigation anticipated?** ☒ No ☐ Yes

**Environmental Permits, Variances, Commitments, and Coordination anticipated:** CWA Section 404 Permit, NPDES

**Air Quality:**

Is the project located in an Ozone Non-attainment area? ☒ No ☐ Yes

Carbon Monoxide hotspot analysis: ☐ Required ☒ Not Required ☐ TBD

**NEPA/GEPA Comments & Information:** Categorical Exclusion.

## COORDINATION, ACTIVITIES, RESPONSIBILITIES, AND COSTS

**Project Meetings:** Concept Meeting held 6/13/2016. See attachments for minutes.

**Other coordination to date:** Project Coordination Meeting held 3/16/2016

Project Activity	Party Responsible for Performing Task(s)
Concept Development	GDOT – Office of Roadway Design
Design	GDOT – Office of Roadway Design
Right-of-Way Acquisition	GDOT – Office of Right of Way
Utility Coordination (Preconstruction)	GDOT – Office of Utilities
Utility Relocation (Construction)	Utility Owners
Letting to Contract	GDOT – Office of Construction Bidding Administration
Construction Supervision	GDOT – District 3 Construction
Providing Material Pits	Contractor
Providing Detours	Contractor
Environmental Studies, Documents, & Permits	GDOT – Environmental Services
Environmental Mitigation	GDOT – Environmental Services
Construction Inspection & Materials Testing	GDOT – Materials & Research Office

### Project Cost Estimate and Funding Responsibilities:

	PE Activities		ROW	Reimbursable Utilities	CST*	Total Cost
	PE Funding	Section 404 Mitigation				
Funded By	GDOT		GDOT	GDOT	GDOT	<i>\$2,202,732</i>
\$ Amount	\$806,795.36		\$159,000	\$100,000	<i><del>\$1,136,937</del></i> <del>\$1,094,104.28</del>	<del>\$2,159,899.64</del>
Date of Estimate	5/6/2009		9/29/2014	6/13/2016	10/6/2016	

\*CST Cost includes: Construction, Engineering and Inspection, Contingencies and Liquid AC Cost Adjustment.

## ALTERNATIVES DISCUSSION

**Preferred Alternative:** Replace the existing bridge at the existing location and elevation using an offsite detour.

<b>Estimated Property Impacts:</b>	<b>None</b>	<b>Estimated Total Cost:</b>	<b>\$2,159,899.64</b>
<b>Estimated ROW Cost:</b>	<b>\$159,000.00</b>	<b>Estimated CST Time:</b>	<b>18 Months</b>

**Rationale:** This alternative would close the bridge to traffic and provide an off-site detour during construction. The proposed northbound detour would reroute traffic from SR 85/Broad Street left on to SR 41/US 27(ALT)/W 2<sup>nd</sup> Street, continue right on to SR 41/US 27(ALT)/S 5<sup>th</sup> Ave, then right onto SR 85 Spur/Perry Street, then right on to SR 85 Spur/Truitt Street, then left back on to SR 85/Foster Street. The proposed detour route would be 1.8 miles in length.







<b>No-Build Alternative:</b>			
<b>Estimated Property Impacts:</b>	<b>None</b>	<b>Estimated Total Cost:</b>	<b>\$0.00</b>
<b>Estimated ROW Cost:</b>	<b>\$0.00</b>	<b>Estimated CST Time:</b>	<b>None</b>
<b>Rationale:</b> This alternative would not meet the project justification as the structural integrity of the bridge is insufficient.			

**Comments/Additional Information:**

**LIST OF ATTACHMENTS/SUPPORTING DATA**

1. Typical sections
2. Detour Map
3. Cost Estimates
  - Construction including Engineering and Inspection
  - Completed Fuel & Asphalt Price Adjustment Forms
  - Preliminary Utility Cost Estimate
  - Preliminary Right of Way Cost Estimate
4. Concept Utility Report
5. Traffic Counts
6. Bridge Inventory Data
7. Concept Team Meeting Sign-In Sheets
  - \*Please contact the Project Manager for Concept Team Meeting Minutes



# REQUIRED PAVEMENT

- (A) RECYCLED ASPHALTIC CONCRETE 9.5 mm SUPERPAVE, 135 lb/sy, TYPE 2, GP 2 ONLY, INCL BITUM MATL & H LIME
- (B) RECYCLED ASPHALTIC CONCRETE 19 mm SUPERPAVE, 220 lb/sy, GP 1 OR 2, INCL BITUM MATL & H LIME
- (C) RECYCLED ASPHALTIC CONCRETE 25 mm SUPERPAVE, 440 lb/sy, GP 1 OR 2, INCL BITUM MATL & H LIME
- (D) GRADED AGGREGATE BASE COURSE, 10", INCL MATL
- (E) MILL ASPH CONC PVMT, 1½ IN DEPTH
- (F) 8" x 30" CONC. CURB & GUTTER, GA. STD. 9032 B, TYPE 2
- (H) LEVELING COURSE, VARIABLE DEPTH
- (J) 4" CONC SIDEWALK
- (P) CONCRETE HEADER CURB, 6 INCH, TP 2




## REVISION DATES


## TYPICAL SECTIONS

CHECKED:	DATE:	DRAWING No.
BATCH CHECKED:	DATE:	05-0001
CORRECTED:	DATE:	
VERIFIED:	DATE:	







Job ID 0007044\_CONCEPT

## DETAILED COST ESTIMATE

JOB NUMBER: 0007044\_CONCEPT

FED/STATE PROJECT NUMBER: 0007044

SPEC YEAR: 13

DESCRIPTION: SR 85 @ CS 811/LANE STREET IN MANCHESTERAssigned Control Group:

OFFICE OF ROADWAY DESIGN

### ITEMS FOR JOB 0007044\_CONCEPT

#### 0010 - ROADWAY ITEMS

LINE NUMBER	ITEM	QUANTITY	UNITS	PRICE	DESCRIPTION	AMOUNT
0005	150-1000	1.00	LS	\$50,000.00000	TRAFFIC CONTROL -	\$50,000.00
0010	153-1300	1.00	EA	\$81,980.79145	FIELD ENGINEERS OFFICE TP 3	\$81,980.79
0015	210-0100	1.00	LS	\$250,000.00000	GRADING COMPLETE -	\$250,000.00
0020	310-1101	368.00	TN	\$28.20394	GR AGGR BASE CRS, INCL MATL	\$10,379.05
0030	402-3103	72.00	TN	\$69.63928	REC AC 9.5 MM SP,TPII,GP2, INCL BM & H L	\$5,014.03
0035	402-3121	139.00	TN	\$85.97145	RECYL AC 25MM SP,GP1/2,BM&HL	\$11,950.03
0040	402-3190	70.00	TN	\$95.72578	RECYL AC 19 MM SP,GP 1 OR 2 ,INC BM&HL	\$6,700.80
0045	413-0750	208.00	GL	\$3.00000	TACK COAT	\$624.00
0050	432-0206	134.00	SY	\$10.16541	MILL ASPH CONC PVMT/ 1.50 DEP	\$1,362.16
0055	441-0104	267.00	SY	\$42.94659	CONC SIDEWALK, 4 IN	\$11,466.74
0065	634-1200	5.00	EA	\$123.68346	RIGHT OF WAY MARKERS	\$618.42
0070	433-1000	215.00	SY	\$171.72638	REINF CONC APPROACH SLAB	\$36,921.17
0220	441-6222	592.00	LF	\$19.67958	CONC CURB & GUTTER/ 8X30TP2	\$11,650.31
0225	641-1100	84.00	LF	\$61.85342	GUARDRAIL, TP T	\$5,195.69
0230	641-1200	50.00	LF	\$22.13997	GUARDRAIL, TP W	\$1,107.00
0235	641-5012	4.00	EA	\$1,919.94907	GUARDRAIL ANCHORAGE, TP 12	\$7,679.80
ROADWAY ITEMS Total						\$492,649.99

#### 0020 - BRIDGE REPLACEMENT

LINE NUMBER	ITEM	QUANTITY	UNITS	PRICE	DESCRIPTION	AMOUNT
0075	540-1101	1.00	LS	\$86,000.00000	REM OF EX BR, STA NO -	\$86,000.00
0080	543-9000	1.00	LS	\$458,160.00000	CONSTR OF BRIDGE COMPLETE -	\$458,160.00
BRIDGE REPLACEMENT Total						\$544,160.00

#### 0030 - TEMPORARY EROSION CONTROL

LINE NUMBER	ITEM	QUANTITY	UNITS	PRICE	DESCRIPTION	AMOUNT
0085	163-0232	1.00	AC	\$496.84205	TEMPORARY GRASSING	\$496.84
0090	163-0240	3.00	TN	\$404.29085	MULCH	\$1,212.87
0095	163-0300	2.00	EA	\$1,351.83648	CONSTRUCTION EXIT	\$2,703.67
0100	163-0550	4.00	EA	\$144.41753	CONS & REM INLET SEDIMENT TRAP	\$577.67
0105	165-0030	600.00	LF	\$0.83195	MAINT OF TEMP SILT FENCE, TP C	\$499.17
0110	165-0101	2.00	EA	\$476.17333	MAINT OF CONST EXIT	\$952.35
0115	165-0105	4.00	EA	\$54.56516	MAINT OF INLET SEDIMENT TRAP	\$218.26
0120	167-1000	2.00	EA	\$233.85116	WATER QUALITY MONITORING AND SAMPLING	\$467.70
0125	167-1500	18.00	MO	\$409.49741	WATER QUALITY INSPECTIONS	\$7,370.95
0130	171-0030	1200.00	LF	\$3.20765	TEMPORARY SILT FENCE, TYPE C	\$3,849.18
0135	643-8200	340.00	LF	\$1.45332	BARRIER FENCE (ORANGE), 4 FT	\$494.13
TEMPORARY EROSION CONTROL Total						\$18,842.79

#### 0040 - PERMANENT EROSION CONTROL

LINE NUMBER	ITEM	QUANTITY	UNITS	PRICE	DESCRIPTION	AMOUNT
0140	716-2000	3000.00	SY	\$1.13880	EROSION CONTROL MATS, SLOPES	\$3,416.40
0145	700-6910	2.00	AC	\$855.16030	PERMANENT GRASSING	\$1,710.32
0150	700-7000	5.00	TN	\$94.39182	AGRICULTURAL LIME	\$471.96
0155	700-8000	3.00	TN	\$611.03688	FERTILIZER MIXED GRADE	\$1,833.11
0160	700-8100	120.00	LB	\$3.02300	FERTILIZER NITROGEN CONTENT	\$362.76
<b>PERMANENT EROSION CONTROL Total</b>						<b>\$7,794.55</b>

**0050 - DRAINAGE**

LINE NUMBER	ITEM	QUANTITY	UNITS	PRICE	DESCRIPTION	AMOUNT
0165	550-1180	35.00	LF	\$52.25049	STM DR PIPE 18,H 1-10	\$1,828.77
0170	668-1100	4.00	EA	\$2,273.88269	CATCH BASIN, GP 1	\$9,095.53
0240	441-0301	4.00	EA	\$1,670.43205	CONC SPILLWAY, TP 1	\$6,681.73
0245	603-2181	100.00	SY	\$40.65078	STN DUMPED RIP RAP, TP 3, 18	\$4,065.08
0250	603-7000	100.00	SY	\$4.08945	PLASTIC FILTER FABRIC	\$408.95
<b>DRAINAGE Total</b>						<b>\$22,080.06</b>

**0060 - SIGNING & MARKING**

LINE NUMBER	ITEM	QUANTITY	UNITS	PRICE	DESCRIPTION	AMOUNT
0175	636-1036	18.00	SF	\$20.00000	HWY SGN,TP1MAT,REFL SH TP 11	\$360.00
0180	636-2090	28.00	LF	\$7.89407	GALV STEEL POSTS, TP 9	\$221.03
0185	636-1033	5.00	SF	\$22.11777	HWY SIGNS, TP1MAT,REFL SH TP 9	\$110.59
0190	636-2070	14.00	LF	\$8.97577	GALV STEEL POSTS, TP 7	\$125.66
0195	653-1501	540.00	LF	\$0.77054	THERMO SOLID TRAF ST 5 IN, WHI	\$416.09
0200	653-1502	540.00	LF	\$0.66668	THERMO SOLID TRAF ST, 5 IN YEL	\$360.01
0205	654-1001	12.00	EA	\$5.17015	RAISED PVMT MARKERS TP 1	\$62.04
0210	657-1085	276.00	LF	\$6.86465	PRF PL SD PVT MKG,8,B/W,TP PB	\$1,894.64
0215	657-6085	276.00	LF	\$6.68077	PRF PL SD PVMT MKG,8,B/Y,TPPB	\$1,843.89
<b>SIGNING &amp; MARKING Total</b>						<b>\$5,393.95</b>

**TOTALS FOR JOB 0007044 CONCEPT**

ITEMS COST:	\$1,090,921.34
COST GROUP COST:	\$0.00
ESTIMATED COST:	\$1,079,765.58
CONTINGENCY PERCENT:	0.00%
ENGINEERING AND INSPECTION:	5.00%
ESTIMATED COST WITH CONTINGENCY AND E&I:	\$1,133,753.86

File Location: Div of Preconstruction > CES

CONFIDENTIALITY NOTICE: This document may contain confidential and/or privileged information. Any unauthorized duplication, disclosure,

distribution/retransmission of taking of any action in reliance upon the material in this document is strictly forbidden.

PROJ. NO.		CALL NO.
P.I. NO.	0007044	
DATE	10/20/2016	

INDEX (TYPE)	DATE	INDEX
REG. UNLEADED	Mar-16	\$ 1.671
DIESEL		\$ 2.009
LIQUID AC		\$ 355.00

Link to Fuel and AC Index:

<http://www.dot.ga.gov/doingbusiness/Materials/Pages/asphaltcementindex.aspx>

#### LIQUID AC ADJUSTMENTS

PA=[((APM-APL)/APL)]xTMTxAPL

##### Asphalt

Price Adjustment (PA)					2992.65	\$	2,992.65
Monthly Asphalt Cement Price month placed (APM)	Max. Cap	60%	\$	568.00			
Monthly Asphalt Cement Price month project let (APL)			\$	355.00			
Total Monthly Tonnage of asphalt cement (TMT)					14.05		

ASPHALT	Tons	%AC	AC ton
Leveling	0	5.0%	0
12.5 OGFC	0	5.0%	0
12.5 mm	0	5.0%	0
9.5 mm SP	72	5.0%	3.6
25 mm SP	139	5.0%	6.95
19 mm SP	70	5.0%	3.5
	281		14.05

##### BITUMINOUS TACK COAT

Price Adjustment (PA)				\$	190.29	\$	190.29
Monthly Asphalt Cement Price month placed (APM)	Max. Cap	60%	\$	568.00			
Monthly Asphalt Cement Price month project let (APL)			\$	355.00			
Total Monthly Tonnage of asphalt cement (TMT)					0.893380992		

##### Bitum Tack

Gals	gals/ton	tons
208	232.8234	0.89338099

##### BITUMINOUS TACK COAT (surface treatment)

Price Adjustment (PA)					0	\$	-
Monthly Asphalt Cement Price month placed (APM)	Max. Cap	60%	\$	568.00			
Monthly Asphalt Cement Price month project let (APL)			\$	355.00			
Total Monthly Tonnage of asphalt cement (TMT)					0		

Bitum Tack	SY	Gals/SY	Gals	gals/ton	tons
Single Surf. Trmt.	0	0.20	0	232.8234	0
Double Surf.Trmt.	0	0.44	0	232.8234	0
Triple Surf. Trmt	0	0.71	0	232.8234	0
					0

<b>TOTAL LIQUID AC ADJUSTMENT</b>	<b>\$</b>	<b>3,182.94</b>
-----------------------------------	-----------	-----------------

**DEPARTMENT OF TRANSPORTATION  
STATE OF GEORGIA**

**INTERDEPARTMENT CORRESPONDENCE**

**FILE**

Project No: **CSBRG-0007-00(044)**  
County **Meriwether**  
P.I. # **0007044**

Office: Thomaston  
Date: June 13, 2016

Description: **Bridge replacement on SR 85 at CS 081117/Lane Street in Manchester**

**FROM** Scott K. Parker, District Utilities Engineer

**TO** Justin Banks, Project Manager

**SUBJECT PRELIMINARY UTILITY COST ESTIMATE**

A review of utilities located on the above referenced project has been conducted without a design concept.. Listed below is a breakdown of the anticipated reimbursable and non-reimbursable cost.

<u>Utility Owner</u>	<u>Reimbursable</u>	<u>Non-Reimbursable</u>	<u>Estimate Based on</u>
Georgia Power - Distribution	\$100,000.00	\$0.00	Site Visit / Available Drawings
AT&T	\$0.00	\$30,000.00	Site Visit / Available Drawings
City of Manchester - Gas	\$0.00	\$21,000.00	Site Visit / Available Drawings
City of Manchester - Water	\$0.00	\$54,000.00	Site Visit / Available Drawings
City of Manchester - Sewer	\$0.00	\$2,000.00	
Charter Communications	\$0.00	\$2,400.00	
	\$0.00	\$0.00	
	\$0.00	\$0.00	
	\$0.00	\$0.00	
	\$0.00	\$0.00	
	\$0.00	\$0.00	
<b>Total 0.00%</b>	<b>\$ 100,000.00</b>	<b>\$ 109,400.00</b>	
<b>Department Responsibility 100.00%</b>	<b>\$ 100,000.00</b>	<b>\$ 0.00</b>	
<b>Local Sponsor Responsibility 0.00%</b>	<b>\$ 0.00</b>	<b>\$ 0.00</b>	<b>PFA Dated N/A with N/A</b>

Estimate is based on the best available information at the current stage, unforeseen prior rights information may be provided by the Utility Company at a later date that could cause some non-reimbursable costs to shift to the reimbursable cost column.

If additional information is needed, please contact Gene McKissick at 706-646-7604.

cc: Yulonda Pride-Foster, State Utilities Preconstruction Engineer  
Lee Upkins, State Utilities Office  
Adam Smith, District Preconstruction Engineer



# Department of Transportation

## State of Georgia

-----

### Interdepartmental Correspondence

<b>FILE</b>	R/W Cost Estimate	<b>OFFICE</b>	Atlanta
		<b>DATE</b>	September 29, 2014
<b>FROM</b>	Phil Copeland, Right of Way Administrator LaShone Alexander, RW Cost Estimator		
<b>TO</b>	Justin Banks, Project Manager		
<b>SUBJECT</b>	<b>Preliminary Right of Way Cost Estimate</b> <b>Project: CSBRG-007-00(044) Meriwether County</b> <b>P.I. No.: 0007044</b> <b>Description: S.R. 85 @CS081117 Lane Street in Manchester</b>		

As per your request, attached is a copy of the approved Preliminary Right of Way Cost Estimates on the above referenced projects.

If you have any questions, please contact LaShone Alexander at One Georgia Center 600 West Parkway Street, NW Atlanta, GA 30308, Right of Way Office at (478) 553-1569 or (478) 232-4045.

PC:LA  
Attachments  
c: File

GEORGIA DEPARTMENT OF TRANSPORTATION  
PRELIMINARY ROW COST ESTIMATE SUMMARY

Date: 9/29/2014

Project: CSBRG-0007-00-(044)

Revised:

County: Meriwether

PI: 0007044

Description: SR85@CS081117 Lane Street in Manchester  
Project Termini: Bridge Replacements

Existing ROW: Varies

Parcels: 4

Required ROW: Varies

Land and Improvements \$60,000.00

Proximity Damage \$0.00

Consequential Damage \$0.00

Cost to Cures \$0.00

Trade Fixtures \$0.00

Improvements \$25,000.00

Valuation Services \$15,000.00

Legal Services \$40,200.00

Relocation \$8,000.00

Demolition \$0.00

Administrative \$35,500.00

TOTAL ESTIMATED COSTS \$158,700.00

**TOTAL ESTIMATED COSTS (ROUNDED) \$159,000.00**

Preparation Credits	Hours	Signature

Prepared By: Dathone Alexander CG#: 286999 09/29/2014 (ATE)

Approved By: Dathone Alexander CG#: 286999 09/29/2014 (ATE)

NOTE: No Market Appreciation is included in this Preliminary Cost Estimate

# Concept Utility Report

---

**Project Number:** CSBRG-0007-00(044)

**District:** 3

**County:** Meriwether

**Prepared by:** Gene McKissick

**P.I. #** 0007044

**Date:** 6/3/2016

**Project Description:** Bridge replacement on SR 85 @ CS 081117/Lane Street in Manchester

---

*The information provided herein has been gathered from Georgia811 and/or field visits and serves as an estimate. Nothing contained in this report is to be used as a substitute for 1<sup>st</sup> Submission or SUE.*

**Are SUE services recommended?** Yes Level: ☐ A ☒ B ☐ C ☐ D

**Public Interest Determination (PID):** ☐ Automatic ☐ Mandatory ☐ Consideration  
☐ No Use ☒ Exempt

**Is a separate utility funding phase recommended?** Yes, assuming Ga. Power Co. will be reimbursable.

**Existing Facilities:** \_\_\_\_\_

Georgia Power - Distribution -- Electrical

AT&T -- Telecommunications

City of Manchester - Gas

City of Manchester - Water

City of Manchester - Sewer

**Potential Project (Schedule/Budget) Impacts:** An existing aerial telephone cable is located under the north end of the bridge that will need to be relcoated prior to the demolition of the bridge.

**Capital Improvement Projects (Utilities) Anticipated in the Area:** None anticipated

**Project Specific Recommendations for Avoidance/Mitigation:** Pursue early authorization for utility relocations.

**Right of Way Coordination:** Purchase permanent easements with the right to place utilities

**Environmental Coordination:** Environmental studies will need to factor in the relocation of utilities.

**Additional Remarks:** None

# Department of Transportation State of Georgia

---

## INTERDEPARTMENT CORRESPONDENCE

**FILE** CSBRG-0007-00(044), Meriwether County **OFFICE** Planning  
P.I. # 0007044  
**DATE** May 7, 2014

**FROM** Cynthia L. VanDyke, State Transportation Planning Administrator

**TO** Albert Shelby, State Program Delivery Engineer  
**Attention:** Krystal Stovall-Dixon

**SUBJECT** **Link Volume Traffic** for SR 85 @ CS 081117 LANE STREET IN MANCHESTER.

The Link Volume Traffic is below:

**TC # 0175**  
**BUILD = NO BUILD**

2011 AADT	4850
2012 DHV	440
2021 AADT	5600
2021 DHV	505
2041 AADT	7100
2041 DHV	640
K	9%
D	55%
T	3.5%
S.U.	3.25%
COMB.	0.25%
24 HOUR T	6.5%
S.U.	4.5%
COMB.	2%

If you have any questions concerning this information please contact Abby Ebodaghe at (404) 631-1923.



## Bridge Inventory Data Listing



## Parameters: Bridge Serial Num

Structure ID:199-0032-0

Meriwether

SUFF. RATING: 46.90

## Location &amp; Geography

**Structure ID:** 199-0032-0

200 Bridge Information: 07

\*6A Feature Int: CS 23023 -000.10E

\*6B Critical Bridge:

\*7A Route No Carried: SR00085

\*7B Facility Carried: SR 85

9 Location: IN MANCHESTER

2 Dot District: 4841300000 - D3 District Three Thomaston

207 Year Photo: 2012

\*91 Inspection Frequency: 24 Date: 03/19/2014

92A Fract Crit Insp Freq: 0 Date: 02/01/1901

92B Underwater Insp Freq: 00 Date: 02/01/1901

92C Other Spc. Insp Freq: 00 Date: 02/01/1901

\* 4 Place Code: 49532

\*5 Inventory Route(O/U): 1

Type: 3 - State

Designation: 1- Mainline

Number: 00085

Direction: 0. Not applicable

\*16 Latitude: 32.0000- 51.2520 HMMS Prefix:SR

\*17 Longitude: 84.0000- 36.6408 HMMS Suffix:00

MP: 0.28

98 Border Bridge: % Shared:00

99 ID Number: 0000000000000000

\*100 STRAHNET: 0- The Feature is not a STRAHNET route.

12 Base Highway Network: 1

13A LRS Inventory Route: 1991008500

13B Sub Inventory Route: 0.00

\*101 Parallel Structure: N. No parallel structure exists

\*102 Direction of Traffic: 2- Two Way

\*264 Road Inventory Mile Post: 000.93

\*208 Inspection Area: Area 03 Initials: WBP

Engineer's Initials: eep

\* Location ID No: 199-00085D-000.28N

\*104 Highway System: 0- Inventory Route is not on the NHS

\*26 Functional Classification: 6- Rural - Minor Arterial

\*204 Federal Route Type: F - Primary. No: 01501

105 Federal Lands Highway: 0. Not applicable

\*110 Truck Route: 0

206 School Bus Route: 1

217 Benchmark Elevation: 0000.00

218 Datum: 0- Not Applicable

\*19 Bypass Length: 1

\*20 Toll: 3- On a Free Road or Non-Highway

\*21 Maintenance: 01-State Highway Agency.

\*22 Owner: 01-State Highway Agency.

\*31 Design Load: 2- H 15

37 Historical Significance: 5- Not eligible for the National Register of Historic Places

205 Congressional District: 003

27 Year Constructed: 1941

106 Year Reconstructed: 0

33 Bridge Median: 0-None

34 Skew: 36

35 Structure Flared: No

38 Navigation Control: N- Bridge is not over water

213 Special Steel Design: 0- Not applicable or other

267 Type of Paint: 5- Waterborne System (Type VI or VII)

\*42 Type of Service On: 5-Highway-Pedestrian

Type of Service Under: 1-Highway (with or without pedestrians)

214 Movable Bridge: 0

203 Type Bridge: A- Spread - O. Concrete M. Steel - O. Concrete

259 Pile Encasement 3

\*43 Structure Type Main: 3-Steel 2-Stringer/Multi-Beam or Girder

45 No.Spans Main: 3

44 Structure Type Appr: 0- Other 0- Other

46 No Spans Appr: 0

226 Bridge Curve Horiz 1 Vert: 1.00

111 Pier Protection N - Navigation Control item coded 0, or Feature not a waterway

107 Deck Structure Type:

108 Wearing Structure Type:

Membrane Type:

Deck Protection:

## Signs &amp; Attachments

225 Expansion Joint Type: 02- Open or sealed concrete joint (silicone sealant). 0- None.

242 Deck Drains: 0- None present.

243 Parapet Location: 0- None present.

Height: 0.00

Width: 0.00

238 Curb Height: 1

Curb Material: 1- Concrete.

239 Handrail 1- Concrete. 1- Concrete.

\*240 Median Barrier Rail: 0- None.

241 Bridge Median Height: 0

\* Bridge Median Width: 0

230 Guardrail Loc. Dir. Rear: 0- None.

Fwd: 0- None.

Oppo. Dir. Rear: 0- None.

Oppo. Fwd: 0- None.

244 Approach Slab 3- Forward and Rear.

224 Retaining Wall: 0- None.

233Posted Speed Limit: 30

236 Warning Sign: 0.00

234 Delineator: 1.00

235 Hazard Boards: 0

237 Utilities Gas: 00- Not Applicable

Water: 00- Not Applicable

Electric: 22- Bottom Right.

Telephone: 00- Not Applicable

Sewer: 00- Not Applicable

247 Lighting Street: 0

Navigation: 0

Aerial: 0- Not

\*248 County Continuity No.: 00

## Bridge Inventory Data Listing



## Parameters: Bridge Serial Num

## Structure ID:199-0032-0

Programming Data			Measurements:					
201 Project No:	FAGM 159-A (1)		*29 ADT	5350	Year:2011	65 Inventory Rating Method:	2-Allowable Stress (AS)	
202 Plans Available:	0- No Plans Available.		109 %Trucks:	1		63 Operating Rating Method:	2-Allowable Stress (AS)	
249 Prop Proj No:	BRG-0007-00(044)		* 28 Lanes On:	2	Under:2	66 Inventory Type:	2 - HS loading. Rating: 19	
250 Approval Status:	0000		210 No. Tracks On:	00	Under:00	64 Operating Type:	2 - HS loading. Rating: 33	
251 PI Number:	0007044		* 48 Max. Span Length	65		231Calculated Loads:		
252 Contract Date:	02/01/1901		* 49 Structure Length:	138		H-Modified:	20	0
260 Seismic No:	00000		51 Br. Rwdy. Width	29.90		HS-Modified:	25	0
75 Type Work:	34- Widening	1- Work to be done by contract	52 Deck Width:	42.20		Type 3:	25	0
94 Bridge Imp. Cost:	with deck \$539		* 47 Tot. Horiz. Cl:	30		Type 3s2:	40	0
95 Roadway Imp. Cost:	\$54		50 Curb / Sidewalk Width	5.00	/ 5.00	Timber:	32	0
96 Total Imp Cost:	\$809		32 Approach Rdwy. Width	30		Piggyback:	40	0
76 Imp Length:	348		*229 Shoulder Width:			261 H Inventory Rating:	15	
97 Imp Year:	2013		Rear Lt:	0.00	Type: 7 - Rt:0	262 H Operating Rating	26	
114 Fureur ADT:	8025	Year:2031	Fwd. Lt:	0.00	Type: 7 - Rt:0	67 Structural Evaluation:	4	
Hydraulic Data			Pavement Width:			58 Deck Condition:	6 - Satisfactory Condition	
215Waterway Data:			Rear:	30.00	Type: 2- Asphalt.	59 Superstructure Condition:	6 - Satisfactory Condition	
High Water Elev:	0000.0	Year:1900		30.00	Type: 2- Asphalt.	* 227 Collision Damage:		
Flood Elev:	0000.0	Freq:00	Intersection Rear:	0	Fwd: 1	60A Substructure Condition:	5 - Fair Condition	
Avg Streambed Elev:	0000.0		36Safety Features Br. Rail:	2- Inspected feature meets acceptable construction date standards.		60B Scour Condition:	N - Not Applicable	
Drainage Area:	00000		Transition:	0- Does not meet standards		60C Underwater Condition	N - Not Applicable	
Area of Opening:	000000		App. G. Rail:	2- Inspected feature meets acceptable construction date standards.		71 Waterway Adequacy:	Not Applicable.	
113 Scour Critical	N. Bridge not over waterway.		App. Rail End:	0- Does not meet standards		61 Channel Protection Cond.:	10	
216 Water Depth:	00.0	Br.Height:00.0	53 Minimum Cl. Over:	99'99"		68 Deck Geometry:	3	
222 Slope Protection:	0		Under: H- Highway beneath structure.	17.00'6.00"		69 UnderClr. Horz/Vert:	4	
221Spur Dikes Rear	0	Fwd:0	*228 Minimum Vertical Cl			72 Appr. Alignment:	7-Between 8 and 6	
219 Fender System	0- None.		Act. Odm Dir:.	99 ' 99"		62 Culvert:	N - Not Applicable	
220 Dolphin:			Oppo. Dir:	99' 99"		Posting Data		
223 Culvert Cover:	000		Posted Odm. Dir:	00' 00"		70 Bridge Posting Required	5. Equal to or above legal loads	
Type:	0- Not Applicable		Oppo. Dir:	00'00 "		41 Struct Open, Posted, CL:	A. Open, no restriction	
No. Barrels:	0		55 Lateral Undercl. Rt:	H- Highway beneath structure.	8.00	* 103 Temporary Structure:	0	
Width:	0.00	Height:0	56 Lateral Undercl. Lt:	0.00		232 Posted Loads		
Length:	0	Apron:0	*10 Max Min Vert Cl:	99' 99" Dir:0		H-Modified:	00	
*265 U/W Insp. Area	0	Diver:ZZZ	39 Nav Vert Cl:	000 Horiz:0		HS-Modified:	00	
*Location ID No:	199-00085D-000.28N		116 Nav Vert Cl Closed:	000		Type 3:	00	
			245 Deck Thickness Main	7.00		Type 3s2:	00	
			Deck Thick Approach:	0.00		Timber:	00	
			246 Overlay Thickness:	4.00		Piggyback	00	
			212 Year Last Painted:	Sup:2000 Sub:0000		253 Notification Date:	02/01/1901	
						258 Fed Notify Date:	02/01/1901	

## Concept Team Meeting Notes (Roadway Design)

Concept Team Meeting held June 13, 2016

- There are conflicting bridge sufficiency ratings between the Project Justification Statement, Project Description and what is shown in the Major Structures table. Verify which is correct and make revisions as necessary.
- Verify all other projects within the area and revise the list if necessary.
- Projected traffic projects were performed by GDOT Planning as opposed to Traffic Operations.
- Revise the pavement evaluation section to indicate that a PTS is not required.
- Verify if the Bridge Design Features table is needed for the CR and remove if not needed.
- The PM should verify if project needs lighting and facilitate necessary coordination.
- Revise the need for TMP to state “yes,” but maintain the classification of non-significant.
- Revise context sensitive solutions section to “yes” as the bridge is within a historic district and is eligible.
- Additional utilities that should be listed are AT&T, Charter and City on Manchester Sewer.
- Revise “Party Responsible for Performing Tasks” table to include the contractor along with D3 construction for detours.
- Verify the right of way cost estimate and revise the reimbursable utilities estimate to \$100,000.
- Revise the estimated construction time for the preferred alternate to 12 months.
- Ensure that the utility and right of way cost estimates are added to the report upon receiving them.

Name	org	Ph. #	email
Todd Mathison	DOT ROW	706 646 7568	tmathison@dot.ga.gov
Samuel Summers	City of Manchester	706-741-5287	utilitydirector@Manchester-GA.Gov
Doug Westberry	CITY of Manchester	706 846-3141	manager@manchester-GA.Gov
Kevin Boatwright	THREE RIVERS RC	678-692-0570	kboatwright@threeriversga.gov
Danny Miller	GDOT Const.	706-845-4115	dmiller@dot.ga.gov
Dan Woods	D3-T.O.	706-646-7588	dwoods@dot.ga.gov
Adam Smith	GDOT Preconst.	706-621-9704	adsmith@dot.ga.gov
GENE MCKISSICK	CONSULTANT- GDOT D3 UTILITY	706-646-7604	gmckissick@dot.ga.gov



SIGN-IN SHEET

0007044 MERWETHER

<u>NAME</u>	<u>PHONE</u>	<u>EMAIL</u>
JUSTIN BANKS	404-631-1153	jbanks@dot.ga.gov
Kim Phillips	404-631-1775	Kiphillips@dot.ga.gov
Ryan Perry	404-631-1271	vperry@dot.ga.gov
Amber Rhea	404-631-1084	arhea@dot.ga.gov
Rachel Perrine	404-631-1072	rperrine@dot.ga.gov
Michelle Lewis	404-631-1185	miclewis@dot.ga.gov
Hannah Held	404-631-1095	hheld@dot.ga.gov
Erik Rohde	404 631 1611	erohde@dot.ga.gov
Josh Taylor	404-631-1659	jotaylor@dot.ga.gov
Lily Manavi	404-631-1676	lmanavi@dot.ga.gov